



RECEIVED

SEP 03 2004

DIV. OF OIL, GAS &amp; MINING

September 2, 2004

State of Utah  
Division of Oil, Gas & Mining  
Attn: Diana Whitney  
1594 West North Temple - Suite 1210  
P.O. Box 145801  
Salt Lake City, Utah 84114-5801

RE: Applications for Permit to Drill: Ashley Federal 14-13-9-15, 16-13-9-15,  
14-14-9-15, and 16-14-9-15.

Dear Diana:

Enclosed find APD's on the above referenced wells. The 8-13-9-16 and 13-13-9-16 are Exception Locations. I have contacted our Land Department in the Denver office and they will be providing you with the appropriate Exception Location Letters. If you have any questions, feel free to give either Brad or myself a call.

Sincerely,

Lana Nebeker  
Production Clerk

enclosures

Form 3160-3  
(September 2001)UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

## APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED  
OMB No. 1004-0136  
Expires January 31, 20045. Lease Serial No.  
UTU-685486. If Indian, Allottee or Tribe Name  
N/A7. If Unit or CA Agreement, Name and No.  
Ashley8. Lease Name and Well No.  
Ashley Federal 14-13-9-159. API Well No. **43-013-3 2669**10. Field and Pool, or Exploratory  
Monument Butte11. Sec., T., R., M., or Blk. and Survey or Area  
SE/SW Sec. 13, T9S R15E12. County or Parish  
Duchesne13. State  
UT1a. Type of Work: ☒ DRILL ☐ REENTER1b. Type of Well: ☒ Oil Well ☐ Gas Well ☐ Other ☒ Single Zone ☐ Multiple Zone2. Name of Operator  
Inland Production Company3a. Address  
Route #3 Box 3630, Myton UT 840523b. Phone No. (include area code)  
(435) 646-37214. Location of Well (Report location clearly and in accordance with any State requirements. \*)  
At surface SE/SW 758' FSL 2020' FWL **569793X 40.02572**  
At proposed prod. zone **4430722Y -110.18209**14. Distance in miles and direction from nearest town or post office\*  
Approximatley 17.0 miles southwest of Myton, Utah15. Distance from proposed\*  
location to nearest  
property or lease line, ft.  
(Also to nearest drig. unit line, if any) Approx. 562' flse, 3260' f/unit16. No. of Acres in lease  
711.2217. Spacing Unit dedicated to this well  
40 Acres18. Distance from proposed location\*  
to nearest well, drilling, completed,  
applied for, on this lease, ft. Approx. 2,737'19. Proposed Depth  
6500'20. BLM/BIA Bond No. on file  
UTU005621. Elevations (Show whether DF, KDB, RT, GL, etc.)  
6158.3' GL22. Approximate date work will start\*  
1st Quarter 200523. Estimated duration  
Approximately seven (7) days from spud to rig release.


## 24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, shall be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).

- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification.
- Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature

Name (Printed/Typed)  
Lana NebekerDate **9-2-04**

Approved by (Signature)

Name (Printed/Typed)

Date

Title



Office

Application approval does not warrant or certify the the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

\*(Instructions on reverse)

APPROVED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING  
DATE: **9-14-04**  
BY: Federal Approval of this  
Action is Necessary


# T9S, R15E, S.L.B.&M.

S89°55'W - 80.16 (G.L.O.)

2651.57' (Measured)

S89°55'W G.L.O. (Basis of Bearings)

S89°52'54"W - 2648.87' (Meas.)



**WELL LOCATION:  
ASHLEY UNIT #14-13**

ELEV. UNGRADED GROUND = 6158.3'

**13**

DRILLING  
WINDOW

2020'

200'

Corner Reestablished  
Proportionately  
(Not Set)

1910  
Brass Cap

Corner Reestablished  
Proportionately  
(Not Set)

S89°49'34"W - 5288.25' (Meas.)



S89°56'W - 80.12 (G.L.O.)

◆ = SECTION CORNERS LOCATED


BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (MYTON SW)

## INLAND PRODUCTION COMPANY

WELL LOCATION, ASHLEY UNIT #14-13,  
LOCATED AS SHOWN IN THE SE 1/4 SW  
1/4 OF SECTION 13, T9S, R15E,  
S.L.B.&M. DUCHESNE COUNTY, UTAH.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS  
PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS  
MADE BY ME OR UNDER MY SUPERVISION AND THAT  
THE SAME ARE TRUE AND CORRECT TO THE BEST OF  
MY KNOWLEDGE AND BELIEF. No.189377



## TRI STATE LAND SURVEYING & CONSULTING

38 WEST 100 NORTH - VERNAL, UTAH 84078

(435) 781-2501

SCALE: 1" = 1000'

SURVEYED BY: D.J.S.

DATE: 8-18-04

DRAWN BY: F.T.M.

NOTES:

FILE #

INLAND PRODUCTION COMPANY  
ASHLEY 14-13-9-15  
SE/SW SECTION 13, T9S, R15E  
DUCHESNE COUNTY, UTAH

ONSHORE ORDER NO. 1

DRILLING PROGRAM

1. GEOLOGIC SURFACE FORMATION:

Uinta formation of Upper Eocene Age

2. ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:

Uinta	0' – 1640'
Green River	1640'
Wasatch	6030'

3. ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:

Green River Formation 1640' – 6500' - Oil

4. PROPOSED CASING PROGRAM

Please refer to the Monument Butte Field Standard Operation Procedure (SOP).

5. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

Please refer to the Monument Butte Field SOP. See Exhibit "C".

6. TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:

Please refer to the Monument Butte Field SOP.

7. AUXILIARY SAFETY EQUIPMENT TO BE USED:

Please refer to the Monument Butte Field SOP.

8. TESTING, LOGGING AND CORING PROGRAMS:

Please refer to the Monument Butte Field SOP.

9. ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:

The anticipated maximum bottom hole pressure is 2000 psi. It is not anticipated that abnormal temperatures will be encountered.

10. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:

Please refer to the Monument Butte Field SOP.



INLAND PRODUCTION COMPANY  
ASHLEY FEDERAL #14-13-9-15  
SE/SW SECTION 13, T9S, R15E  
DUCHESNE COUNTY, UTAH

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. EXISTING ROADS

See attached Topographic Map "A"

To reach Inland Production Company well location site Ashley Federal #14-13-9-15 located in the SE 1/4 SW 1/4 Section 13, T9S, R15E, Duchesne County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40 - 1.6 miles  $\pm$  to the junction of this highway and UT State Hwy 53; proceed southwesterly along Hwy 53 - 11.3 miles  $\pm$  to it's junction with an existing dirt road to the northwest; proceed 3.1 miles  $\pm$  to it's junction with an existing road to the east; proceed easterly .1.0 miles  $\pm$  to it's junction with the beginning of the proposed access road; proceed southeasterly along the proposed access road - 405'  $\pm$  to the proposed well location.

2. PLANNED ACCESS ROAD

See Topographic Map "B" for the location of the proposed access road.

3. LOCATION OF EXISTING WELLS

Refer to Exhibit "B".

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

Please refer to the Monument Butte Field Standard Operating Procedure (SOP).

5. LOCATION AND TYPE OF WATER SUPPLY

Please refer to the Monument Butte Field SOP. See Exhibit "A".

6. SOURCE OF CONSTRUCTION MATERIALS

Please refer to the Monument Butte Field SOP.

7. METHODS FOR HANDLING WASTE DISPOSAL

Please refer to the Monument Butte Field SOP.

8. ANCILLARY FACILITIES

Please refer to the Monument Butte Field SOP.

9. **WELL SITE LAYOUT**

See attached Location Layout Diagram.

10. **PLANS FOR RESTORATION OF SURFACE**

Please refer to the Monument Butte Field SOP.

11. **SURFACE OWNERSHIP** - Bureau Of Land Management

12. **OTHER ADDITIONAL INFORMATION**

The Archaeological Resource Survey and Paleontological Resource Survey for this area are attached. MOAC Report #01-163,05/23/02. Paleontological Resource Survey prepared by, Wade E. Miller, 6/7/03. See attached report cover pages, Exhibit "D".

For the Ashley Federal #14-13-9-15 Inland Production Company requests 405' of disturbed area be granted in the Ashley Unit to allow for construction of the proposed access road. **Refer to Topographic Map "B"**. The proposed access road will be an 18' crown road (9' either side of the centerline) with drainage ditches along either side of the proposed road whether it is deemed necessary in order to handle any run-off from normal meteorological conditions that are prevalent to this area. The maximum grade will be less than 8%. There will be no culverts required along this access road. There will be barrow ditches and turnouts as needed along this road. There are no fences encountered along this proposed road. There will be no new gates or cattle guards required. All construction material for this access road will be borrowed material accumulated during construction of the access road.

Inland Production Company requests 405' of disturbed area be granted in the Ashley Unit to allow for construction of the proposed gas lines. It is proposed that the disturbed area will be 50' wide to allow for construction of a 2" gas gathering line, and a 2" poly fuel gas line. Both lines will tie in to the existing pipeline infrastructure. **Refer to Topographic Map "C."** For a ROW plan of development, please refer to the Monument Butte Field SOP.

**Water Disposal**

Immediately upon first production, all produced water will be confined to a steel storage tank. If the production water meets quality guidelines, it is transported to the Ashley, Monument Butte, Jonah, and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Inland's secondary recovery project.

Water not meeting quality criteria, is disposed at Inland's Pariette #4 disposal well (Sec. 7, T9S R19E) or at State of Utah approved surface disposal facilities.

**Threatened, Endangered, And Other Sensitive Species**

**Sage Grouse:**

No new construction or surface disturbance within a 2 mile radius of strutting grounds March 1 – June 30.

**Reserve Pit Liner**

A 12 mil liner with felt is required if fractured rock is encountered. Please refer to the Monument Butte Field SOP.

**Muffler**

To reduce noise levels in the area, a hospital muffler or multi-cylinder engine shall be installed on the pumping unit.

### Location and Reserve Pit Reclamation

Please refer to the Monument Butte Field SOP.

The following seed mixture will be used on the topsoil stockpile, to the recontoured surface of the reserve pit, and for final reclamation: (All poundages are in pure live seed)

Black Sage	<i>Artemisia Nova</i>	1 lbs/acre
Indian Rice Grass	<i>Oryzopsis Hymenoides</i>	6 lbs/acre
Beardless Blue Bunch Wheat Grass	<i>Agropyron Spicatum</i>	5 lbs/acre

### Details of the On-Site Inspection

The proposed Ashley Federal #14-13-9-15 was on-sited on 4/15/04. The following were present; Brad Mecham (Inland Production), David Gerbig (Inland Production), Byron Tolman (Bureau of Land Management), and a SWCA representative. Weather conditions were clear.

### 13. LESSEE'S OR OPERATORS REPRESENTATIVE AND CERTIFICATION

#### Representative

Name: Brad Mecham  
Address: Route #3 Box 3630  
Myton, UT 84052  
Telephone: (435) 646-3721


#### Certification

Please be advised that INLAND PRODUCTION COMPANY is considered to be the operator of well #14-13-9-15 SE/SW Section 13, Township 9S, Range 15E: Ashley Unit; Duchesne County, Utah: and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by Hartford Accident #4488944.

I hereby certify that the proposed drillsite and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Inland Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

9-2-04


Date

  
Lana Nebeker  
Production Clerk

# INLAND PRODUCTION COMPANY

## ASHLEY UNIT 14-13

Section 13, T9S, R15E, S.L.B.&M.



### REFERENCE POINTS

210' EAST = 6152.3'

260' EAST = 6149.9'

SURVEYED BY: D.J.S.

SCALE: 1" = 50'

DRAWN BY: F.T.M.





DATE: 8-18-04

**Tri State**  
Land Surveying, Inc.

(435) 781-2501

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

**INLAND PRODUCTION COMPANY**  
**CROSS SECTIONS**  
**ASHLEY UNIT 14-13**



NOTE:  
UNLESS OTHERWISE NOTED  
ALL CUT/FILL SLOPES ARE  
AT 1.5:1

**ESTIMATED EARTHWORK QUANTITIES**  
(No Shrink or swell adjustments have been used)  
(Expressed in Cubic Yards)

ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	2,260	2,260	Topsoil is not included in Pad Cut	0
PIT	640	0		640
TOTALS	2,900	2,260	890	640

SURVEYED BY: D.J.S.

SCALE: 1" = 50'


DRAWN BY: F.T.M.

DATE: 8-18-04

**Tri State**  
**Land Surveying, Inc.**  
(435) 781-2501  
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

TYPICAL RIG LAYOUT  
ASHLEY UNIT 14-13

PROPOSED ACCESS  
ROAD (Max. 6% Grade)




SURVEYED BY: D.J.S.

SCALE:  $1'' = 50'$

DRAWN BY: F.T.M.

DATE: 8-18-04

**Tri State** (435) 781-2501  
Land Surveying, Inc.  
180 NORTH VERNAL AVE. VERNAL, UTAH 84078



**Ashley Unit 14-13**  
**SEC. 13, T9S, R15E, S.L.B.&M.**



**Tri-State**  
**Land Surveying Inc.**  
 (435) 781-2501  
 180 North Vernal Ave. Vernal, Utah 84078

**SCALE: 1 = 100,000**  
**DRAWN BY: bgm**  
**DATE: 08-18-2004**

**Legend**


- Existing Road
- Proposed Access

**TOPOGRAPHIC MAP**

**"A"**







**Ashley Unit 14-13**  
**SEC. 13, T9S, R15E, S.L.B.&M.**



**Tri-State**  
*Land Surveying Inc.*  
 (435) 781-2501  
 180 North Vernal Ave. Vernal, Utah 84078


**SCALE: 1" = 2,000'**  
**DRAWN BY: bgm**  
**DATE: 08-18-2004**

**Legend**

- Roads
- Existing Gas Line
- Proposed Gas Line

**TOPOGRAPHIC MAP**

**"C"**





UTU-74826

UTU-74

UTU-66184

UTU-64379

U-02458

98/16E

Proposed Location  
Well Pad 14-13



Ashley Unit 14-13  
SEC. 13, T9S, R15E, S.L.B.&M.



**Tri-State**  
Land Surveying Inc.  
(435) 781-2501  
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'  
DRAWN BY: bgm  
DATE: 08-18-2004

Legend

- Well Locations
- One-Mile Radius

Exhibit "B"

# 2-M SYSTEM

Blowout Prevention Equipment Systems




EXHIBIT C

CULTURAL RESOURCE INVENTORY OF  
INLAND RESOURCES' 1750 ACRE ASHLEY UNIT, IN  
TOWNSHIP 9S, RANGE 15E, SECTIONS 13, 14, AND 15,  
DUCHESNE COUNTY, UTAH

Anne Raney  
and  
Keith Montgomery

Prepared For:

Bureau of Land Management  
Vernal Field Office  
Vernal, Utah

Prepared Under Contract With:

Jon D. Holst & Associates  
for  
Inland Resources  
2507 Flintridge Place  
Fort Collins, CO 80521

Prepared By:


Montgomery Archaeological Consultants  
P.O. Box 147  
Moab, Utah 84532

MOAC Report No. 01-163

May 23, 2002

United States Department of Interior (FLPMA)  
Permit No. 02-UT-60122

State of Utah Antiquities Project (Survey)  
Permit No. U-02-MQ-0235b



**INLAND RESOURCES, INC.**

**PALEONTOLOGICAL FIELD SURVEY OF PROPOSED  
PRODUCTION DEVELOPMENT AREAS,  
DUCHESNE COUNTY, UTAH**

(South half Section 13, south half Section 14, south half Section 15,  
entire Sections 22, 23, 24, T 9 S, R 15 E; Section 5 minus SW &  
SE 1/4, SE 1/4, and existing well site at NW 1/4, NE 1/4, T 9 S, R 18 E)

**REPORT OF SURVEY**


Prepared for:

**Inland Resources, Inc.**

Prepared by:

Wade E. Miller  
Consulting Paleontologist  
June 7, 2003







**WORKSHEET**  
**APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 09/03/2004

API NO. ASSIGNED: 43-013-32669

WELL NAME: ASHLEY FED 14-13-9-15OPERATOR: INLAND PRODUCTION ( N5160 )CONTACT: LANA NEBEKERPHONE NUMBER: 435-646-3721

## PROPOSED LOCATION:

SESW 13 090S 150E

SURFACE: 0758 FSL 2020 FWL

BOTTOM: 0758 FSL 2020 FWL

DUCHESNE

MONUMENT BUTTE ( 105 )

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU-68548

SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: GRRV

COALBED METHANE WELL? NO

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LATITUDE: 40.02572

LONGITUDE: -110.1821

## RECEIVED AND/OR REVIEWED:

- ☒ Plat
- ☒ Bond: Fed[1] Ind[] Sta[] Fee[]  
 (No. UTU0056 )
- ☒ Potash (Y/N)
- ☒ Oil Shale 190-5 (B) or 190-3 or 190-13
- ☒ Water Permit  
 (No. MUNICIPAL )
- ☒ RDCC Review (Y/N)  
 (Date: \_\_\_\_\_ )
- ☒ Fee Surf Agreement (Y/N)

## LOCATION AND SITING:

\_\_\_ R649-2-3.

Unit ASHLEY

\_\_\_ R649-3-2. General

Siting: 460 From Qtr/Qtr & 920' Between Wells

\_\_\_ R649-3-3. Exception

☒ Drilling UnitBoard Cause No: 242-1Eff Date: 8-25-1998Siting: Suspends General Siting


\_\_\_ R649-3-11. Directional Drill

## COMMENTS:

Cop, Separate Files

## STIPULATIONS:

1- Federal Approval




OPERATOR: INLAND PROD CO (N5160)

SEC. 13 T.9S R.15E

FIELD: MONUMENT BUTTE (105)

COUNTY: DUCHESNE

CAUSE: 242-1 / 8-25-1998



Utah Oil Gas and Mining

Wells	Units.shp	Fields.shp
⊕ GAS INJECTION	□ EXPLORATORY	⬜ ABANDONED
⊕ GAS STORAGE	□ GAS STORAGE	⬜ ACTIVE
⊗ LOCATION ABANDONED	□ NF PP OIL	⬜ COMBINED
⊕ NEW LOCATION	□ NF SECONDARY	⬜ INACTIVE
⊕ PLUGGED & ABANDONED	□ PENDING	⬜ PROPOSED
⊕ PRODUCING GAS	□ PI OIL	⬜ STORAGE
⊕ PRODUCING OIL	□ PP GAS	⬜ TERMINATED
⊕ SHUT-IN GAS	□ PP GEOTHERML	
⊕ SHUT-IN OIL	□ PP OIL	
⊕ TEMP. ABANDONED	□ SECONDARY	
⊕ TEST WELL	□ TERMINATED	
⊕ WATER INJECTION		
⊕ WATER SUPPLY		
⊕ WATER DISPOSAL		



PREPARED BY: DIANA WHITNEY  
DATE: 10-SEPTEMBER-2004

## United States Department of the Interior

## BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, Utah 84145-0155

## IN REPLY REFER TO:

3160

(UT-922)

September 10, 2004

## Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2004 Plan of Development Ashley Unit,  
Duchesne County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2004 within the Ashley Unit, Duchesne County, Utah.

API #	WELL NAME	LOCATION
-------	-----------	----------

(Proposed PZ Green River)

43-013-32668	Ashley Federal 16-13-9-15 Sec 13 T09S R15E 0682 FSL 0523 FEL	
43-013-32669	Ashley Federal 14-13-9-15 Sec 13 T09S R15E 0758 FSL 2020 FWL	
43-013-32670	Ashley Federal 14-14-9-15 Sec 14 T09S R15E 0483 FSL 1990 FWL	
43-013-32667	Ashley Federal 16-14-9-15 Sec 14 T09S R15E 0620 FSL 0645 FEL	

This office has no objection to permitting the wells at this time.

/s/ Michael L. Coulthard

bcc: File - Ashley Unit  
Division of Oil Gas and Mining  
Central Files  
Agr. Sec. Chron  
Fluid Chron

MCoulthard:mc:9-10-04



State of Utah

Department of  
Natural Resources

ROBERT L. MORGAN  
*Executive Director*

Division of  
Oil, Gas & Mining

LOWELL P. BRAXTON  
*Division Director*

OLENE S. WALKER  
*Governor*

GAYLE F. McKEACHNIE  
*Lieutenant Governor*

September 14, 2004

Inland Production Company  
Rt. #3, Box 3630  
Myton, UT 84052

Re: Ashley Federal 14-13-9-15 Well, 758' FSL, 2020' FWL, SE SW, Sec. 13,  
T. 9 South, R. 15 East, Duchesne County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-013-32669.

Sincerely,

A handwritten signature in black ink, appearing to read "John R. Baza".

John R. Baza  
Associate Director

pab  
Enclosures

cc: Duchesne County Assessor  
Bureau of Land Management, Vernal District Office

Operator: Inland Production Company

Well Name & Number Ashley Federal 14-13-9-15

API Number: 43-013-32669

Lease: UTU-68548

Location: SE SW                      Sec. 13                      T. 9 South                      R. 15 East

### Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.



# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, UT 84145-0155

<http://www.blm.gov>



IN REPLY REFER TO:  
3106  
(UT-924)

September 16, 2004

### Memorandum

To: Vernal Field Office

From: Acting Chief, Branch of Fluid Minerals

Subject: Merger Approval

Attached is an approved copy of the name change recognized by the Utah State Office. We have updated our records to reflect the merger from Inland Production Company into Newfield Production Company on September 2, 2004.

Michael Coulthard  
Acting Chief, Branch of  
Fluid Minerals

### Enclosure

1. State of Texas Certificate of Registration

cc: MMS, Reference Data Branch, James Sykes, PO Box 25165, Denver CO 80225  
State of Utah, DOGM, Attn: Earlene Russell, PO Box 145801, SLC UT 84114  
Teresa Thompson  
Joe Incardine  
Connie Seare

UTSL-	15855	61052	73088	76561	
071572A	16535	62848	73089	76787	
065914	16539	63073B	73520A	76808	
	16544	63073D	74108	76813	
	17036	63073E	74805	76954	63073X
	17424	63073O	74806	76956	63098A
	18048	64917	74807	77233	68528A
UTU-	18399	64379	74808	77234	72086A
	19267	64380	74389	77235	72613A
02458	26026A	64381	74390	77337	73520X
03563	30096	64805	74391	77338	74477X
03563A	30103	64806	74392	77339	75023X
04493	31260	64917	74393	77357	76189X
05843	33992	65207	74398	77359	76331X
07978	34173	65210	74399	77365	76788X
09803	34346	65635	74400	77369	77098X
017439B	36442	65967	74404	77370	77107X
017985	36846	65969	74405	77546	77236X
017991	38411	65970	74406	77553	77376X
017992	38428	66184	74411	77554	78560X
018073	38429	66185	74805	78022	79485X
019222	38431	66191	74806	79013	79641X
020252	39713	67168	74826	79014	80207X
020252A	39714	67170	74827	79015	81307X
020254	40026	67208	74835	79016	
020255	40652	67549	74868	79017	
020309D	40894	67586	74869	79831	
022684A	41377	67845	74870	79832	
027345	44210	68105	74872	79833	
034217A	44426	68548	74970	79831	
035521	44430	68618	75036	79834	
035521A	45431	69060	75037	80450	
038797	47171	69061	75038	80915	
058149	49092	69744	75039	81000	
063597A	49430	70821	75075		
075174	49950	72103	75078		
096547	50376	72104	75089		
096550	50385	72105	75090		
	50376	72106	75234		
	50750	72107	75238		
10760	51081	72108	76239		
11385	52013	73086	76240		
13905	52018	73087	76241		
15392	58546	73807	76560		

Corporations Section  
P.O.Box 13697  
Austin, Texas 78711-3697



Geoffrey S. Connor  
Secretary of State

## Office of the Secretary of State

The undersigned, as Secretary of State of Texas, does hereby certify that the attached is a true and correct copy of each document on file in this office as described below:

Newfield Production Company  
Filing Number: 41530400

Articles of Amendment

September 02, 2004

In testimony whereof, I have hereunto signed my name officially and caused to be impressed hereon the Seal of State at my office in Austin, Texas on September 10, 2004.



A handwritten signature in black ink, appearing to read "G. Connor".

Secretary of State



ARTICLES OF AMENDMENT  
TO THE  
ARTICLES OF INCORPORATION  
OF  
INLAND PRODUCTION COMPANY

FILED  
In the Office of the  
Secretary of State of Texas

SEP 02 2004  
Corporations Section

Pursuant to the provisions of Article 4.04 of the Texas Business Corporation Act (the "TBCA"), the undersigned corporation adopts the following articles of amendment to the articles of incorporation:

ARTICLE 1 – Name

The name of the corporation is Inland Production Company.

ARTICLE 2 – Amended Name

The following amendment to the Articles of Incorporation was approved by the Board of Directors and adopted by the shareholders of the corporation on August 27, 2004.

The amendment alters or changes Article One of the Articles of Incorporation to change the name of the corporation so that, as amended, Article One shall read in its entirety as follows:

"ARTICLE ONE – The name of the corporation is Newfield Production Company."

ARTICLE 3 – Effective Date of Filing

This document will become effective upon filing.

The holder of all of the shares outstanding and entitled to vote on said amendment has signed a consent in writing pursuant to Article 9.10 of the TBCA, adopting said amendment, and any written notice required has been given.

IN WITNESS WHEREOF, the undersigned corporation has executed these Articles of Amendment as of the 1<sup>st</sup> day of September, 2004.

INLAND RESOURCES INC.

By: Susan G. Riggs  
Susan G. Riggs, Treasurer



6a. (R649-9-2)Waste Management Plan has been received on: IN PLACE  
6b. Inspections of LA PA state/fee well sites complete on: waived

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM BIA

8. **Federal and Indian Units:**  
The BLM or BIA has approved the successor of unit operator for wells listed on: n/a

9. **Federal and Indian Communization Agreements ("CA"):**  
The BLM or BIA has approved the operator for all wells listed within a CA on: na/

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 2/23/2005

**DATA ENTRY:**

1. Changes entered in the **Oil and Gas Database** on: 2/28/2005  
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 2/28/2005  
3. Bond information entered in RBDMS on: 2/28/2005  
4. Fee/State wells attached to bond in RBDMS on: 2/28/2005  
5. Injection Projects to new operator in RBDMS on: 2/28/2005  
6. Receipt of Acceptance of Drilling Procedures for APD/New on: waived

**FEDERAL WELL(S) BOND VERIFICATION:**

1. Federal well(s) covered by Bond Number: UT 0056

**INDIAN WELL(S) BOND VERIFICATION:**

1. Indian well(s) covered by Bond Number: 61BSBDH2912

**FEE & STATE WELL(S) BOND VERIFICATION:**

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number 61BSBDH2919  
2. The **FORMER** operator has requested a release of liability from their bond on: n/a\*  
The Division sent response by letter on: n/a

**LEASE INTEREST OWNER NOTIFICATION:**

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a


**COMMENTS:**

\*Bond rider changed operator name from Inland Production Company to Newfield Production Company - received 2/23/05

RECEIVED

JUN 03 2005

DIV. OF OIL, GAS &amp; MINING

Form 3160-3  
(September 2001)UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

## APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED  
OMB No. 1004-0136  
Expires January 31, 20045. Lease Serial No.  
UTU-68548  
6. If Indian, Allottee or Tribe Name  
N/A7. If Unit or CA Agreement, Name and No.  
Ashley8. Lease Name and Well No.  
Ashley Federal 14-13-9-159. API Well No.  
43-013-32166910. Field and Pool, or Exploratory  
Monument Butte11. Sec., T., R., M., or Blk. and Survey or Area  
SE/SW Sec. 13, T9S R15E12. County or Parish  
Duchesne  
13. State  
UT1a. Type of Work: ☒ DRILL ☐ REENTER1b. Type of Well: ☒ Oil Well ☐ Gas Well ☐ Other ☒ Single Zone ☐ Multiple Zone2. Name of Operator  
Newfield Production Company3a. Address  
Route #3 Box 3630, Myton UT 840523b. Phone No. (include area code)  
(435) 646-3721

4. Location of Well (Report location clearly and in accordance with any State requirements. \*)

At surface SE/SW 758' FSL 2020' FWL

At proposed prod. zone

14. Distance in miles and direction from nearest town or post office\*  
Approximatley 17.0 miles southwest of Myton, Utah15. Distance from proposed\*  
location to nearest  
property or lease line, ft.  
(Also to nearest drig. unit line, if any) Approx. 562' f/lse, 3260' f/unit16. No. of Acres in lease  
711.2217. Spacing Unit dedicated to this well  
40 Acres18. Distance from proposed location\*  
to nearest well, drilling, completed,  
applied for, on this lease, ft. Approx. 2,737'19. Proposed Depth  
6500'20. BLM/BIA Bond No. on file  
UTV005621. Elevations (Show whether DF, KDB, RT, GL, etc.)  
6158.3' GL22. Approximate date work will start\*  
1st Quarter 200523. Estimated duration  
Approximately seven (7) days from spud to rig release.

## 24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, shall be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification.
- Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature

Name (Printed/Typed)

Date

Lana Nebeker

9-2-04

Title  
Production Clerk

Approved by (Signature)

Name (Printed/Typed)

Date

Office

05/14/2005

Title Assistant  
Mineral Resource

Application approval does not warrant or certify the the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

\*(Instructions on reverse)

NOTICE OF APPROVAL

CONDITIONS OF APPROVAL ATTACHED

CONDITIONS OF APPROVAL  
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Inland Production Company  
Well Name & Number: ASHLEY FEDERAL 14-13-9-15  
API Number: 43-013-32669  
Lease Number: UTU - 68548  
Location: SESW Sec. 13 TWN: 09S RNG: 15E  
Agreement: N/A

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

**Submit an electronic copy of all logs run on this well in LAS format. This submission will replace the requirement for submittal of paper logs to the BLM.**

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Casing Program and Auxiliary Equipment

As a minimum, the usable water and oil shale resources shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the top of the Green River Formation, identified at  $\pm 1,460$  ft.

**CONDITIONS OF APPROVAL**  
**FOR THE SURFACE USE PROGRAM OF THE**  
**APPLICATION FOR PERMIT TO DRILL**

Company/Operator: Newfield Production Company

API Number: 43-013-32669

Well Name & Number: Federal 14-13-9-15

Lease Number: U-66184

Location: SESW Sec. 13 T. 9 S. R. 15 E.

Surface Ownership: BLM

Date NOS Received: None

Date APD Received: 9-3-04

-None. All required stipulations are included in the APD.

## DIVISION OF OIL, GAS AND MINING

### **SPUDDING INFORMATION**

Name of Company: NEWFIELD PRODUCTION COMPANY

Well Name: ASHLEY FED 14-13-9-15

Api No: 43-013-32669 Lease Type: FEDERAL

Section 13 Township 09S Range 15E County DUCHESNE

Drilling Contractor ROSS DRILLING RIG # 24

### **SPUDDED:**

Date 07/27/05

Time 10:00 AM

How DRY

**Drilling will Commence:** \_\_\_\_\_

Reported by TROY

Telephone # 1-435-823-6013

Date 07/28/05 Signed CHD



RECEIVED

JUL 28 2005

STATE OF UTAH  
DIVISION OF OIL, GAS AND MINING  
ENTITY ACTION FORM - FORM 6

DIV. OF OIL, GAS &amp; MINING

OPERATOR: NEWFIELD PRODUCTION COMPANY  
ADDRESS: RT. 3 BOX 3630  
MYTON, UT 84052

OPERATOR ACCT. NO. N2695

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QZ	SC	TP	RG	COUNTY		
A	99999	12419	43-013-32646	Ashley Federal 4-24-9-15	NW/WW	24	9S	15E	Duchesne	7/20/2005	7/28/05
WELL 1 COMMENTS: <i>GRW</i>											
A	99999	12419	43-013-32669	Ashley Federal 14-13-9-15	SE/SW	13	9S	15E	Duchesne	7/27/2005	7/28/05
WELL 2 COMMENTS: <i>GRW</i>											
WELL 3 COMMENTS:											
WELL 4 COMMENTS:											
WELL 5 COMMENTS:											

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- E - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected

*Kebbie S. Jones*  
Signature  
Kebbie S. Jones  
Production Clerk  
Title  
July 28, 2005  
Date

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB No. 1004-0135  
Expires January 31, 2004

**SUNDRY NOTICES AND REPORTS ON WELLS**  
Do not use this form for proposals to drill or to re-enter an  
abandoned well. Use Form 3160-3 (APD) for such proposals.

**SUBMIT IN TRIPLICATE - Other Instructions on reverse side**

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Newfield Production Company

3a. Address Route 3 Box 3630

Myton, UT 84052

3b. Phone No. (include area code)

435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

758 FSL 2020 FWL

SE/SW Section 13 T9S R15E

5. Lease Serial No.

UTU68548

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or No.

ASHLEY PA A

8. Well Name and No.

ASHLEY FEDERAL 14-13-9-15

9. API Well No.

4301332669

10. Field and Pool, or Exploratory Area  
Monument Butte

11. County or Parish, State

Duchesne, UT

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production(Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug & Abandon	<input type="checkbox"/> Temporarily Abandon	Spud Notice _____
	<input type="checkbox"/> Convert to Injector	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	_____

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

On 7/27/2005 MIRU Ross Rig # 24. Spud well @ 10:00 AM. Drill 302' of 12 1/4" hole with air mist. TIH W/ 7 Jt's 8 5/8" J-55 24 # csgn. Set @ 314.20' KB On 8/21/2005 cement with 160 sks of class "G" w/ 3% CaCL2 + 1/4# sk Cello- Flake Mixed @ 15.8 ppg > 1.17 cf/ sk yeild. Returned 4 bbls cement to pit. WOC.

I hereby certify that the foregoing is true and correct

Name (Printed/ Typed)  
Floyd Mitchell

Title

Drilling Supervisor

Signature

*Floyd Mitchell*

Date

08/22/2005

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by \_\_\_\_\_

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)

**AUG 23 2005**

DIV. OF OIL, GAS & MINING

# NEWFIELD PRODUCTION COMPANY - CASING & CEMENT REPORT

8 5/8 CASING SET AT 314.2

LAST CASING 8 5/8" SET AT 314.2'  
 DATUM 12. KB  
 DATUM TO CUT OFF CASING \_\_\_\_\_  
 DATUM TO BRADENHEAD FLANGE \_\_\_\_\_  
 TD DRILLER 302' LOGGER \_\_\_\_\_  
 HOLE SIZE 12 1/4

OPERATOR Newfield Production Company  
 WELL Ashley Fed 14-13-9-15  
 FIELD/PROSPECT Monument Butte  
 CONTRACTOR & RIG # Ross Rig # 24

## LOG OF CASING STRING:

PIECES	OD	ITEM - MAKE - DESCRIPTION	WT / FT	GRD	THREAD	CONDT	LENGTH	
		42.70 sh jt' shjt						
		WHI - 92 csg head			8rd	A	0.95	
7	8 5/8"	Maverick ST&C csg	24#	J-55	8rd	A	302.35	
		GUIDE shoe			8rd	A	0.9	
CASING INVENTORY BAL.		FEET	JTS	TOTAL LENGTH OF STRING				304.2
TOTAL LENGTH OF STRING		304.2	7	LESS CUT OFF PIECE				2
LESS NON CSG. ITEMS		1.85		PLUS DATUM TO T/CUT OFF CSG				12
PLUS FULL JTS. LEFT OUT		0		CASING SET DEPTH				314.2

BEGIN RUN CSG.	SPUD	7/27/2005	10:00 AM	GOOD CIRC THRU JOB	Yes
CSG. IN HOLE		7/29/2005	12:00 PM	Bbls CMT CIRC TO SURFACE	4
BEGIN CIRC		8/21/2005	2:00 PM	RECIPROCATED PIPE FOR	THRU FT STROKE
BEGIN PUMP CMT		8/21/2005	2:15 PM	DID BACK PRES. VALVE HOLD ?	N/A
BEGIN DSPL. CMT		8/21/2005	2:28 PM	BUMPED PLUG TO	930 PSI
PLUG DOWN		8/21/2005	2:32 PM		

CEMENT USED		CEMENT COMPANY- B. J.	
STAGE	# SX	CEMENT TYPE & ADDITIVES	
1	160	Class "G" w/ 2% CaCL2 + 1/4#/sk Cello-Flake mixed @ 15.8 ppg 1.17 cf/sk yield	
CENTRALIZER & SCRATCHER PLACEMENT		SHOW MAKE & SPACING	
Centralizers - Middle first, top second & third for 3			

COMPANY REPRESENTATIVE Floyd Mitchell DATE 8/22/2005

RECEIVED

AUG 23 2005

DIV. OF OIL, GAS & MINING

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB No. 1004-0135  
Expires January 31, 2004

**SUNDRY NOTICES AND REPORTS ON WELLS**  
Do not use this form for proposals to drill or to re-enter an  
abandoned well. Use Form 3160-3 (APD) for such proposals.

**SUBMIT IN TRIPLICATE - Other Instructions on reverse side**

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Newfield Production Company

3a. Address Route 3 Box 3630

Myton, UT 84052

3b. Phone No. (include area code)

435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

758 FSL 2020 FWL

SE/SW Section 13 T9S R15E

5. Lease Serial No.

UTU68548

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or No.

ASHLEY PA A

8. Well Name and No.

ASHLEY FEDERAL 14-13-9-15

9. API Well No.

4301332669

10. Field and Pool, or Exploratory Area  
Monument Butte

11. County or Parish, State

Duchesne, UT

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug & Abandon	<input type="checkbox"/> Temporarily Abandon	Weekly Status Report
	<input type="checkbox"/> Convert to Injector	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

On 8-25-2005 MIRU NDSI Rig # 1. Set all equipment. Pressure test Kelly, TIW, Choke manifold, & Bop's to 2,000 psi. Test 8.625 csgn to 1,500 psi. Vernal BLM field, & Roosevelt DOGM office was notified of test. PU BHA and tag cement @ 265'. Drill out cement & shoe. Drill a 7.875 hole with fresh water to a depth of 5985'. Lay down drill string & BHA. Open hole log w/ Dig/SP/GR log's TD to surface. PU & TIH with Guide shoe, shoe jt, float collar, 136 jt's of 5.5 J-55, 15.5# csgn. Set @ 5976.71' / KB. Cement with 300 sks cement mixed @ 11.0 ppg & 3.43 yld. Then 450 sks cement mixed @ 14.4 ppg & 1.24 yld. With 10 bbls cement returned to pit. Nipple down Bop's. Drop slips @ 87,000 #s tension. Release rig 12:30 pm on 9-1-2005.

I hereby certify that the foregoing is true and correct

Name (Printed/ Typed)

Troy Zulett

Signature

Title

Drilling Foreman

Date

09/01/2005

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)

SEP 08 2005

DIV. OF OIL, GAS & MINING

# NEWFIELD PRODUCTION COMPANY - CASING & CEMENT REPORT

<p style="text-align: center;"><u>5 1/2"</u> CASING SET AT <u>5976.71</u></p> <p>LAST CASING <u>8 5/8"</u> SET AT <u>314'</u></p> <p>DATUM <u>12' KB</u></p> <p>DATUM TO CUT OFF CASING <u>12'</u></p> <p>DATUM TO BRADENHEAD FLANGE _____</p> <p>TD DRILLER <u>5985'</u> Loggers TD <u>5985'</u></p> <p>HOLE SIZE <u>7 7/8"</u></p>	<p>Flt cllr @ <u>5933.16</u></p> <p>OPERATOR <u>Newfield Production Company</u></p> <p>WELL <u>Ashley Federal 14-13-9-15</u></p> <p>FIELD/PROSPECT <u>Monument Butte</u></p> <p>CONTRACTOR &amp; RIG # <u>NDSI # 1</u></p>
--	--

## LOG OF CASING STRING:

PIECES	OD	ITEM - MAKE - DESCRIPTION	WT / FT	GRD	THREAD	CONDT	LENGTH
		Landing Jt					14
	SHJT	6.29' @ 3936'					
135	5 1/2"	ETC LT & C casing	15.5#	J-55	8rd	A	5933.16
		Float collar					0.6
1	5 1/2"	ETC LT&C csg	15.5#	J-55	8rd	A	44.3
		GUIDE shoe			8rd	A	0.65
CASING INVENTORY BAL.		FEET	JTS	TOTAL LENGTH OF STRING			5978.71
TOTAL LENGTH OF STRING		5978.71	136	LESS CUT OFF PIECE			14
LESS NON CSG. ITEMS		15.25		PLUS DATUM TO T/CUT OFF CSG			12
PLUS FULL JTS. LEFT OUT		177.08	4	CASING SET DEPTH			5976.71
TOTAL		6378.20	140	} COMPARE			
TOTAL CSG. DEL. (W/O THRDS)		6140.54	140				
TIMING		1ST STAGE	2nd STAGE				
BEGIN RUN CSG.		8/31/2005	2:00 PM	GOOD CIRC THRU JOB YES			
CSG. IN HOLE		8/31/2005	5:00 PM	Bbls CMT CIRC TO SURFACE 10			
BEGIN CIRC		8/31/2005	5:30 PM	RECIPROCATED PIPE FOR THRUSTROKE			
BEGIN PUMP CMT		8/31/2005	6:36 PM	DID BACK PRES. VALVE HOLD ? YES			
BEGIN DSPL. CMT		8/31/2005	19:38	BUMPED PLUG TO 1600 PSI			
PLUG DOWN		31-Aug	8:00 PM				
CEMENT USED		CEMENT COMPANY- B. J.					
STAGE	# SX	CEMENT TYPE & ADDITIVES					
1	300	Premlite II w/ 10% gel + 3 % KCL, 3#s /sk CSE + 2# sk/kolseal + 1/2#s/sk Cello Flake					
		mixed @ 11.0 ppg W / 3.43 cf/sk yield					
2	450	50/50 poz W/ 2% Gel + 3% KCL, .5%EC1, 1/4# sk C.F. 2% gel. 3% SM mixed @ 14.4 ppg W/ 1.24 YLD					
CENTRALIZER & SCRATCHER PLACEMENT			SHOW MAKE & SPACING				
Centralizers - Middle first, top second & third. Then every third collar for a total of 20.							

COMPANY REPRESENTATIVE Troy Zufelt DATE 9/1/2005

**RECEIVED**

**SEP 08 2005**

DIV. OF OIL, GAS & MINING

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB No. 1004-0135  
Expires January 31, 2004

**SUNDRY NOTICES AND REPORTS ON WELLS**  
Do not use this form for proposals to drill or to re-enter an  
abandoned well. Use Form 3160-3 (APD) for such proposals.

**SUBMIT IN TRIPLICATE - Other Instructions on reverse side**

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Newfield Production Company

3a. Address Route 3 Box 3630

Myton, UT 84052

3b. Phone No. (include area code)

435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

758 FSL 2020 FWL

SE/SW Section 13 T9S R15E

5. Lease Serial No.

UTU68548

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or No.

ASHLEY PA A

8. Well Name and No.

ASHLEY FEDERAL 14-13-9-15

9. API Well No.

4301332669

10. Field and Pool, or Exploratory Area  
Monument Butte

11. County or Parish, State

Duchesne, UT

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production(Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug & Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injector	<input type="checkbox"/> Plug Back	<input checked="" type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Formation water is produced to a steel storage tank. If the production water meets quality guidelines, it is transported to the Ashley, Monument Butte, Jonah, and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project.

Water not meeting quality criteria, is disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E) or at State of Utah approved surface disposal facilities.

Accepted by the  
Utah Division of  
Oil, Gas and Mining  
FOR RECORD ONLY

SEP 2 / 2005

I hereby certify that the foregoing is true and correct

Name (Printed/Typed)  
Mandie Crozier

Signature

Title

Regulatory Specialist

Date

09/26/2005

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB No. 1004-0135  
Expires January 31, 2004

**SUNDRY NOTICES AND REPORTS ON WELLS**  
Do not use this form for proposals to drill or to re-enter an  
abandoned well. Use Form 3160-3 (APD) for such proposals.

**SUBMIT IN TRIPLICATE - Other Instructions on reverse side**

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Newfield Production Company

3a. Address

Route 3 Box 3630  
Myton, UT 84052

3b. Phone No. (include area code)

435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

758 FSL 2020 FWL

SE/SW Section 13 T9S R15E

5. Lease Serial No.

UTU68548

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or No.

ASHLEY PA A

8. Well Name and No.

ASHLEY FEDERAL 14-13-9-15

9. API Well No.

4301332669

10. Field and Pool, or Exploratory Area

Monument Butte

11. County or Parish, State

Duchesne, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production(Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug & Abandon	<input type="checkbox"/> Temporarily Abandon	Variance _____
	<input type="checkbox"/> Convert to Injector	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Newfield Production Company is requesting a variance from Onshore Order 43 CFR Part 3160 Section 4 requiring production tanks to be equipped with Enardo or equivalent vent line valves. Newfield operates wells that produce from the Green River formation, which are relatively low gas producers (20 mcfpd). The majority of the wells are equipped with a three phase separator to maximize gas separation and sales.

Newfield is requesting a variance for safety reasons. Crude oil production tanks equipped with back pressure devices will emit a surge of gas when the thief hatches are open. While gauging tanks, lease operators will be subject to breathing toxic gases as well as risk a fire hazard, under optimum conditions

COPY SENT TO OPERATOR

Date: 9-27-05  
Initials: CHD

RECEIVED

SEP 27 2005

DIV. OF OIL, GAS & MINING

I hereby certify that the foregoing is true and correct

Name (Printed/Typed)  
Mandie Crozier

Title

Regulatory Specialist

Signature

Date

09/26/2005

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Accepted by the  
Utah Division of  
Oil, Gas and Mining

Date

Federal Approval Of This  
Action Is Necessary

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make any statement or representation as to any matter within its jurisdiction.

(Instructions on reverse)

By:

Date: 9/27/05

By: [Signature]

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB No. 1004-0135  
Expires January 31, 2004

**SUNDRY NOTICES AND REPORTS ON WELLS**  
Do not use this form for proposals to drill or to re-enter an  
abandoned well. Use Form 3160-3 (APD) for such proposals.

**SUBMIT IN TRIPLICATE - Other Instructions on reverse side**

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Newfield Production Company

3a. Address Route 3 Box 3630

Myton, UT 84052

3b. Phone No. (include area code)

435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

758 FSL 2020 FWL

SE/SW Section 13 T9S R15E

5. Lease Serial No.

UTU68548

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or No.

ASHLEY PA A

8. Well Name and No.

ASHLEY FEDERAL 14-13-9-15

9. API Well No.

4301332669

10. Field and Pool, or Exploratory Area  
Monument Butte

11. County or Parish, State

Duchesne, UT

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug & Abandon	<input type="checkbox"/> Temporarily Abandon	Weekly Status Report
	<input type="checkbox"/> Convert to Injector	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Status report for time period 09/15/05 - 09/24/05

Subject well had completion procedures initiated in the Green River formation on 09-15-05 without the use of a service rig over the well. A cement bond log was run and a total of four Green River intervals were perforated and hydraulically fracture treated with 20/40 mesh sand. Perforated intervals are as follows: Stage #1 (4894'-4900'), (4828'-4832'); Stage #2 (4754'-4762'); Stage #3 (4672'-4678'); Stage #4 (4006'-4024'). All perforations, were 4 JSPF. Composite flow-through frac plugs were used between stages. Fracs were flowed back through chokes. A service rig was moved over the well on 09-22-2005. Bridge plugs were drilled out and well was cleaned to 5931.00'. Zones were swab tested for sand cleanup. A new 1 1/2" bore rod pump was run in well on sucker rods. Well was placed on production via rod pump on 09-24-2005.

I hereby certify that the foregoing is true and correct

Name (Printed/ Typed)  
Lana Nebeker

Signature

Title

Production Clerk

Date

10/07/2005

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)

**RECEIVED**

**OCT 11 2005**

**DIV. OF OIL, GAS & MINING**



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

## WELL COMPLETION OR RECOMPLETION REPORT AND LOG\*

## 1a. TYPE OF WORK

OIL  
WELL ☒GAS  
WELL ☐DRY ☐

Other \_\_\_\_\_

## 1b. TYPE OF WELL

NEW  
WELL ☒WORK  
OVER ☐DEEPEN ☐PLUG  
BACK ☐DIFF  
RESVR. ☐

Other \_\_\_\_\_

## 2. NAME OF OPERATOR

Newfield Exploration Company

## 3. ADDRESS AND TELEPHONE NO.

1401 17th St. Suite 1000 Denver, CO 80202

## 4. LOCATION OF WELL (Report locations clearly and in accordance with any State requirements.\*)

At Surface

758' FSL &amp; 2020' FWL (SE/SW) Sec.13, T9S, R15E

At top prod. Interval reported below

At total depth

14. API NO.

43-013-32669

DATE ISSUED

9/14/04

12. COUNTY OR PARISH

Duchesne

13. STATE

UT

15. DATE SPUDDED

7/27/05

16. DATE T.D. REACHED

8/31/05

17. DATE COMPL. (Ready to prod.)

9/24/05

18. ELEVATIONS (DF, RKB, RT, GR, ETC.)\*

6158' GL

19. ELEV. CASINGHEAD

6170' KB

20. TOTAL DEPTH, MD &amp; TVD

5985'

21. PLUG BACK T.D., MD &amp; TVD

5931'

22. IF MULTIPLE COMPL...

HOW MANY\*

23. INTERVALS

DRILLED BY

-----&gt;

ROTARY TOOLS

X

CABLE TOOLS

24. PRODUCING INTERVAL(S). OF THIS COMPLETION--TOP, BOTTOM, NAME (MD AND TVD)\*

Green River 4006'-4900'

25. WAS DIRECTIONAL  
SURVEY MADE

No

26. TYPE ELECTRIC AND OTHER LOGS RUN

Dual Induction Guard, SP, Compensated Density, Compensated Neutron, GR, Caliper, Cement Bond Log

27. WAS WELL CORED

No

## 23. CASING RECORD (Report all strings set in well)

CASING SIZE/GRADE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	TOP OF CEMENT, CEMENTING RECORD	AMOUNT PULLED
8-5/8" - J-55	24#	314'	12-1/4"	To surface with 160 sx Class "G" cmt	
5-1/2" - J-55	15.5#	5977'	7-7/8"	300 sx Premlite II and 450 sx 50/50 Poz	

## 29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
					2-7/8"	EOT @ 4968'	TA @ 4870'

## 31. PERFORATION RECORD (Interval, size and number)

INTERVAL	SIZE	SPF/NUMBER	DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
(B.5&2) 4828'-4832', 4894'-4900'	.41"	4/40	4828'-4900'	Frac w/ 59,638# 20/40 sand in 476 bbls fluid
(C) 4754'-4762'	.41"	4/32	4754'-4762'	Frac w/ 49,648# 20/40 sand in 418 bbls fluid
(D2) 4672'-4678'	.41"	4/24	4672'-4678'	Frac w/ 30,644# 20/40 sand in 323 bbls fluid
(GB2) 4006'-4024'	.41"	4/72	4006'-4024'	Frac w/ 84,673# 20/40 sand in 583 bbls fluid

33.\*

## PRODUCTION

DATE FIRST PRODUCTION 9/24/05		PRODUCTION METHOD (Flowing, gas lift, pumping--size and type of pump) 2-1/2" x 1-1/2" x 14.5' RHAC SM Plunger Pump					WELL STATUS (Producing or shut-in) PRODUCING	
DATE OF TEST 10 day ave	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD ----->	OIL--BBL. 46	GAS--MCF 32	WATER--BBL. 92		GAS-OIL RATIO 696
FLOW, TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE ----->	OIL--BBL.	GAS--MCF		WATER--BBL.		OIL GRAVITY-API (CORR.)
			RECEIVED					

34. DISPOSITION OF GAS (Solid, used for fuel, vented, etc.)

Sold &amp; Used for Fuel

TEST WITNESSED BY


OCT 25 2005

## 35. LIST OF ATTACHMENTS

DIV. OF OIL, GAS &amp; MINING

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED

  
Mandie Crozier

TITLE


Regulatory Specialist


DATE

10/24/2005

\*(See Instructions and Spaces for Additional Data on Reverse Side)

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem, tests, including depth interval tested, cyshion used, time tool open, flowing and shut-in pressures, and recoveries);				38. GEOLOGIC MARKERS		
FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	TOP	
			Well Name		MEAS. DEPTH	TRUE
			Ashley Federal 14-13-9-15			VERT. DEPTH
				Garden Gulch Mkr	3588'	
				Garden Gulch 1	3819'	
				Garden Gulch 2	3925'	
				Point 3 Mkr	4175'	
				X Mkr	4438'	
				Y-Mkr	4475'	
				Douglas Creek Mkr	4582'	
				BiCarbonate Mkr	4793'	
				B Limestone Mkr	4934'	
				Castle Peak	5487'	
				Basal Carbonate	5920'	
				Total Depth (LOGGERS)	5985'	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>																														
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-68548																														
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>																														
<b>2. NAME OF OPERATOR:</b> NEWFIELD PRODUCTION COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b> GMBU (GRRV)																														
<b>3. ADDRESS OF OPERATOR:</b> Rt 3 Box 3630 , Myton, UT, 84052		<b>8. WELL NAME and NUMBER:</b> ASHLEY FED 14-13-9-15																														
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0758 FSL 2020 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SESW Section: 13 Township: 09.0S Range: 15.0E Meridian: S		<b>9. API NUMBER:</b> 43013326690000																														
<b>PHONE NUMBER:</b> 435 646-4825 Ext		<b>9. FIELD and POOL or WILDCAT:</b> MONUMENT BUTTE																														
<b>COUNTY:</b> DUCHESNE		<b>STATE:</b> UTAH																														
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>																																
<b>TYPE OF SUBMISSION</b>  <input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 5/6/2013  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<b>TYPE OF ACTION</b>  <table style="width: 100%;"> <tr> <td><input type="checkbox"/> ACIDIZE</td> <td><input type="checkbox"/> ALTER CASING</td> <td><input type="checkbox"/> CASING REPAIR</td> </tr> <tr> <td><input type="checkbox"/> CHANGE TO PREVIOUS PLANS</td> <td><input type="checkbox"/> CHANGE TUBING</td> <td><input type="checkbox"/> CHANGE WELL NAME</td> </tr> <tr> <td><input type="checkbox"/> CHANGE WELL STATUS</td> <td><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS</td> <td><input type="checkbox"/> CONVERT WELL TYPE</td> </tr> <tr> <td><input type="checkbox"/> DEEPEN</td> <td><input type="checkbox"/> FRACTURE TREAT</td> <td><input type="checkbox"/> NEW CONSTRUCTION</td> </tr> <tr> <td><input type="checkbox"/> OPERATOR CHANGE</td> <td><input type="checkbox"/> PLUG AND ABANDON</td> <td><input type="checkbox"/> PLUG BACK</td> </tr> <tr> <td><input type="checkbox"/> PRODUCTION START OR RESUME</td> <td><input type="checkbox"/> RECLAMATION OF WELL SITE</td> <td><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION</td> </tr> <tr> <td><input type="checkbox"/> REPERFORATE CURRENT FORMATION</td> <td><input type="checkbox"/> SIDETRACK TO REPAIR WELL</td> <td><input type="checkbox"/> TEMPORARY ABANDON</td> </tr> <tr> <td><input type="checkbox"/> TUBING REPAIR</td> <td><input type="checkbox"/> VENT OR FLARE</td> <td><input type="checkbox"/> WATER DISPOSAL</td> </tr> <tr> <td><input type="checkbox"/> WATER SHUTOFF</td> <td><input type="checkbox"/> SI TA STATUS EXTENSION</td> <td><input type="checkbox"/> APD EXTENSION</td> </tr> <tr> <td><input type="checkbox"/> WILDCAT WELL DETERMINATION</td> <td><input checked="" type="checkbox"/> OTHER</td> <td>OTHER: <span style="border: 1px solid black; padding: 2px;">Non Routine Treatment</span></td> </tr> </table>		<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input checked="" type="checkbox"/> OTHER	OTHER: <span style="border: 1px solid black; padding: 2px;">Non Routine Treatment</span>
<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR																														
<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME																														
<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE																														
<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION																														
<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK																														
<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION																														
<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON																														
<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL																														
<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION																														
<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input checked="" type="checkbox"/> OTHER	OTHER: <span style="border: 1px solid black; padding: 2px;">Non Routine Treatment</span>																														
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b>  Newfield is going to conduct a 4 well absorption test program For the Ashley Federal 14-13-9-15 the planned job is listed as follows: Reservoir: D2 sand (zone will be isolated and tested separately) Chemical: Surtek Solution 1 Alkali: 0.75 wt % NaOH (MSDS/TDS sheets provided) Surfactant: 0.10 wt% Alfoterra 145-4S (MSDS/TDS sheets provided) Volume to be pumped: 198.0 bbl																																
<b>Accepted by the Utah Division of Oil, Gas and Mining</b>  <b>Date:</b> May 07, 2013 <b>By:</b> 																																
<b>NAME (PLEASE PRINT)</b> Mandie Crozier	<b>PHONE NUMBER</b> 435 646-4825	<b>TITLE</b> Regulatory Tech																														
<b>SIGNATURE</b> N/A	<b>DATE</b> 5/6/2013																															



Health	2
Fire	0
Reactivity	0
Personal Protection	E

## Material Safety Data Sheet

### Sodium bromide MSDS

#### Section 1: Chemical Product and Company Identification

**Product Name:** Sodium bromide

**Catalog Codes:** SLS3820, SLS1600

**CAS#:** 7647-15-6

**RTECS:** VZ3150000

**TSCA:** TSCA 8(b) inventory: Sodium bromide

**CI#:** Not available.

**Synonym:** Bromide salt of sodium

**Chemical Name:** Sodium Bromide

**Chemical Formula:** NaBr

#### Contact Information:

**Sciencelab.com, Inc.**

14025 Smith Rd.

Houston, Texas 77396

US Sales: **1-800-901-7247**

International Sales: **1-281-441-4400**

Order Online: [ScienceLab.com](http://ScienceLab.com)

**CHEMTREC (24HR Emergency Telephone), call:**

1-800-424-9300

**International CHEMTREC, call:** 1-703-527-3887

**For non-emergency assistance, call:** 1-281-441-4400

#### Section 2: Composition and Information on Ingredients

##### Composition:

Name	CAS #	% by Weight
Sodium bromide	7647-15-6	100

**Toxicological Data on Ingredients:** Sodium bromide: ORAL (LD50): Acute: 3500 mg/kg [Rat]. 7000 mg/kg [Mouse].

#### Section 3: Hazards Identification

##### Potential Acute Health Effects:

Hazardous in case of eye contact (irritant), of ingestion, of inhalation. Slightly hazardous in case of skin contact (irritant).

##### Potential Chronic Health Effects:

CARCINOGENIC EFFECTS: Not available. MUTAGENIC EFFECTS: Not available. TERATOGENIC EFFECTS: Not available. DEVELOPMENTAL TOXICITY: Not available. Repeated or prolonged exposure is not known to aggravate medical condition.

#### Section 4: First Aid Measures

##### Eye Contact:

Check for and remove any contact lenses. In case of contact, immediately flush eyes with plenty of water for at least 15 minutes. Cold water may be used. Get medical attention.

##### Skin Contact:

Wash with soap and water. Cover the irritated skin with an emollient. Get medical attention if irritation develops. Cold water may be used.

**Serious Skin Contact:** Not available.

**Inhalation:**

If inhaled, remove to fresh air. If not breathing, give artificial respiration. If breathing is difficult, give oxygen. Get medical attention.

**Serious Inhalation:** Not available.

**Ingestion:**

Do NOT induce vomiting unless directed to do so by medical personnel. Never give anything by mouth to an unconscious person. Loosen tight clothing such as a collar, tie, belt or waistband. Get medical attention if symptoms appear.

**Serious Ingestion:** Not available.

## Section 5: Fire and Explosion Data

**Flammability of the Product:** Non-flammable.

**Auto-Ignition Temperature:** Not applicable.

**Flash Points:** Not applicable.

**Flammable Limits:** Not applicable.

**Products of Combustion:** Not available.

**Fire Hazards in Presence of Various Substances:** Not applicable.

**Explosion Hazards in Presence of Various Substances:**

Risks of explosion of the product in presence of mechanical impact: Not available. Risks of explosion of the product in presence of static discharge: Not available.

**Fire Fighting Media and Instructions:** Not applicable.

**Special Remarks on Fire Hazards:** Not available.

**Special Remarks on Explosion Hazards:** Not available.

## Section 6: Accidental Release Measures

**Small Spill:**

Use appropriate tools to put the spilled solid in a convenient waste disposal container. Finish cleaning by spreading water on the contaminated surface and dispose of according to local and regional authority requirements.

**Large Spill:**

Use a shovel to put the material into a convenient waste disposal container. Finish cleaning by spreading water on the contaminated surface and allow to evacuate through the sanitary system.

## Section 7: Handling and Storage

**Precautions:**

Do not ingest. Do not breathe dust. Avoid contact with eyes. Wear suitable protective clothing. In case of insufficient ventilation, wear suitable respiratory equipment. If ingested, seek medical advice immediately and show the container or the label. Keep away from incompatibles such as oxidizing agents, acids.

**Storage:** Keep container tightly closed. Keep container in a cool, well-ventilated area. Do not store above 25°C (77°F).

## Section 8: Exposure Controls/Personal Protection

**Engineering Controls:**

Use process enclosures, local exhaust ventilation, or other engineering controls to keep airborne levels below recommended exposure limits. If user operations generate dust, fume or mist, use ventilation to keep exposure to airborne contaminants below the exposure limit.

**Personal Protection:**

Splash goggles. Lab coat. Dust respirator. Be sure to use an approved/certified respirator or equivalent. Gloves.

**Personal Protection in Case of a Large Spill:**

Splash goggles. Full suit. Dust respirator. Boots. Gloves. A self contained breathing apparatus should be used to avoid inhalation of the product. Suggested protective clothing might not be sufficient; consult a specialist BEFORE handling this product.

**Exposure Limits:** Not available.

## Section 9: Physical and Chemical Properties

**Physical state and appearance:** Solid.

**Odor:** Not available.

**Taste:** Not available.

**Molecular Weight:** 102.91 g/mole

**Color:** Not available.

**pH (1% soln/water):** 6.5-8.0

**Boiling Point:** 1390°C (2534°F)

**Melting Point:** 755°C (1391°F)

**Critical Temperature:** Not available.

**Specific Gravity:** 3.21 (Water = 1)

**Vapor Pressure:** Not applicable.

**Vapor Density:** Not available.

**Volatility:** Not available.

**Odor Threshold:** Not available.

**Water/Oil Dist. Coeff.:** Not available.

**Ionicity (in Water):** Not available.

**Dispersion Properties:** See solubility in water, methanol.

**Solubility:**

Easily soluble in cold water, hot water. Soluble in methanol. 1 g dissolves in 1.1 ml of water. 1 g dissolves in about 16 ml of alcohol. 1 g dissolves in 6 ml of methanol

## Section 10: Stability and Reactivity Data

**Stability:** The product is stable.

**Instability Temperature:** Not available.

**Conditions of Instability:** Incompatible materials, moisture

**Incompatibility with various substances:** Reactive with oxidizing agents, acids.

**Corrosivity:** Non-corrosive in presence of glass.

**Special Remarks on Reactivity:**

Absorbs moisture from the air but is not deliquescent. Hygroscopic. Also incompatible with alkaloidal and heavy metal salts, and Bromine Trifluoride.

**Special Remarks on Corrosivity:** Not available.

**Polymerization:** Will not occur.

## Section 11: Toxicological Information

**Routes of Entry:** Inhalation. Ingestion.

**Toxicity to Animals:** Acute oral toxicity (LD50): 3500 mg/kg [Rat].

**Chronic Effects on Humans:** Not available.

**Other Toxic Effects on Humans:**

Hazardous in case of ingestion, of inhalation. Slightly hazardous in case of skin contact (irritant).

**Special Remarks on Toxicity to Animals:** Not available.

**Special Remarks on Chronic Effects on Humans:**

May cause adverse reproductive effects (male and female effects on fertility and effects on newborns and fetotoxicity) based on animal data Human: passes the placental barrier, detected in maternal milk.

**Special Remarks on other Toxic Effects on Humans:**

Acute Potential Health Effects: Skin: May cause mild skin irritation. Eyes: Causes eye irritation. Inhalation: May cause respiratory tract irritation. Ingestion: May cause gastrointestinal tract irritation with nausea and vomiting, abdominal pain, constipation. Bromide poisoning following acute ingestion is more rare and may affect the central nervous system (CNS depression - somnolence, confusion, ataxia, coma and other symptoms similar to chronic ingestion), cardiovascular system (hypotension, tachycardia), kidneys (acute renal failure, urinary incontinence), and respiration (acute respiratory distress syndrome). It may also cause eye disturbances such as mydriasis and nystagmus, disturbances of apparent color of objects, blurring or indistinctness of vision, apparent movement or wiggling and change in apparent size of objects, large pupils, subnormal reaction to light, diplopia, and photophobia. Chronic Potential Health Effects: Skin: Prolonged or repeated skin contact may cause skin rashes. Eyes: Prolonged or repeated eye contact may cause blepharitis, and conjunctivitis. Prolonged or repeated ingestion may cause skin rashes (bromoderma, acne, pyoderma gangrenosum, erythema multiforme), affect the liver, endocrine system (thyroid), metabolism(anorexia), blood, vision (visual disturbances, permanently decreased vision and may produce a toxic syndrome, "Bromism" which may be characterized by behavior/central nervous symptoms such CNS depression, irritability, headache, confusion, slurred speech, memory loss, lethargy, ataxia, tremor, agitation, delusion, disoriented, paranoia, aggressiveness, hallucinations, mania, fatigue, seizure, neuropathy, muscle weakness, coma. Also, in individuals with chronic bromism, the tongue may have a coated or furred appearance.

## Section 12: Ecological Information

**Ecotoxicity:** Not available.

**BOD5 and COD:** Not available.

**Products of Biodegradation:**

Possibly hazardous short term degradation products are not likely. However, long term degradation products may arise.

**Toxicity of the Products of Biodegradation:** The product itself and its products of degradation are not toxic.

**Special Remarks on the Products of Biodegradation:** Not available.

## Section 13: Disposal Considerations

**Waste Disposal:**

Waste must be disposed of in accordance with federal, state and local environmental control regulations.

#### Section 14: Transport Information

**DOT Classification:** Not a DOT controlled material (United States).

**Identification:** Not applicable.

**Special Provisions for Transport:** Not applicable.

#### Section 15: Other Regulatory Information

**Federal and State Regulations:** TSCA 8(b) inventory: Sodium bromide

**Other Regulations:** EINECS: This product is on the European Inventory of Existing Commercial Chemical Substances.

**Other Classifications:**

**WHMIS (Canada):** Not controlled under WHMIS (Canada).

**DSCL (EEC):**

R36- Irritating to eyes. S2- Keep out of the reach of children. S24/25- Avoid contact with skin and eyes. S46- If swallowed, seek medical advice immediately and show this container or label.

**HMIS (U.S.A.):**

**Health Hazard:** 2

**Fire Hazard:** 0

**Reactivity:** 0

**Personal Protection:** E

**National Fire Protection Association (U.S.A.):**

**Health:** 2

**Flammability:** 0

**Reactivity:** 0

**Specific hazard:**

**Protective Equipment:**

Gloves. Lab coat. Dust respirator. Be sure to use an approved/certified respirator or equivalent. Splash goggles.

#### Section 16: Other Information

**References:** Not available.


**Other Special Considerations:** Not available.

**Created:** 10/10/2005 08:26 PM

**Last Updated:** 06/09/2012 12:00 PM

*The information above is believed to be accurate and represents the best information currently available to us. However, we make no warranty of merchantability or any other warranty, express or implied, with respect to such information, and we assume no liability resulting from its use. Users should make their own investigations to determine the suitability of the information for their particular purposes. In no event shall ScienceLab.com be liable for any claims, losses, or damages of any third party or for lost profits or any special, indirect, incidental, consequential or exemplary damages, howsoever arising, even if ScienceLab.com has been advised of the possibility of such damages.*





Health	2
Fire	0
Reactivity	0
Personal Protection	E

## Material Safety Data Sheet

### Sodium bromide MSDS

#### Section 1: Chemical Product and Company Identification

**Product Name:** Sodium bromide

**Catalog Codes:** SLS3820, SLS1600

**CAS#:** 7647-15-6

**RTECS:** VZ3150000

**TSCA:** TSCA 8(b) inventory: Sodium bromide

**CI#:** Not available.

**Synonym:** Bromide salt of sodium

**Chemical Name:** Sodium Bromide

**Chemical Formula:** NaBr

#### Contact Information:

**Sciencelab.com, Inc.**

14025 Smith Rd.

Houston, Texas 77396

US Sales: **1-800-901-7247**

International Sales: **1-281-441-4400**

Order Online: [ScienceLab.com](http://ScienceLab.com)

**CHEMTREC (24HR Emergency Telephone), call:**

1-800-424-9300

**International CHEMTREC, call:** 1-703-527-3887

**For non-emergency assistance, call:** 1-281-441-4400

#### Section 2: Composition and Information on Ingredients

##### Composition:

Name	CAS #	% by Weight
Sodium bromide	7647-15-6	100

**Toxicological Data on Ingredients:** Sodium bromide: ORAL (LD50): Acute: 3500 mg/kg [Rat]. 7000 mg/kg [Mouse].

#### Section 3: Hazards Identification

##### Potential Acute Health Effects:

Hazardous in case of eye contact (irritant), of ingestion, of inhalation. Slightly hazardous in case of skin contact (irritant).

##### Potential Chronic Health Effects:

CARCINOGENIC EFFECTS: Not available. MUTAGENIC EFFECTS: Not available. TERATOGENIC EFFECTS: Not available. DEVELOPMENTAL TOXICITY: Not available. Repeated or prolonged exposure is not known to aggravate medical condition.

#### Section 4: First Aid Measures

##### Eye Contact:

Check for and remove any contact lenses. In case of contact, immediately flush eyes with plenty of water for at least 15 minutes. Cold water may be used. Get medical attention.

##### Skin Contact:

Wash with soap and water. Cover the irritated skin with an emollient. Get medical attention if irritation develops. Cold water may be used.

**Serious Skin Contact:** Not available.

**Inhalation:**

If inhaled, remove to fresh air. If not breathing, give artificial respiration. If breathing is difficult, give oxygen. Get medical attention.

**Serious Inhalation:** Not available.

**Ingestion:**

Do NOT induce vomiting unless directed to do so by medical personnel. Never give anything by mouth to an unconscious person. Loosen tight clothing such as a collar, tie, belt or waistband. Get medical attention if symptoms appear.

**Serious Ingestion:** Not available.

## Section 5: Fire and Explosion Data

**Flammability of the Product:** Non-flammable.

**Auto-Ignition Temperature:** Not applicable.

**Flash Points:** Not applicable.

**Flammable Limits:** Not applicable.

**Products of Combustion:** Not available.

**Fire Hazards in Presence of Various Substances:** Not applicable.

**Explosion Hazards in Presence of Various Substances:**

Risks of explosion of the product in presence of mechanical impact: Not available. Risks of explosion of the product in presence of static discharge: Not available.

**Fire Fighting Media and Instructions:** Not applicable.

**Special Remarks on Fire Hazards:** Not available.

**Special Remarks on Explosion Hazards:** Not available.

## Section 6: Accidental Release Measures

**Small Spill:**

Use appropriate tools to put the spilled solid in a convenient waste disposal container. Finish cleaning by spreading water on the contaminated surface and dispose of according to local and regional authority requirements.

**Large Spill:**

Use a shovel to put the material into a convenient waste disposal container. Finish cleaning by spreading water on the contaminated surface and allow to evacuate through the sanitary system.

## Section 7: Handling and Storage

**Precautions:**

Do not ingest. Do not breathe dust. Avoid contact with eyes. Wear suitable protective clothing. In case of insufficient ventilation, wear suitable respiratory equipment. If ingested, seek medical advice immediately and show the container or the label. Keep away from incompatibles such as oxidizing agents, acids.

**Storage:** Keep container tightly closed. Keep container in a cool, well-ventilated area. Do not store above 25°C (77°F).

## Section 8: Exposure Controls/Personal Protection

**Engineering Controls:**

Use process enclosures, local exhaust ventilation, or other engineering controls to keep airborne levels below recommended exposure limits. If user operations generate dust, fume or mist, use ventilation to keep exposure to airborne contaminants below the exposure limit.

**Personal Protection:**

Splash goggles. Lab coat. Dust respirator. Be sure to use an approved/certified respirator or equivalent. Gloves.

**Personal Protection in Case of a Large Spill:**

Splash goggles. Full suit. Dust respirator. Boots. Gloves. A self contained breathing apparatus should be used to avoid inhalation of the product. Suggested protective clothing might not be sufficient; consult a specialist BEFORE handling this product.

**Exposure Limits:** Not available.

## Section 9: Physical and Chemical Properties

**Physical state and appearance:** Solid.

**Odor:** Not available.

**Taste:** Not available.

**Molecular Weight:** 102.91 g/mole

**Color:** Not available.

**pH (1% soln/water):** 6.5-8.0

**Boiling Point:** 1390°C (2534°F)

**Melting Point:** 755°C (1391°F)

**Critical Temperature:** Not available.

**Specific Gravity:** 3.21 (Water = 1)

**Vapor Pressure:** Not applicable.

**Vapor Density:** Not available.

**Volatility:** Not available.

**Odor Threshold:** Not available.

**Water/Oil Dist. Coeff.:** Not available.

**Ionicity (in Water):** Not available.

**Dispersion Properties:** See solubility in water, methanol.

**Solubility:**

Easily soluble in cold water, hot water. Soluble in methanol. 1 g dissolves in 1.1 ml of water. 1 g dissolves in about 16 ml of alcohol. 1 g dissolves in 6 ml of methanol

## Section 10: Stability and Reactivity Data

**Stability:** The product is stable.

**Instability Temperature:** Not available.

**Conditions of Instability:** Incompatible materials, moisture

**Incompatibility with various substances:** Reactive with oxidizing agents, acids.

**Corrosivity:** Non-corrosive in presence of glass.

**Special Remarks on Reactivity:**

Absorbs moisture from the air but is not deliquescent. Hygroscopic. Also incompatible with alkaloidal and heavy metal salts, and Bromine Trifluoride.

**Special Remarks on Corrosivity:** Not available.

**Polymerization:** Will not occur.

## Section 11: Toxicological Information

**Routes of Entry:** Inhalation. Ingestion.

**Toxicity to Animals:** Acute oral toxicity (LD50): 3500 mg/kg [Rat].

**Chronic Effects on Humans:** Not available.

**Other Toxic Effects on Humans:**

Hazardous in case of ingestion, of inhalation. Slightly hazardous in case of skin contact (irritant).

**Special Remarks on Toxicity to Animals:** Not available.

**Special Remarks on Chronic Effects on Humans:**

May cause adverse reproductive effects (male and female effects on fertility and effects on newborns and fetotoxicity) based on animal data Human: passes the placental barrier, detected in maternal milk.

**Special Remarks on other Toxic Effects on Humans:**

Acute Potential Health Effects: Skin: May cause mild skin irritation. Eyes: Causes eye irritation. Inhalation: May cause respiratory tract irritation. Ingestion: May cause gastrointestinal tract irritation with nausea and vomiting, abdominal pain, constipation. Bromide poisoning following acute ingestion is more rare and may affect the central nervous system (CNS depression - somnolence, confusion, ataxia, coma and other symptoms similar to chronic ingestion), cardiovascular system (hypotension, tachycardia), kidneys (acute renal failure, urinary incontinence), and respiration (acute respiratory distress syndrome). It may also cause eye disturbances such as mydriasis and nystagmus, disturbances of apparent color of objects, blurring or indistinctness of vision, apparent movement or wiggling and change in apparent size of objects, large pupils, subnormal reaction to light, diplopia, and photophobia. Chronic Potential Health Effects: Skin: Prolonged or repeated skin contact may cause skin rashes. Eyes: Prolonged or repeated eye contact may cause blepharitis, and conjunctivitis. Prolonged or repeated ingestion may cause skin rashes (bromoderma, acne, pyoderma gangrenosum, erythema multiforme), affect the liver, endocrine system (thyroid), metabolism(anorexia), blood, vision (visual disturbances, permanently decreased vision and may produce a toxic syndrome, "Bromism" which may be characterized by behavior/central nervous symptoms such CNS depression, irritability, headache, confusion, slurred speech, memory loss, lethargy, ataxia, tremor, agitation, delusion, disoriented, paranoia, aggressiveness, hallucinations, mania, fatigue, seizure, neuropathy, muscle weakness, coma. Also, in individuals with chronic bromism, the tongue may have a coated or furred appearance.

## Section 12: Ecological Information

**Ecotoxicity:** Not available.

**BOD5 and COD:** Not available.

**Products of Biodegradation:**

Possibly hazardous short term degradation products are not likely. However, long term degradation products may arise.

**Toxicity of the Products of Biodegradation:** The product itself and its products of degradation are not toxic.

**Special Remarks on the Products of Biodegradation:** Not available.

## Section 13: Disposal Considerations

**Waste Disposal:**

Waste must be disposed of in accordance with federal, state and local environmental control regulations.

#### Section 14: Transport Information

**DOT Classification:** Not a DOT controlled material (United States).

**Identification:** Not applicable.

**Special Provisions for Transport:** Not applicable.

#### Section 15: Other Regulatory Information

**Federal and State Regulations:** TSCA 8(b) inventory: Sodium bromide

**Other Regulations:** EINECS: This product is on the European Inventory of Existing Commercial Chemical Substances.

**Other Classifications:**

**WHMIS (Canada):** Not controlled under WHMIS (Canada).

**DSCL (EEC):**

R36- Irritating to eyes. S2- Keep out of the reach of children. S24/25- Avoid contact with skin and eyes. S46- If swallowed, seek medical advice immediately and show this container or label.

**HMIS (U.S.A.):**

**Health Hazard:** 2

**Fire Hazard:** 0

**Reactivity:** 0

**Personal Protection:** E

**National Fire Protection Association (U.S.A.):**

**Health:** 2

**Flammability:** 0

**Reactivity:** 0

**Specific hazard:**

**Protective Equipment:**

Gloves. Lab coat. Dust respirator. Be sure to use an approved/certified respirator or equivalent. Splash goggles.

#### Section 16: Other Information

**References:** Not available.

**Other Special Considerations:** Not available.

**Created:** 10/10/2005 08:26 PM

**Last Updated:** 06/09/2012 12:00 PM

*The information above is believed to be accurate and represents the best information currently available to us. However, we make no warranty of merchantability or any other warranty, express or implied, with respect to such information, and we assume no liability resulting from its use. Users should make their own investigations to determine the suitability of the information for their particular purposes. In no event shall ScienceLab.com be liable for any claims, losses, or damages of any third party or for lost profits or any special, indirect, incidental, consequential or exemplary damages, howsoever arising, even if ScienceLab.com has been advised of the possibility of such damages.*



# WELLBROM® 12.5 Completion Fluid

## Description

WELLBROM 12.5 is a clear brine completion fluid based on an aqueous solution of sodium bromide.

## Applications

Because of its high density, WELLBROM 12.5 is used extensively as a completion, fracturing, workover and packer fluid in oilfield applications.


## Specifications

Appearance	Clear
Density, 70°F (21.1°C), lb/gal	≥12.30

## Physical properties

Appearance	Clear liquid, light to water-white color
Boiling point, °F (°C)	230–243 (110–117)
Flash point	None
Odor	Slight
Specific gravity, 70°F (21.1°C)	≥1.47
Color, APHA	≤30
pH (diluted 1:10 with water)	7.0–8.5

Variation of the crystallization temperature of NaBr with concentration.



**Compatibility**

**Compatible materials of construction:** This product is compatible with most non-metallic materials of construction, including fiber-glass-reinforced plastic (vinyl ester and polyester FRP), polyvinyl chloride (PVC), chlorinated polyvinyl chloride (CPVC), high-density polyethylene, polypropylene, Viton®, Teflon®, natural rubber, chlorobutyl rubber, Hypalon®, Halar® ethylene chlorotrifluoroethylene, Tefzel® ethylene/tetrafluoroethylene copolymer and most high-performance polytetrafluoroethylene-based gasket materials such as W.L. Gore GORE-TEX® and UPG Style 800, and Garlock Gylon® styles 3504 and 3500.

Titanium and high-nickel alloys such as Inconel® 625 and 686, and Hastelloy® C-22 and C276 are also suitably compatible.

**Incompatible materials of construction:** The compatibility of this product with common metals depends on storage conditions and the environment the material is in. Aluminum, brass, carbon steel, copper, stainless steel and other common metals are generally not suitable for use. Carbon steel and copper can result in discoloration of the product. Aluminum suffers pitting attack. Dissolved oxygen increases the corrosion rate of stainless steel.

**Recommended materials of construction for storage tanks:** Vinyl ester FRP such as Ashland Derakane® 411 and 470, and bisphenol A fumarate polyester FRP such as Reichhold Atlae 6694 are suitable for use.

**Recommended materials of construction for piping and valves:** For piping, an adhesive socket FRP system such as the Reinforced Plastics Systems P150 series or the Smith Fibercast CL-2030 series is suitable. A flat-faced FRP ball valve such as the Nil-Cor 310 series is a good choice for FRP piping. Polypropylene-lined steel also is suitable. For low-pressure lines (<5 psig) such as overflows and drains, solid PVC or CPVC piping can be used, but should be safeguarded from mechanical damage.

**Shipping information****Container information:**

Available in tank trailers and drums

**Shipping classification:**

Not regulated for transportation

**Safety and handling information**

For specific safety, toxicity and handling information, please refer to the material safety data sheet for this product.

**Chemical registration numbers**

CAS:	7647-15-6
EINECS:	231-599-9
MITI:	1-113



**AMERICAS** 451 Florida Street • Baton Rouge, Louisiana 70801-1765 • Tel +1 225-388-7402 or 800-535-3030 • Fax +1 225-388-7848  
**EUROPE** Parc Scientifique de LLN • Rue du Bosquet 9 • B-1348 Louvain-la-Nueve Sud, Belgium • Tel +32-10-48-1711 • Fax +32-10-48-1717  
**ASIA PACIFIC** 16h Floor, Fukoku Science Building • 2-2-2, Uchisawai-cho • Chiyoda-Ku, Tokyo 100-0011, Japan • Tel +81-3-5251-0796 • Fax: +81-3-3500-5623  
**ASIA PACIFIC** China World Tower, Room 1317 • No. 1 Jan Guo Mon Wai Avenue • Beijing, 100004 China • Tel +86-10-6505-4153 or +86-10-6505-4154 • Fax +86-10-6505-4150



<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-68548
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> NEWFIELD PRODUCTION COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b> GMBU (GRRV)
<b>3. ADDRESS OF OPERATOR:</b> Rt 3 Box 3630, Myton, UT, 84052		<b>8. WELL NAME and NUMBER:</b> ASHLEY FED 14-13-9-15
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0758 FSL 2020 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SESW Section: 13 Township: 09.0S Range: 15.0E Meridian: S		<b>9. API NUMBER:</b> 43013326690000
<b>PHONE NUMBER:</b> 435 646-4825 Ext		<b>9. FIELD and POOL or WILDCAT:</b> MONUMENT BUTTE
<b>COUNTY:</b> DUCHESNE		<b>STATE:</b> UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input checked="" type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input checked="" type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION	OTHER: <input style="width: 100px;" type="text"/>
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <b>7/31/2014</b>				
<input type="checkbox"/> SPUD REPORT Date of Spud:				
<input type="checkbox"/> DRILLING REPORT Report Date:				

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The subject well has been converted from a producing oil well to an injection well on 07/29/2014. On 07/30/2014 Chris Jensen with the State of Utah DOGM was contacted concerning the initial MIT on the above listed well. On 07/31/2014 the casing was pressured up to 1449 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 300 psig during the test. There was a State representative available to witness the test - Chris Jensen.

**Accepted by the**  
**Utah Division of**  
**Oil, Gas and Mining**  
**FOR RECORD ONLY**  
 August 06, 2014

<b>NAME (PLEASE PRINT)</b> Lucy Chavez-Naupoto	<b>PHONE NUMBER</b> 435 646-4874	<b>TITLE</b> Water Services Technician
<b>SIGNATURE</b> N/A	<b>DATE</b> 8/5/2014	



# Mechanical Integrity Test Casing or Annulus Pressure Test

Newfield Production Company

Rt. 3 Box 3630

Myton, UT 84052

435-646-3721

Witness: Chris Jensen Date 7/31/14 Time 10:15 (am/pm)  
Test Conducted by: Dustin Allred  
Others Present: Steve Weight

Well: ASTLEY

Field: GMBU

Well Location: 14-13-9-15

API No: 4301332669

<u>Time</u>	<u>Casing Pressure</u>	
0 min	<u>1449</u>	psig
5	<u>1449</u>	psig
10	<u>1450</u>	psig
15	<u>1450</u>	psig
20	<u>1449</u>	psig
25	<u>1449</u>	psig
30 min	<u>1449</u>	psig
35		psig
40		psig
45		psig
50		psig
55		psig
60 min		psig

Tubing pressure: 300 psig

Result: Pass Fail

Signature of Witness:


Chris Jensen

Signature of Person Conducting Test:

Dustin Allred

Ashley 14-13-9-15 MIT

7/31/2014 10:11:12 AM



NEWFIELD



Well Name: Ashley 14-13-9-15

## Job Detail Summary Report

Jobs		Job Start Date	Job End Date
Primary Job Type Conversion		7/24/2014	7/31/2014

Daily Operations			
Report Start Date	Report End Date	24hr Activity Summary	
7/24/2014	7/24/2014	MIRU	
Start Time	13:00	End Time	14:30
Start Time	14:30	End Time	17:30
Start Time	17:30	End Time	18:00
Start Time	18:00	End Time	19:00
Report Start Date	Report End Date	24hr Activity Summary	
7/25/2014	7/25/2014	ND WH, NU BOP, L/D TBG	
Start Time	06:00	End Time	07:00
Start Time	07:00	End Time	09:00
Start Time	09:00	End Time	10:30
Start Time	10:30	End Time	13:30
Start Time	13:30	End Time	15:00
Start Time	15:00	End Time	16:00
Start Time	17:00	End Time	18:00
Report Start Date	Report End Date	24hr Activity Summary	
7/28/2014	7/28/2014	FISH VALVE, FLUSH TBG, POOH TBG SV STUCK IN JT	
Start Time	06:00	End Time	07:00
Start Time	07:00	End Time	07:30
Start Time	07:30	End Time	08:30
Start Time	08:30	End Time	09:30
Start Time	09:30	End Time	11:00
Start Time	11:00	End Time	13:00
Start Time	13:00	End Time	17:30



Well Name: Ashley 14-13-9-15

# Job Detail Summary Report

Start Time	17:30	End Time	18:00	Comment
Start Time	18:00	End Time	19:00	Comment
Report Start Date	7/29/2014	Report End Date	7/29/2014	24hr Activity Summary
Start Time	06:00	End Time	07:00	Comment
Start Time	07:00	End Time	08:00	Comment
Start Time	08:00	End Time	09:00	Comment
Start Time	09:00	End Time	10:30	Comment
Start Time	10:30	End Time	12:30	Comment
Start Time	12:30	End Time	15:00	Comment
Start Time	15:00	End Time	16:00	Comment
Report Start Date	7/31/2014	Report End Date	7/31/2014	24hr Activity Summary
Start Time	10:15	End Time	10:45	Comment

On 07/30/2014 Chris Jensen with the State of Utah DOGM was contacted concerning the initial MIT on the above listed well. On 07/31/2014 the casing was pressured up to 1449 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 300 psig during the test. There was a State representative available to witness the test - Chris Jensen.

## NEWFIELD

## Schematic

Well Name: Ashley 14-13-9-15


Surface Legal Location 13-9S-15E		API/UWI 43013326690000	Well RC 500151917	Lease	State/Province Utah	Field Name GMBU CTB2	County DUCHESNE
Spud Date	Rig Release Date	On Production Date 9/24/2005	Original KB Elevation (ft) 6,170	Ground Elevation (ft) 6,158	Total Depth All (TVD) (ftKB)	PBTD (All) (ftKB) Original Hole - 5,931.2	

## Most Recent Job

Job Category Production / Workover	Primary Job Type Conversion	Secondary Job Type Basic	Job Start Date 7/24/2014	Job End Date 7/31/2014
---------------------------------------	--------------------------------	-----------------------------	-----------------------------	---------------------------

TD: 5,985.0

Vertical - Original Hole, 8/4/2014 11:35:28 AM





**NEWFIELD****Newfield Wellbore Diagram Data  
Ashley 14-13-9-15**

Surface Legal Location 13-9S-15E		API/UWI 43013326690000		Lease	
County DUCHESNE	State/Province Utah		Basin Uintah Basin	Field Name GMBU CTB2	
Well Start Date 7/27/2005	Spud Date		Final Rig Release Date	On Production Date 9/24/2005	
Original KB Elevation (ft) 6,170	Ground Elevation (ft) 6,158	Total Depth (ftKB) 5,985.0	Total Depth All (TVD) (ftKB)	PBTD (All) (ftKB) Original Hole - 5,931.2	

**Casing Strings**

Csg Des	Run Date	OD (in)	ID (in)	Wt/Len (lb/ft)	Grade	Set Depth (ftKB)
Surface	8/26/2005	8 5/8	8.097	24.00	J-55	314
Production	8/31/2005	5 1/2	4.950	15.50	J-55	5,977

**Cement****String: Surface, 314ftKB 8/26/2005**

Cementing Company	Top Depth (ftKB) 12.0	Bottom Depth (ftKB) 314.2	Full Return?	Vol Cement Ret (bbl)
Fluid Description	Fluid Type Lead	Amount (sacks) 160	Class G	Estimated Top (ftKB) 12.0

**String: Production, 5,977ftKB 9/1/2005**

Cementing Company	Top Depth (ftKB) 12.0	Bottom Depth (ftKB) 5,985.0	Full Return?	Vol Cement Ret (bbl)
Fluid Description 10% gel + 3 % KCL, 3#s /sk CSE + 2# sk/kolseal + 1/2#s/sk Cello Flake	Fluid Type Lead	Amount (sacks) 300	Class Premilite II	Estimated Top (ftKB) 12.0
Fluid Description 2% Gel + 3% KCL, .5%EC1, 1/4# sk C.F. 2% gel. 3% SM	Fluid Type Tail	Amount (sacks) 450	Class 50/50 POZ	Estimated Top (ftKB) 2,390.7

**Tubing Strings**

Tubing Description					Run Date		Set Depth (ftKB)	
Tubing					7/30/2014		3,921.0	
Item Des	Jts	OD (in)	ID (in)	Wt (lb/ft)	Grade	Len (ft)	Top (ftKB)	Btm (ftKB)
Tubing	125	2 7/8	2.441	6.50	J-55	3,894.57	12.0	3,906.6
Pump Seating Nipple	1	2 7/8				1.10	3,906.6	3,907.7
Packer	1	5 1/2	4.950			6.99	3,907.7	3,914.7
Cross Over	1	2 3/8	1.991			0.60	3,914.7	3,915.3
Tubing Pup Joint	1	2 3/8				4.11	3,915.3	3,919.4
Nipple	1	2 3/8				1.10	3,919.4	3,920.5
Wireline Guide	1	2 3/8				0.50	3,920.5	3,921.0

**Rod Strings**

Rod Description		Run Date			Set Depth (ftKB)		
Item Des	Jts	OD (in)	Wt (lb/ft)	Grade	Len (ft)	Top (ftKB)	Btm (ftKB)

**Other In Hole**

Des	Top (ftKB)	Btm (ftKB)	Run Date	Pull Date
Retrievable Bridge Plug	4,744	4,750	9/18/2013	

**Perforation Intervals**


Stage#	Zone	Top (ftKB)	Btm (ftKB)	Shot Dens (shots/ft)	Phasing (°)	Nom Hole Dia (in)	Date
5	GB2, Original Hole	4,006	4,024	4			9/19/2005
4	D2, Original Hole	4,672	4,678	4			9/19/2005
3	C, Original Hole	4,754	4,762	4			9/19/2005
2	B .5, Original Hole	4,828	4,832	4			9/16/2005
1	B2, Original Hole	4,894	4,900	4			9/16/2005

**Stimulations & Treatments**

Stage#	ISIP (psi)	Frac Gradient (psi/ft)	Max Rate (bbl/min)	Max PSI (psi)	Total Clean Vol (bbl)	Total Slurry Vol (bbl)	Vol Recov (bbl)
1	2,300	0.91	25.2	1,925			
1	2,300	0.91	25.2	1,925			
2	3,650	1.2	31.8	2,485			
3	2,030	0.87	25.2	2,125			
4	2,610	1.08	25.2	2,100			

**Proppant**

Stage#	Total Prop Vol Pumped (lb)	Total Add Amount
1		
1		
2		
3		
4		

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-68548
<b>1. TYPE OF WELL</b> Water Injection Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> NEWFIELD PRODUCTION COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b> GMBU (GRRV)
<b>3. ADDRESS OF OPERATOR:</b> Rt 3 Box 3630, Myton, UT, 84052		<b>8. WELL NAME and NUMBER:</b> ASHLEY FED 14-13-9-15
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0758 FSL 2020 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SESW Section: 13 Township: 09.0S Range: 15.0E Meridian: S		<b>9. API NUMBER:</b> 43013326690000
<b>PHONE NUMBER:</b> 435 646-4825 Ext		<b>9. FIELD and POOL or WILDCAT:</b> MONUMENT BUTTE
<b>COUNTY:</b> DUCHESNE		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 10/29/2014	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input checked="" type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <span style="border: 1px solid black; display: inline-block; width: 100px; height: 15px;"></span>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between; align-items: flex-start;"> <div style="width: 60%;"> <p>The above reference well was put on injection at 10:45 AM on 10/29/2014.</p> </div> <div style="width: 35%; text-align: right;"> <p><b>Accepted by the Utah Division of Oil, Gas and Mining</b></p> <p><b>Date:</b> <del>November 10, 2014</del></p> <p><b>By:</b> </p> </div> </div>		
<b>NAME (PLEASE PRINT)</b> Lucy Chavez-Naupoto	<b>PHONE NUMBER</b> 435 646-4874	<b>TITLE</b> Water Services Technician
<b>SIGNATURE</b> N/A		<b>DATE</b> 10/30/2014



GARY R. HERBERT  
Governor

SPENCER J. COX  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil, Gas and Mining

JOHN R. BAZA  
Division Director

## UNDERGROUND INJECTION CONTROL PERMIT

Cause No. UIC-372

**Operator:** Newfield Production Company  
**Well:** Ashley Federal 14-13-9-15  
**Location:** Section 13, Township 9 South, Range 15 East  
**County:** Duchesne  
**API No.:** 43-013-32669  
**Well Type:** Enhanced Recovery (waterflood)

### Stipulations of Permit Approval

1. Approval for conversion to Injection Well issued on March 31, 2011.
2. Maximum Allowable Injection Pressure: 2,000 psig
3. Maximum Allowable Injection Rate: (restricted by pressure limitation)
4. Injection Interval: Green River Formation (3,925' – 5,931')
5. Any subsequent wells drilled within a ½ mile radius of this well shall have production casing cement brought up to or above the top of the unitized interval for the Greater Monument Butte Unit.

Approved by:

  
John Rogers

Associate Director

10/27/2014  
Date

JR/MLR/js

cc: Bruce Suchomel, Environmental Protection Agency  
Bureau of Land Management, Vernal  
Jill Loyle, Newfield Production Company, Denver  
Newfield Production Company, Myton  
Duchesne County  
Well File

N:\O&G Reviewed Docs\ChronFile\UIC\Newfield







GARY R. HERBERT  
Governor

GREGORY S. BELL  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil, Gas and Mining

JOHN R. BAZA  
Division Director

March 31, 2011

Newfield Production Company  
1001 Seventeenth Street, Suite 2000  
Denver, CO 80202

Subject: Greater Monument Butte Unit Well: Ashley Federal 14-13-9-15, Section 13, Township 9 South, Range 15 East, SLBM, Duchesne County, Utah, API Well # 43-013-32669

Gentlemen:

Pursuant to Utah Admin. Code R649-5-3-3, the Division of Oil, Gas and Mining (the "Division") issues its administrative approval for conversion of the referenced well to a Class II injection well. Accordingly, the following stipulations shall apply for full compliance with this approval:

1. Compliance with all applicable requirements for the operation, maintenance and reporting for Underground Injection Control ("UIC") Class II injection wells pursuant to Utah Admin. Code R649-1 et seq.
2. Conformance with all conditions and requirements of the complete application submitted by Newfield Production Company.
3. A casing\tubing pressure test shall be conducted prior to commencing injection.
4. Pressure shall be monitored between the surface casing and the production casing on a regular basis. Any pressure changes observed shall be reported to the Division immediately.

A final approval to commence injection will be issued upon satisfactory completion of the listed stipulations. If you have any questions regarding this approval or the necessary requirements, please contact Mark Reinbold at 801-538-5333 or Brad Hill at 801-538-5315.

Sincerely,

John Rogers  
Associate Director

JR/MLR/js

cc: Bruce Suchomel, Environmental Protection Agency  
Bureau of Land Management, Vernal  
Duchesne County  
Newfield Production Company, Myton  
Well File

N:\O&G Reviewed Docs\ChronFile\UIC\Newfield





**DIVISION OF OIL, GAS AND MINING  
UNDERGROUND INJECTION CONTROL PROGRAM  
PERMIT  
STATEMENT OF BASIS**

**Applicant:** Newfield Production Company      **Well:** Ashley Federal 14-13-9-15

**Location:** 13/9S/15E      **API:** 43-013-32669

**Ownership Issues:** The proposed well is located on BLM land. The well is located in the Greater Monument Butte Unit. Lands in the one-half mile radius of the well are administered by the BLM. The Federal Government is the mineral owner within the area of review (AOR). Newfield and other various individuals hold the leases in the unit. Newfield has provided a list of all surface, mineral and lease holders in the half-mile radius. Newfield is the operator of the Greater Monument Butte Unit. Newfield has submitted an affidavit stating that all owners and interest owners have been notified of their intent.

**Well Integrity:** The proposed well has surface casing set at 314 feet and has a cement top at the surface. A 5½ inch production casing is set at 5,977 feet. The cement bond log is somewhat problematic, but it demonstrates adequate bond in this well up to about 2,905 feet or higher. A 2 7/8 inch tubing with a packer will be set at 3,956 feet. Higher perforations will be opened at a later date. A mechanical integrity test will be run on the well prior to injection. At the time of this revision (9/30/2014), based on surface locations, there are 10 producing wells, 8 injection wells, and 1 shut-in well (the proposed injection well) in the AOR. Two of the producing wells are directionally drilled, with surface locations inside the AOR and bottom hole locations outside the AOR. Additionally, there is 1 currently approved surface location inside the AOR for a directional well with a bottom hole location outside the AOR. All of the existing wells have evidence of adequate casing and cement.

**Ground Water Protection:** As interpreted from the Utah Geological Survey's DOE Project-Uinta Basin Water Draft Map (Paul B. Anderson, December 2, 2011), the base of moderately saline water (3000-10,000 mg/l TDS) is at a depth of approximately 1900 feet. Injection shall be limited to the interval between 3,925 feet and 5,931 feet in the Green River Formation. Information submitted by Newfield indicates that the fracture gradient for the 14-13-9-15 well is 0.87 psi/ft., which was the lowest reported fracture gradient for the injection zone. The resulting minimum fracture pressure for the proposed injection interval is 2,000 psig. The requested maximum pressure is 2,000 psig. We intend to permit this well at a maximum pressure of 2,000 psig. The anticipated average injection pressure is 1100 psig. Injection at this pressure should not initiate any new fractures or propagate existing fractures in the adjacent confining intervals. Any ground water present should be adequately protected.

**Ashley Federal 14-13-9-15**

**page 2**

**Oil/Gas& Other Mineral Resources Protection:** The Board of Oil, Gas & Mining approved the Greater Monument Butte Unit on December 1, 2009. Correlative rights issues were addressed at this time. Previous reviews in this area indicate that other mineral resources in the area have been protected or are not at issue.

**Bonding:** Bonded with the BLM

**Actions Taken and Further Approvals Needed:** A notice of agency action has been sent to the Salt Lake Tribune and the Uinta Basin Standard. A casing/tubing pressure test will be required prior to injection. It is recommended that approval of this application be granted.

Note: Applicable technical publications concerning water resources in the general vicinity of this project have been reviewed and taken into consideration during the permit review process.

Reviewer(s): Mark Reinbold

Date: 3/1/2011 (revised 9/30/2014)

PROOF OF PUBLICATION

CUSTOMER'S COPY

CUSTOMER NAME AND ADDRESS	ACCOUNT NUMBER	DATE
DIV OF OIL-GAS & MINING, 1594 W NORTH TEMP #1210 P.O. BOX 145801 SALT LAKE CITY, UT 84114	9001402352	3/1/2011

ACCOUNT NAME	
DIV OF OIL-GAS & MINING,	
TELEPHONE	ADORDER# / INVOICE NUMBER
8015385340	0000667853 /
SCHEDULE	
Start 02/28/2011	End 02/28/2011
CUST. REF. NO.	
Cause # UIC-372	
CAPTION	
BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT OF NATURAL RESOURCES	
SIZE	
82 Lines	2.00 COLUMN
TIMES	RATE
3	
MISC. CHARGES	AD CHARGES
TOTAL COST	
210.00	

AFFIDAVIT OF PUBLICATION

AS NEWSPAPER AGENCY COMPANY, LLC dba MEDIAONE OF UTAH LEGAL BOOKER, I CERTIFY THAT THE ATTACHED ADVERTISEMENT OF **BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT OF NATURAL RESOURCES STATE OF UTAH NOTICE OF AGENCY ACTION CAUSE NO. UIC-372 IN THE MATTER OF THE APPLICATION FOR DIV OF OIL-GAS & MINING**, WAS PUBLISHED BY THE NEWSPAPER AGENCY COMPANY, LLC dba MEDIAONE OF UTAH, AGENT FOR THE SALT LAKE TRIBUNE AND DESERET NEWS, DAILY NEWSPAPERS PRINTED IN THE ENGLISH LANGUAGE WITH GENERAL CIRCULATION IN UTAH, AND PUBLISHED IN SALT LAKE CITY, SALT LAKE COUNTY IN THE STATE OF UTAH. NOTICE IS ALSO POSTED ON UTAHLEGALS.COM ON THE SAME DAY AS THE FIRST NEWSPAPER PUBLICATION DATE AND REMAINS ON UTAHLEGALS.COM INDEFINITELY.

PUBLISHED ON Start 02/28/2011 End 02/28/2011

SIGNATURE

*Bobby Taylor*

3/1/2011

VIRGINIA CRAFT  
Notary Public, State of Utah  
Commission # 531469  
My Commission Expires  
January 12, 2014

*Virginia Craft*

**THIS IS NOT A STATEMENT BUT A "PROOF OF PUBLICATION"**  
**PLEASE PAY FROM BILLING STATEMENT**

BEFORE THE DIVISION OF OIL, GAS AND MINING  
DEPARTMENT OF NATURAL RESOURCES  
STATE OF UTAH  
NOTICE OF AGENCY ACTION  
CAUSE NO. UIC-372

IN THE MATTER OF THE APPLICATION OF NEWFIELD PRODUCTION COMPANY FOR ADMINISTRATIVE APPROVAL OF CERTAIN WELLS LOCATED IN SECTIONS 13, 14, AND 15 TOWNSHIP 9 SOUTH, RANGE 15 EAST, AND SECTION 1, TOWNSHIP 9 SOUTH, RANGE 16 EAST, DUCHESNE COUNTY, UTAH, AS CLASS II INJECTION WELLS.

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.

Notice is hereby given that the Division of Oil, Gas and Mining (the "Division") is commencing an informal adjudicative proceeding to consider the application of Newfield Production Company for administrative approval of the following wells located in Duchesne County, Utah, for conversion to Class II injection wells:

Greater Monument Butte Unit:  
Ashley Federal 2-13-9-15 well located in NW/4 NE/4, Section 13, Township 9 South, Range 15 East  
Ashley Federal 4-13-9-15 well located in NW/4 NE/4, Section 13, Township 9 South, Range 15 East  
Ashley Federal 6-13-9-15 well located in SE/4 NW/4, Section 13, Township 9 South, Range 15 East  
Ashley Federal 8-13-9-15 well located in SE/4 NE/4, Section 13, Township 9 South, Range 15 East  
Ashley Federal 10-13-9-15 well located in NW/4 SE/4, Section 13, Township 9 South, Range 15 East  
Ashley Federal 12-13-9-15 well located in NW/4 SW/4, Section 13, Township 9 South, Range 15 East  
Ashley Federal 14-13-9-15 well located in SE/4 SW/4, Section 13, Township 9 South, Range 15 East  
Ashley Federal 16-13-9-15 well located in SE/4 SE/4, Section 13, Township 9 South, Range 15 East  
Ashley Federal 2-14-9-15 well located in NW/4 NE/4, Section 14, Township 9 South, Range 15 East  
Ashley Federal 4-14-9-15 well located in NW/4 NW/4, Section 14, Township 9 South, Range 15 East  
Ashley Federal 6-14-9-15 well located in SE/4 NE/4, Section 14, Township 9 South, Range 15 East  
Ashley Federal 8-14-9-15 well located in SE/4 SE/4, Section 14, Township 9 South, Range 15 East  
Ashley Federal 10-14-9-15 well located in NW/4 NE/4, Section 15, Township 9 South, Range 15 East  
Ashley Federal 12-14-9-15 well located in NW/4 SW/4, Section 15, Township 9 South, Range 15 East  
Ashley Federal 14-14-9-15 well located in SE/4 SW/4, Section 15, Township 9 South, Range 15 East  
Ashley Federal 16-14-9-15 well located in SE/4 SE/4, Section 15, Township 9 South, Range 15 East

The proceeding will be conducted in accordance with Utah Admin. R649-10, Administrative Procedures.

Selected zones in the Green River Formation will be used for water injection. The maximum requested injection pressures and rates will be determined based on fracture gradient information submitted by Newfield Production Company.

Any person desiring to object to the application or otherwise intervene in the proceeding, must file a written protest or notice of intervention with the Division within fifteen days following publication of this notice. The Division's Presiding Officer for the proceeding is Brad Hill, Permitting Manager, at P.O. Box 145801, Salt Lake City, UT 84114-5801, phone number (801) 338-5340. If such a protest or notice of intervention is received, a hearing will be scheduled in accordance with the aforementioned administrative procedural rules. Protestants and/or intervenors should be prepared to demonstrate at the hearing how this matter affects their interests.

Dated this 23rd day of February, 2011.

STATE OF UTAH  
DIVISION OF OIL, GAS & MINING  
/s/ Brad Hill  
Brad Hill  
Permitting Manager

667853 UPAXLP

# AFFIDAVIT OF PUBLICATION

County of Duchesne,  
STATE OF UTAH


I, Geoff Liesik on oath, say that I am the EDITOR of the Uintah Basin Standard, a weekly newspaper of general circulation, published at Roosevelt, State and County aforesaid, and that a certain notice, a true copy of which is hereto attached, was published in the full issue such newspaper for 1 consecutive issues, and that the first publication was on the 1 day of March, 2011, and that the last publication of such notice was in the issue of such newspaper dated the 1 day of March, 2011, and that said notice was published on Utahlegals.com on the same day as the first newspaper publication and the notice remained on Utahlegals.com until the end of the scheduled run.

Geoff Liesik  
Editor

Subscribed and sworn to before me this

2 day of March, 2011

Bonnie Parrish  
Notary Public



## NOTICE OF AGENCY ACTION CAUSE NO. UIC-372

BEFORE THE DIVISION OF OIL, GAS AND MINING

DEPARTMENT OF NATURAL RESOURCES, STATE OF UTAH

IN THE MATTER OF THE APPLICATION OF NEWFIELD PRODUCTION COMPANY FOR ADMINISTRATIVE APPROVAL OF CERTAIN WELLS LOCATED IN SECTIONS 13, 14, AND 15 TOWNSHIP 9 SOUTH, RANGE 15 EAST, AND SECTION 1, TOWNSHIP 9 SOUTH, RANGE 16 EAST, DUCHESNE COUNTY, UTAH, AS CLASS II INJECTION WELLS.

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.

Notice is hereby given that the Division of Oil, Gas and Mining (the "Division") is commencing an informal adjudicative proceeding to consider the application of Newfield Production Company for administrative approval of the following

wells located in Duchesne County, Utah, for conversion to Class II injection wells:

Greater Monument Butte Unit:

Ashley Federal 2-13-9-15 well located in NW/4 NE/4, Section 13, Township 9 South, Range 15 East

Ashley Federal 4-13-9-15 well located in NW/4 NW/4, Section 13, Township 9 South, Range 15 East

Ashley Federal 6-13-9-15 well located in SE/4 NW/4, Section 13, Township 9 South, Range 15 East

Ashley Federal 8-13-9-15 well located in SE/4 NE/4, Section 13, Township 9 South, Range 15 East

Ashley Federal 10-13-9-15 well located in NW/4 SE/4, Section 13, Township 9 South, Range 15 East

Ashley Federal 12-13-9-15 well located in NW/4 SW/4, Section 13, Township 9 South, Range 15 East

Ashley Federal 14-13-9-15 well located in SE/4 SW/4, Section 13, Township 9 South, Range 15 East

Ashley Federal 16-13-9-15 well located in SE/4 SE/4, Section 13, Township 9 South, Range 15 East

Ashley Federal 2-14-9-15 well located in NW/4 NE/4, Section 14, Township 9 South, Range 15 East

Ashley Federal 4-14-9-15 well located in NW/4 NW/4, Section 14, Township 9 South, Range 15 East

Ashley Federal 8-14-9-15 well located in SE/4 NE/4, Section 14, Township 9 South, Range 15 East

Ashley Federal 16-14-9-15 well located in SE/4 SE/4, Section 14, Township 9 South, Range 15 East

Ashley Federal 2-15-9-15 well located in NW/4 NE/4, Section 15, Township 9 South, Range 15 East

Monument Butte 1-23 well located in NE/4 SW/4, Section 1, Township 9 South, Range 16 East

The proceeding will be conducted in accordance with Utah Admin. R649-10 Administrative

BEFORE THE DIVISION OF OIL, GAS AND MINING  
DEPARTMENT OF NATURAL RESOURCES  
STATE OF UTAH  
NOTICE OF AGENCY ACTION  
CAUSE NO. UIC-372

IN THE MATTER OF THE APPLICATION OF NEWFIELD PRODUCTION COMPANY FOR ADMINISTRATIVE APPROVAL OF CERTAIN WELLS LOCATED IN SECTIONS 13, 14, AND 15 TOWNSHIP 9 SOUTH, RANGE 15 EAST, AND SECTION 1, TOWNSHIP 9 SOUTH, RANGE 16 EAST, DUCHESNE COUNTY, UTAH, AS CLASS II INJECTION WELLS.

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.

Notice is hereby given that the Division of Oil, Gas and Mining (the "Division") is commencing an informal adjudicative proceeding to consider the application of Newfield Production Company for administrative approval of the following wells located in Duchesne County, Utah, for conversion to Class II injection wells:

Greater Monument Butte Unit:

Ashley Federal 2-13-9-15 well located in NW/4 NE/4, Section 13, Township 9 South, Range 15 East  
Ashley Federal 4-13-9-15 well located in NW/4 NW/4, Section 13, Township 9 South, Range 15 East  
Ashley Federal 6-13-9-15 well located in SE/4 NW/4, Section 13, Township 9 South, Range 15 East  
Ashley Federal 8-13-9-15 well located in SE/4 NE/4, Section 13, Township 9 South, Range 15 East  
Ashley Federal 10-13-9-15 well located in NW/4 SE/4, Section 13, Township 9 South, Range 15 East  
Ashley Federal 12-13-9-15 well located in NW/4 SW/4, Section 13, Township 9 South, Range 15 East  
Ashley Federal 14-13-9-15 well located in SE/4 SW/4, Section 13, Township 9 South, Range 15 East  
Ashley Federal 16-13-9-15 well located in SE/4 SE/4, Section 13, Township 9 South, Range 15 East  
Ashley Federal 2-14-9-15 well located in NW/4 NE/4, Section 14, Township 9 South, Range 15 East  
Ashley Federal 4-14-9-15 well located in NW/4 NW/4, Section 14, Township 9 South, Range 15 East  
Ashley Federal 8-14-9-15 well located in SE/4 NE/4, Section 14, Township 9 South, Range 15 East  
Ashley Federal 16-14-9-15 well located in SE/4 SE/4, Section 14, Township 9 South, Range 15 East  
Ashley Federal 2-15-9-15 well located in NW/4 NE/4, Section 15, Township 9 South, Range 15 East  
Monument Butte 1-23 well located in NE/4 SW/4, Section 1, Township 9 South, Range 16 East


The proceeding will be conducted in accordance with Utah Admin. R649-10, Administrative Procedures.

Selected zones in the Green River Formation will be used for water injection. The maximum requested injection pressures and rates will be determined based on fracture gradient information submitted by Newfield Production Company.

Any person desiring to object to the application or otherwise intervene in the proceeding, must file a written protest or notice of intervention with the Division within fifteen days following publication of this notice. The Division's Presiding Officer for the proceeding is Brad Hill, Permitting Manager, at P.O. Box 145801, Salt Lake City, UT 84114-5801, phone number (801) 538-5340. If such a protest or notice of intervention is received, a hearing will be scheduled in accordance with the aforementioned administrative procedural rules. Protestants and/or interveners should be prepared to demonstrate at the hearing how this matter affects their interests.

Dated this 23rd day of February, 2011.

STATE OF UTAH  
DIVISION OF OIL, GAS & MINING

  
\_\_\_\_\_  
Brad Hill  
Permitting Manager



**Newfield Production Company**

**ASHLEY FEDERAL 2-13-9-15, ASHLEY FEDERAL 4-13-9-15,  
ASHLEY FEDERAL 6-13-9-15, ASHLEY FEDERAL 8-13-9-15,  
ASHLEY FEDERAL 10-13-9-15, ASHLEY FEDERAL 12-13-9-15,  
ASHLEY FEDERAL 14-13-9-15, ASHLEY FEDERAL 16-13-9-15,  
ASHLEY FEDERAL 2-14-9-15, ASHLEY FEDERAL 4-14-9-15,  
ASHLEY FEDERAL 8-14-9-15, ASHLEY FEDERAL 16-14-9-15,  
ASHLEY FEDERAL 2-15-9-15, MONUMENT BUTTE 1-23**

**Cause No. UIC-372**

Publication Notices were sent to the following:

Newfield Production Company  
1001 17th Street, Suite 2000  
Denver, CO 80202

Uintah Basin Standard  
268 South 200 East  
Roosevelt, UT 84066  
via e-mail [ubs@ubstandard.com](mailto:ubs@ubstandard.com)

Salt Lake Tribune  
P O Box 45838  
Salt Lake City, UT 84145  
via e-mail [naclegal@mediaoneutah.com](mailto:naclegal@mediaoneutah.com)

Vernal Office  
Bureau of Land Management  
170 South 500 East  
Vernal, UT 84078

Duchesne County Planning  
P O Box 317  
Duchesne, UT 84021-0317

Bruce Suchomel  
US EPA Region 8  
MS 8P-W-GW  
1595 Wynkoop Street  
Denver, CO 80202-1129

SITLA  
675 East 500 South  
Salt Lake City, UT 84102-2818

Newfield Production Company  
Rt 3 Box 3630  
Myton, UT 84052

  
\_\_\_\_\_





GARY R. HERBERT  
Governor

GREGORY S. BELL  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil, Gas and Mining

JOHN R. BAZA  
Division Director

February 24, 2011

Via e-mail: [legals@ubstandard.com](mailto:legals@ubstandard.com)

Uintah Basin Standard  
268 South 200 East  
Roosevelt, UT 84066

Subject: Notice of Agency Action – Newfield Production Company Cause No. UIC-372

To whom it may concern:

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please notify me via e-mail of the date it will be published. My e-mail address is: [jsweet@utah.gov](mailto:jsweet@utah.gov).

Please send proof of publication and billing to:

Division of Oil, Gas and Mining  
PO Box 145801  
Salt Lake City, UT 84114-5801

Sincerely,

Jean Sweet  
Executive Secretary

Enclosure





GARY R. HERBERT  
Governor

GREGORY S. BELL  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil, Gas and Mining

JOHN R. BAZA  
Division Director

February 24, 2011

Via e-mail: [naclegal@mediaoneutah.com](mailto:naclegal@mediaoneutah.com)

Salt Lake Tribune  
P. O. Box 45838  
Salt Lake City, UT 84145

Subject: Notice of Agency Action – Newfield Production Company Cause No. UIC-372

To whom it may concern:

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please notify me via e-mail of the date it will be published. My e-mail address is: [jsweet@utah.gov](mailto:jsweet@utah.gov).

Please send proof of publication and billing for **account #9001402352** to:

Division of Oil, Gas and Mining  
PO Box 145801  
Salt Lake City, UT 84114-5801

Sincerely,

Jean Sweet  
Executive Secretary

Enclosure



**Jean Sweet - RE: Notice of Agency Action - Newfield Production Company Cause No. UIC-372**

---

**From:** "NAC Legal" <naclegal@mediaoneutah.com>  
**To:** "Jean Sweet" <jsweet@utah.gov>  
**Date:** 2/24/2011 12:22 PM  
**Subject:** RE: Notice of Agency Action - Newfield Production Company Cause No. UIC-372

---

Ad #667853 is scheduled to run February 28th in Salt Lake Tribune and Online  
utahlegals.com .

Total charge is \$210.00. Please check the ad in the paper.

Thank you,

Lynn Valdez

MediaOne of Utah,

a Newspaper Agency Company

4770 South 5600 West

West Valley City, Utah 84118

Ph.: 801-204-6245

Email: naclegal@mediaoneutah.com

---

**From:** Jean Sweet [mailto:jsweet@utah.gov]  
**Sent:** Thursday, February 24, 2011 11:28 AM  
**To:** naclegal@mediaoneutah.com



February 9, 2011

Mr. Dan Jarvis  
State of Utah  
Division of Oil, Gas and Mining  
Post Office Box 145801  
Salt Lake City, Utah 84114-5801

RE: Permit Application for Water Injection Well  
Ashley Federal #14-13-9-15  
Monument Butte Field, Lease #UTU-68548  
Section 13-Township 9S-Range 15E  
Duchesne County, Utah

Dear Mr. Jarvis:

Newfield Production Company herein requests approval to convert the Ashley Federal #14-13-9-15 from a producing oil well to a water injection well in the Monument Butte (Green River) Field.

I hope you find this application complete; however, if you have any questions or require additional information, please contact me at (303) 893-0102.

Sincerely,

A handwritten signature in black ink, appearing to read "Eric Sundberg". The signature is fluid and cursive, with a long horizontal stroke extending to the right.

Eric Sundberg  
Regulatory Lead

RECEIVED

FEB 10 2011


DIV. OF OIL, GAS & MINING

**NEWFIELD PRODUCTION COMPANY**  
**APPLICATION FOR APPROVAL OF CLASS II INJECTION WELL**  
**ASHLEY FEDERAL #14-13-9-15**  
**MONUMENT BUTTE FIELD (GREEN RIVER) FIELD**  
**LEASE #UTU-68548**  
**FEBRUARY 9, 2011**

## TABLE OF CONTENTS

LETTER OF INTENT	
COVER PAGE	
TABLE OF CONTENTS	
UIC FORM 1 – APPLICATION FOR INJECTION WELL	
WELLBORE DIAGRAM OF PROPOSED INJECTION	
WORK PROCEDURE FOR INJECTION CONVERSION	
COMPLETED RULE R615-5-1 QUESTIONNAIRE	
COMPLETED RULE R615-5-2 QUESTIONNAIRE	
ATTACHMENT A	ONE-HALF MILE RADIUS MAP
ATTACHMENT A-1	WELL LOCATION PLAT
ATTACHMENT B	LIST OF SURFACE OWNERS WITHIN ONE-HALF MILE RADIUS
ATTACHMENT C	CERTIFICATION FOR SURFACE OWNER NOTIFICATION
ATTACHMENT E	WELLBORE DIAGRAM – ASHLEY FEDERAL #14-13-9-15
ATTACHMENT E-1	WELLBORE DIAGRAM – ASHLEY FEDERAL #10-13-9-15
ATTACHMENT E-2	WELLBORE DIAGRAM – ASHLEY FEDERAL #11-13-9-15
ATTACHMENT E-3	WELLBORE DIAGRAM – ASHLEY FEDERAL #12-13-9-15
ATTACHMENT E-4	WELLBORE DIAGRAM – ASHLEY FEDERAL #13-13-9-15
ATTACHMENT E-5	WELLBORE DIAGRAM – ASHLEY FEDERAL #16-13-9-15
ATTACHMENT E-6	WELLBORE DIAGRAM – ASHLEY FEDERAL #15-13-9-15
ATTACHMENT E-7	WELLBORE DIAGRAM – ASHLEY FEDERAL #16-14-9-15
ATTACHMENT E-8	WELLBORE DIAGRAM – ASHLEY FEDERAL #2-24-9-15
ATTACHMENT E-9	WELLBORE DIAGRAM – ASHLEY FEDERAL #4-24-9-15
ATTACHMENT E-10	WELLBORE DIAGRAM – ASHLEY FEDERAL #3-24-9-15
ATTACHMENT E-11	WELLBORE DIAGRAM – ASHLEY FEDERAL #6-24-9-15
ATTACHMENT E-12	WELLBORE DIAGRAM – ASHLEY #6-13-9-16
ATTACHMENT F	WATER ANALYSIS
ATTACHMENT G	FRACTURE GRADIENT CALCULATIONS
ATTACHMENT G-1	FRACTURE REPORTS DATED – 9/16/05 – 9/25/05
ATTACHMENT H	WORK PROCEDURE FOR PROPOSED PLUG AND ABANDON
ATTACHMENT H-1	WELLBORE DIAGRAM OF PROPOSED PLUGGED WELL

## APPLICATION FOR INJECTION WELL - UIC FORM 1

Well Name and number: Ashley Federal #16-13-9-15	
Field or Unit name: Monument Butte (Green River)	Lease No. UTU-68548
Well Location: QQ SE/SW section 13 township 9S range 15E county Duchesne	
Is this application for expansion of an existing project? Yes [ X ] No [ ]	
Will the proposed well be used for: Enhanced Recovery? Yes [ X ] No [ ]	
Disposal? Yes [ ] No [ X ]	
Storage? Yes [ ] No [ X ]	
Is this application for a new well to be drilled? Yes [ ] No [ X ]	
If this application is for an existing well, has a casing test been performed on the well? Yes [ ] No [ X ]	
Date of test: _____	
API number: 43-013-32669	
Proposed injection interval: from 3925 to 5931	
Proposed maximum injection: rate 500 bpd pressure 2000 psig	
Proposed injection zone contains [ x ] oil, [ ] gas, and/or [ ] fresh water within 1/2 mile of the well.	
IMPORTANT: Additional information as required by R615-5-2 should accompany this form.	
List of Attachments: Attachments "A" through "H-1"	
I certify that this report is true and complete to the best of my knowledge.	
Name: Eric Sundberg	Signature: 
Title: Regulatory Lead	Date: 2/19/11
Phone No. (303) 893-0102	
(State use only)	
Application approved by _____	Title _____
Approval Date _____	
Comments:	

# Ashley Federal 14-13-9-15

Spud Date: 7/27/05  
Put on Production: 9/24/05  
GL: 6158' KB: 6170'

Initial Production: 46 BOPD,  
32 MCFD, 92 BWPD

## Proposed Injection Wellbore Diagram

### SURFACE CASING

CSG SIZE: 8 5/8"  
GRADE: J-55  
WEIGHT: 24#  
LENGTH: 7 jts. (304.2')  
DEPTH LANDED: 314.2' KB  
HOLE SIZE: 12 1/4"  
CEMENT DATA: 160 sks Class G Mix. Est 4 bbls cement to pit

### PRODUCTION CASING

CSG SIZE: 5 1/2"  
GRADE: J-55  
WEIGHT: 15.5#  
LENGTH: 136 jts. (5978.71')  
DEPTH LANDED: 5976.71' KB  
HOLE SIZE: 7 7/8"  
CEMENT DATA: 300 sks Prem. Lite II mixed & 450 sks 50/50 POZ mix.  
CEMENT TOP AT: 91'

### TUBING

SIZE/GRADE/WT.: 2 7/8" / J-55 / 6.5#  
NO. OF JOINTS: 156 jts (4858.15")  
TUBING ANCHOR: 4870.15' KB  
NO. OF JOINTS: 1 jts (31.05')  
SEATING NIPPLE: 2 7/8" (1.10')  
SN LANDED AT: 4904.00' KB  
NO. OF JOINTS: 2 jts (62.38')  
TOTAL STRING LENGTH: 4967.93' w/ 12' KB

### FRAC JOB

9/19/05 4828'-4900'	<b>Frac B.5 &amp; 2 sands as follows:</b> 59,638#'s of 20/40sand in 476 bbls lightning 17 frac fluid. Treated @ avg press of 1690, w/avg rate of 25 bpm. ISIP 2300 psi. Calc flush: 4826 gal. Actual flush: 4872 gal.
9/19/05 4754'-4762'	<b>Frac C sands as follows:</b> 49,648#'s of 20/40 sand in 418 bbls lightning 17 frac fluid. Treated @ avg press of 2308, w/avg rate of 28.5 bpm. ISIP 3650 psi. Calc flush: 4752 gal. Actual flush: 4788 gal.
9/19/05 4672'-4678'	<b>Frac D2 sands as follows:</b> 60,644#'s of 20/40 sand in 323 bbls lightning 17 frac fluid. Treated @ avg press of 1910, w/avg rate of 25.1 bpm. ISIP 2030 psi. Calc flush: 4670 gal. Actual flush: 4662 gal.
9/19/05 4006'-4024'	<b>Frac GB2 sands as follows:</b> 84,673#'s of 20/40 sand in 583 bbls lightning 17 frac fluid. Treated @ avg press of 1903, w/avg rate of 25 bpm. ISIP 2610 psi. Calc flush: 4004 gal. Actual flush: 3906 gal.
02/08/06	Pump Change. Update tubing and rod details.
05/29/08	Production log. Updated rod and tubing detail
4/28/09	RTP . Updated r & t details.



### PERFORATION RECORD

9/19/05	4894'-4900'	4 JSPF	24 holes
9/19/05	4828'-4832'	4 JSPF	16 holes
9/19/05	4754'-4762'	4 JSPF	32 holes
9/19/05	4672'-4678'	4 JSPF	24 holes
9/19/05	4006'-4024'	4 JSPF	72 holes

**NEWFIELD**

Ashley Federal 14-13-9-15  
758' FSL & 2020' FWL  
SE/SW Section 13-T9S-R15E  
Duchesne Co, Utah  
API #43-013-32669; Lease #UTU-68548



## **WORK PROCEDURE FOR INJECTION CONVERSION**

1. Rig up hot oil truck to casing. Pump water. Unseat pump. Flush rods. Trip out of hole with rods and pump.
2. Trip out of hole with tubing, breaking and doping every connection. Trip in hole with packer and tubing. Rig up water truck to casing. Pump packer fluid. Set packer.
3. Test casing and packer.
4. Rig down and move out.

**REQUIREMENTS FOR INJECTION OF FLUIDS INTO RESERVOIRS  
RULE R615-5-1**

- 1. Operations to increase ultimate recovery, such as cycling of gas, the maintenance of pressure, the introduction of gas, water or other substances into a reservoir for the purpose of secondary or other enhanced recovery or for storage and the injection of water into any formation for the purpose of water disposal shall be permitted only by order of the Board after notice and hearing.**
- 2. A request for agency action for authority for the injection of gas, liquified petroleum gas, air, water or any other medium into any formation for any reason, including but not necessarily limited to the establishment of or the expansion of waterflood projects, enhanced recovery projects, and pressure maintenance projects shall contain:**

**2.1 The name and address of the operator of the project.**

Newfield Production Company  
1001 17<sup>th</sup> Street, Suite 2000  
Denver, Colorado 80202

**2.2 A plat showing the area involved and identifying all wells, including all proposed injection wells, in the project area and within one-half mile of the project area.**

See Attachment A.

**2.3 A full description of the particular operation for approval is requested.**

Approval is requested to convert the Ashley Federal #14-13-9-15 from a producing oil well to a water injection well in Monument Butte (Green River) Field.

**2.4 A description of the pools from which the identified wells are producing or have produced.**

The proposed injection well will inject into the Green River Formation.

**2.5 The names, description and depth of the pool or pools to be affected.**

The injection zone is in the Green River Formation. For the Ashley Federal #14-13-9-15 well, the proposed injection zone is from Garden Gulch to Basal Carbonate (3925' - 5931'). The confining strata directly above and below the injection zones are the Garden Gulch and the top of the Wasatch Formation or TD, which ever is shallower. The Garden Gulch Marker top is at 3588' and the TD is at 5985'.

**2.6 A copy of a log of a representative well completed in the pool.**

The referenced log for the Ashley Federal #14-13-9-15 is on file with the Utah Division of Oil, Gas and Mining.

- 2.7 A statement as to the type of fluid to be used for injection, its source and the estimated amounts to be injected daily.**

The primary type and source of fluid to be used for injection will be culinary water commingled with produced water. The average estimated injection of fluids will be at a rate of 300 BPD, and the estimated maximum injection will be at a rate of 500 BPD.

- 2.8 A list of all operators and surface owners within one-half mile radius of the proposed project.**

See Attachment B.

- 2.9 An affidavit certifying that said operators or owners and surface owners within a one-half mile radius have been provided a copy of the petition for injection.**

See Attachment C.

- 2.10 Any additional information the Board may determine is necessary to adequately review the petition.**

Newfield Production Company will supply any additional information requested by the Utah Division of Oil, Gas and Mining.

- 4.0 Establish recovery projects may be expanded and additional wells placed on injection only upon authority from the Board after notice and hearing or by administrative approval.**

This proposed injection well is on a Federal lease (Lease #UTU-68548) in the Monument Butte Federal (Green River) Field, and this request is for administrative approval.

**REQUIREMENTS FOR CLASS II INJECTION WELLS INCLUDING WATER DISPOSAL,  
STORAGE AND ENHANCED RECOVERY WELLS  
SECTION V – RULE R615-5-2**

- 1. Injection well shall be completed, equipped, operated, and maintained in a manner that will prevent pollution and damage to any USDW, or other resources and will confine injected fluids to the interval approved.**
- 2. The application for an injection well shall include a properly completed Form DOGM-UIC-1 and the following:**
  - 2.1 A plat showing the location of the injection well, all abandoned or active wells within a one-half mile radius of the proposed wells, and the surface owner and the operator of any lands or producing leases, respectively, within a one-half mile radius of the proposed injection well.**

See Attachments A and B.
  - 2.2 Copies of electrical or radioactive logs, including gamma ray logs, for the proposed well run prior to the installation of casing and indicating resistivity, spontaneous potential, caliper and porosity.**

All logs are on file with the Utah Division of Oil, Gas and Mining.
  - 2.3 A copy of a cement bond or comparable log run for the proposed injection well after casing was set and cemented.**

A copy of the cement bond log is on file with the Utah Division of Oil, Gas and Mining.
  - 2.4 Copies of logs already on file with the Division should be referenced, but need not be refiled.**

All copies of logs are on file with the Utah Division of Oil, Gas and Mining.
  - 2.5 A description of the casing or proposed casing program of the injection well and of the proposed method for testing the casing before use of the well.**

The casing program is 8-5/8", 24# surface casing run to 314' KB, and 5-1/2", 15.5# casing run from surface to 5977' KB. A casing integrity test will be conducted at the time of conversion. See Attachment E.
  - 2.6 A statement as to the type of fluid to be used for injection, its source and estimated amounts to be injected daily.**

The primary type and source of fluid to be used for injection will be culinary water commingled with produced water. The estimated average rate of injection will be 300 BPD, and the estimated maximum rate of injection will be 500 BPD.
  - 2.7 Standard laboratory analysis of the fluid to be injected, the fluid in the formation into which the fluid is being injected, and the compatibility of the fluids.**

See Attachment F.

**The proposed average and maximum injection pressures.**

The proposed average injection pressure will be approximately 1100 psig and the maximum injection pressure will not exceed 2000 psig.

- 2.8 Evidence and data to support a finding that the proposed injection well will not initiate fractures through the overlying strata or a confining interval that could enable the injected fluid or formation fluid to enter the fresh water strata.**

The minimum fracture gradient for the Ashley Federal #14-13-9-15, for existing perforations (4006' - 4900') calculates at 0.87 psig/ft. The maximum injection pressures will be limited so as not to exceed this gradient. A step rate test will be performed periodically to ensure we are below parting pressure. The proposed maximum injection pressure is 2000 psig. We may add additional perforations between 3588' and 5985'. See Attachments G and G-1.

- 2.9 Appropriate geological data on the injection interval and confining beds, including the geologic name, lithologic description, thickness, depth, and lateral extent.**

In the Ashley Federal #14-13-9-15, the proposed injection zone (3925' - 5931') is in the Garden Gulch to the Basal Carbonate of the Green River Formation. The reservoir is a very fine-grained sandstone with minor imbedded shale streaks. The estimated porosity is 13%. The members are composed of porous and permeable lenticular calcareous sandstone and low porosity carbonates and calcareous shale. The porous and lenticular sandstone varies in thickness from 0-31' and is confined to the Monument Butte Federal Field. Outside the Monument Butte Federal Field, the sandstone is composed of tight, very fine, silty, calcareous sandstone, less than 3' thick. The stratum confining the injection zone is composed of tight, moderately calcareous, sandy lacustrine shale. All of the confining strata are impermeable, and will effectively seal off the oil, gas, and water of the injection zone from any strata directly above or below it.

- 2.10 A review of the mechanical condition of each well within a one-half mile radius of the proposed injection well to assure that no conduit exists that could enable fluids to migrate up or down the wellbore and enter the improper intervals.**

See Attachments E through E-12.

Additionally, the injection system will be equipped with high and low pressure shut down devices that will automatically shut in injection waters if a system blockage or leakage occurs. One way check valves will also ensure proper flow management. Relief valves will also be utilized for high-pressure relief.


- 2.11 An affidavit certifying that a copy of the application has been provided to all operators or owners, and surface owners within a one-half mile radius of the proposed injection well.**

See Attachment C.

- 2.12 Any other information that the Board or Division may determine is necessary to adequately review the application.**

Newfield Production Company will supply any requested information to the Board or Division.





- 14\_13\_9\_15
- Well Status
- Location
  - CTI
  - Surface Spud
  - Drilling
  - Waiting on Completion
  - Producing Oil Well
  - Producing Gas Well
  - Water Injection Well
  - Dry Hole
  - Temporarily Abandoned
  - Plugged & Abandoned
  - Shut In
- Countyline
- 14\_13\_9\_15\_Buffer
- Injection system
- high pressure
  - low pressure
  - proposed
  - return
  - return proposed
- Wells\_Raw
- Leases
- Mining tracts
- Gas Pipelines
- Gathering lines
- Proposed lines

UTU-68548

UTU-66184

UTU-66185

UTU-02458

Ashley 14-13  
Section 13, T9S-R15E

**NEWFIELD**  
ROCKY MOUNTAINS



1/2 Mile Radius Map  
Duchesne & Uintah Counties

1001 17th Street Suite 2000  
Denver, Colorado 80202  
Phone: (303) 893-0102

January 17, 2011



T9S, R15E, S.L.B.&amp;M.

S89°55'W - 80.16 (G.L.O.)

2651.57' (Measured)

S89°55'W G.L.O. (Basis of Bearings)

S89°52'54"W - 2648.87' (Meas.)

1910  
Brass Cap1910  
Brass Cap1910  
Brass Cap

N00°00'25"E - 2644.78' (Meas.)

N00°06'03"E - 2640.46' (Meas.)

**WELL LOCATION:  
ASHLEY UNIT #14-13**

ELEV. UNGRADED GROUND = 6158.3'

13

1910  
Brass Cap1910  
Brass Cap

N00°06'05"W - 2644.96' (Meas.)

N00°04'09"E - 2642.57' (Meas.)

NORTH (G.L.O.)

DRILLING  
WINDOW

2020'

758'  
200'Corner Reestablished  
Proportionately  
(Not Set)1910  
Brass CapCorner Reestablished  
Proportionately  
(Not Set)



S89°49'34"W - 5288.25' (Meas.)

S89°56'W - 80.12 (G.L.O.)

◆ = SECTION CORNERS LOCATED

BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (MYTON SW)

INLAND PRODUCTION COMPANY

WELL LOCATION, ASHLEY UNIT #14-13,  
LOCATED AS SHOWN IN THE SE 1/4 SW  
1/4 OF SECTION 13, T9S, R15E,  
S.L.B.&M. DUCHESNE COUNTY, UTAH.THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS  
PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS  
MADE BY ME OR UNDER MY SUPERVISION AND THAT  
THE SAME ARE TRUE AND CORRECT TO THE BEST OF  
MY KNOWLEDGE AND BELIEF. No.189377

TRI STATE LAND SURVEYING &amp; CONSULTING

38 WEST 100 NORTH - VERNAL, UTAH 84078  
(435) 781-2501

SCALE: 1" = 1000'

SURVEYED BY: D.J.S.

DATE: 8-18-04

DRAWN BY: F.T.M.

NOTES:

FILE #

## EXHIBIT B

#	Legal Description	Lessor & Expiration	Lessee & Operating Rights	Surface Owner
1	<u>T9S,R15E SLM</u> Section 13: S2S2 Section 14: S2S2 Section 15: Lot 4 (SESW) Section 22: Lot 1 (NWNW), E2NW, NE Section 23: N2NW	USA UTU-68548 HBP	Newfield Production Company Newfield RMI LLC	USA
2	<u>T9S,R15E SLM</u> Section 13: N2, N2S2 Section 14: N2, N2S2 Section 15: Lots 1-3 (E2NW, NESW), E2	USA UTU-66184 HBP	Newfield Production Company Newfield RMI LLC	USA
3	<u>T9S,R15E SLM</u> Section 22: Lots 2-4 (SWNW, W2SW), E2SW Section 23: NENE, W2E2, S2NW, E2SW Section 24: N2N2 Section 25: All Section 26: NE, NENW, S2NW, S2 Section 27: Lots 1-2 (W2NW), E2NW, S2NE, SE	USA UTU-66185 HBP	Newfield Production Company Newfield RMI LLC	USA



## EXHIBIT B

#	Legal Description	Lessor & Expiration	Lessee & Operating Rights	Surface Owner
4	<u>T9S,R15E SLM</u> Section 23: SENE, W2SW, NESE Section 24: S2N2, S2	USA UTU-02458 HBP	Newfield Production Company Newfield RMI LLC	USA

ATTACHMENT C

CERTIFICATION FOR SURFACE OWNER NOTIFICATION

RE: Application for Approval of Class II Injection Well  
Ashley Federal #14-13-9-15

I hereby certify that a copy of the injection application has been provided to all surface owners within a one-half mile radius of the proposed injection well.

Signed: \_\_\_\_\_


*Eric Sundberg*  
Newfield Production Company  
Eric Sundberg  
Regulatory Lead

Sworn to and subscribed before me this 9<sup>th</sup> day of February, 2011.

Notary Public in and for the State of Colorado: \_\_\_\_\_

*Candice L. Twitty*

My Commission Expires: 02/10/2013



## Ashley Federal 14-13-9-15

Spud Date: 7/27/05  
 Put on Production: 9/24/05  
 GL: 6158' KB: 6170'

Initial Production: 46 BOPD,  
 32 MCFD, 92 BWPD

## Wellbore Diagram

**SURFACE CASING**

CSG SIZE: 8 5/8"  
 GRADE: J-55  
 WEIGHT: 24#  
 LENGTH: 7 jts. (304.2')  
 DEPTH LANDED: 314.2' KB  
 HOLE SIZE: 12 1/4"  
 CEMENT DATA: 160 sks Class G Mix. Est 4 bbls cement to pit

**PRODUCTION CASING**

CSG SIZE: 5 1/2"  
 GRADE: J-55  
 WEIGHT: 15.5#  
 LENGTH: 136 jts. (5978.71')  
 DEPTH LANDED: 5976.71' KB  
 HOLE SIZE: 7 7/8"  
 CEMENT DATA: 300 sks Prem. Lite II mixed & 450 sks 50/50 POZ mix.  
 CEMENT TOP AT: 91'

**TUBING**

SIZE/GRADE/WT.: 2 7/8" / J-55 / 6.5#  
 NO. OF JOINTS: 156 jts (4858.15')  
 TUBING ANCHOR: 4870.15' KB  
 NO. OF JOINTS: 1 jts (31.05')  
 SEATING NIPPLE: 2 7/8" (1.10')  
 SN LANDED AT: 4904.00' KB  
 NO. OF JOINTS: 2 jts (62.38')  
 TOTAL STRING LENGTH: 4967.93' w/ 12' KB

**SUCKER RODS**

POLISHED ROD: 1 1/2" x 22' polished rod  
 SUCKER RODS: 1-8", 1-6", 1-4", 1-2", x 3/4" ponies, 99-3/4" scraped rods,  
 80-3/4" plain rods, 10-3/4" scraped rods, 6-1 1/4" weight rods  
 PUMP SIZE: CDI 2 1/2" x 1 3/4" x 21" x 24' RHAC pump w/SM plunger  
 STROKE LENGTH: 86"  
 PUMP SPEED, SPM: 5 SPM

**FRAC JOB**


9/19/05 4828'-4900' **Frac B.5 & 2 sands as follows:**  
 59,638#'s of 20/40 sand in 476 bbls lightning  
 17 frac fluid. Treated @ avg press of 1690,  
 w/avg rate of 25 bpm. ISIP 2300 psi. Calc  
 flush: 4826 gal. Actual flush: 4872 gal.

9/19/05 4754'-4762' **Frac C sands as follows:**  
 49,648#'s of 20/40 sand in 418 bbls lightning  
 17 frac fluid. Treated @ avg press of 2308,  
 w/avg rate of 28.5 bpm. ISIP 3650 psi. Calc  
 flush: 4752 gal. Actual flush: 4788 gal.

9/19/05 4672'-4678' **Frac D2 sands as follows:**  
 60,644#'s of 20/40 sand in 323 bbls  
 lightning 17 frac fluid. Treated @ avg press  
 of 1910, w/avg rate of 25.1 bpm. ISIP 2030  
 psi. Calc flush: 4670 gal. Actual flush: 4662  
 gal.

9/19/05 4006'-4024' **Frac GB2 sands as follows:**  
 84,673#'s of 20/40 sand in 583 bbls  
 lightning 17 frac fluid. Treated @ avg press  
 of 1903, w/avg rate of 25 bpm. ISIP 2610  
 psi. Calc flush: 4004 gal. Actual flush: 3906  
 gal.

02/08/06 Pump Change. Update tubing and rod details.  
 05/29/08 Production log. Updated rod and tubing detail  
 4/28/09 RTP. Updated r & t details.

**PERFORATION RECORD**

9/19/05	4894'-4900'	4 JSPF	24 holes
9/19/05	4828'-4832'	4 JSPF	16 holes
9/19/05	4754'-4762'	4 JSPF	32 holes
9/19/05	4672'-4678'	4 JSPF	24 holes
9/19/05	4006'-4024'	4 JSPF	72 holes

**NEWFIELD**

Ashley Federal 14-13-9-15  
 758' FSL & 2020' FWL  
 SE/SW Section 13-T9S-R15E  
 Duchesne Co, Utah  
 API #43-013-32669; Lease #UTU-68548

## Ashley Federal 10-13-9-15

Spud Date: 2/3/2005

Put on Production: 03/4/2005

GL: 6115' KB: 6127'

Injection Wellbore  
DiagramSURFACE CASING

CSG SIZE: 8-5/8"

GRADE: J-55

WEIGHT: 24#

LENGTH: 7 jts. (301')

DEPTH LANDED: (311')

HOLE SIZE: 12-1/4"

CEMENT DATA: 160 sxs class "G", 3 bbls cmt to surface.

PRODUCTION CASING

CSG SIZE: 5-1/2"

GRADE: J-55

WEIGHT: 15.5#

LENGTH: 143 jts. (6025.2')

DEPTH LANDED: (6023.2')

HOLE SIZE: 7-7/8"

CEMENT DATA: 300 sxs Premix II &amp; 400 sxs 50/50 POZ.

CEMENT TOP AT: 450'

TUBING

SIZE/GRADE/WT. 2-7/8" J-55 / 6.5#

NO OF JOINTS: 141 jts (4627.6')

SEATING NIPPLE: 2-7/8" (1.10')

SN LANDED AT: 4639.6' KB

ON/OFF TOOL AT: 4640.7'

ARROW #1 PACKER CE AT: 4645'

TBG PUP 2-3/8 J-55 AT: 4648.7'

XO 2-3/8 x 2-7/8 J-55 AT: 4653.1'

TOTAL STRING LENGTH: EOT @ 4654.07'

FRAC JOB

02/28/05 5852-5922'

Frac BS &amp; CFS sands as follows: 64,491# 20/40 sand in 526 bbls Lightning 17 frac fluid. Treated @ avg press. of 1928 w/ avg rate of 24.6 bpm. ISIP 2180. Calc flush: 5850 gal. Actual flush: 5880 gal

03/01/05 5680-5724'

Frac CFS sands as follows: 69,786# 20/40 sand in 558 bbls Lightning 17 frac fluid. Treated @ avg press. of 1682 w/ avg rate of 24.5 bpm. ISIP 2100. Calc flush: 5678 gal. Actual flush: 5712 gal

03/01/05 5463-5564'

Frac CP1 &amp; LODC sands as follows: 94,982# 20/40 sand in 698 bbls Lightning 17 frac fluid. Treated @ avg press. of 1742 w/ avg rate of 24.8 bpm. ISIP 2230. Calc flush: 5461 gal. Actual flush: 5502 gal

03/01/05 5322-5333'

Frac LODC sands as follows: 59,881# 20/40 sand in 491 bbls lightning 17 frac fluid. Treated @ avg press. of 2170 w/ avg rate of 24.8 bpm. ISIP 2430. Calc flush: 5320 gal. Actual Flush: 5334 gal.

03/01/05 5196-5221'

Frac LODC sands as follows: 29,366# 20/40 sand in 332 bbls lightning 17 frac fluid. Treated @ avg press. of 2258 w/ avg rate of 14.4 bpm. ISIP 3350. Calc flush: 5194 gal. Actual Flush: 5208 gal.

03/01/05 4978-5056'

Frac A.S &amp; A1 sands as follows: 75,155# 20/40 sand in 564 bbls lightning 17 frac fluid. Treated @ avg press. of 1849 w/ avg rate of 24.8 bpm. ISIP 2000. Calc flush: 4976 gal. Actual Flush: 4756 gal.

03/02/05 4671-4722'

Frac D2 &amp; D3 sands as follows: 62,583# 20/40 sand in 476 bbls lightning 17 frac fluid. Treated @ avg press. of 1720 w/ avg rate of 24.7 bpm. ISIP 2100. Calc flush: 4669 gal. Actual Flush: 4578 gal.

04/08/08

Workover: Rod &amp; Tubing detail updated

4/25/09

RTP. Updated r &amp; t details.

10/17/13

Convert to Injection Well

10/18/13

Conversion MIT Finalized - update thg detail

SN @ 4640'

On Off Tool @ 4641'

Packer @ 4645'

EOT @ 4654'

4671-4676'

4709-4722'

4978-4984'

5042-5056'

5196-5203'

5216-5221'

5322-5333'

5463-5476'

5544-5564'

5680-5700'

5720-5724'

5852-5864'

5915-5922'

PBD @ 5983'

SHOE @ 6023'

TD @ 6038'

PERFORATION RECORD

2/22/2005	5915-5922'	4 SPF	28 holes
2/22/2005	5852-5864'	4 SPF	48 holes
2/28/2005	5720-5724'	4 SPF	16 holes
2/28/2005	5680-5700'	4 SPF	80 holes
3/01/2005	5544-5564'	4 SPF	80 holes
3/01/2005	5463-5476'	4 SPF	52 holes
3/01/2005	5322-5333'	4 SPF	44 holes
3/01/2005	5216-5221'	4 SPF	20 holes
3/01/2005	5196-5203'	4 SPF	28 holes
3/01/2005	5042-5056'	4 SPF	56 holes
3/01/2005	4978-4984'	4 SPF	24 holes
3/01/2005	4709-4722'	4 SPF	52 holes
3/01/2005	4671-4676'	4 SPF	20 holes

**NEWFIELD**

Ashley Federal 10-13-9-15

1938' FSL &amp; 1967' FEL

NW/SE Section 13-T9S-R15E

Duchesne Co, Utah

API #43-013-32458; Lease #UTU-66184

Spud Date: 01/20/05  
 Put on Production: 03/01/2005  
 GL: 6157' KB: 6169'

## ASHLEY FEDERAL 11-13-9-15

Initial Production: 85BOPD,  
 254MCFD, 18BWPD

Injection Wellbore  
DiagramSURFACE CASING

CSG SIZE: 8 5/8"  
 GRADE: J-55  
 WEIGHT: 24#  
 LENGTH: 7 jts. (298.09')  
 DEPTH LANDED: 308.09' KB  
 HOLE SIZE: 12 1/4"  
 CEMENT DATA: 160 sks Class G Mix. 5 bbls cement to surface.

PRODUCTION CASING

CSG SIZE: 5 1/2"  
 GRADE: J-55  
 WEIGHT: 15.5#  
 LENGTH: 143 jts. (6032.98')  
 DEPTH LANDED: 6030.98' KB  
 HOLE SIZE: 7 7/8"  
 CEMENT DATA: 300 sks Prem. Lite II mixed & 400 sks 50/50 POZ mix.  
 CEMENT TOP AT: 150'

TUBING

SIZE/GRADE/WT.: 2 7/8" / J-55 / 6.5#  
 NO. OF JOINTS: 139 jts (4617.60')  
 SEATING NIPPLE: 2 7/8" (1.10')  
 SN LANDED AT: 4629.60' KB  
 TOTAL STRING LENGTH: 4638.10' w/ 12' KB

Cement Top @ 150'

Packer @ 4635'

4672'-4676'

4705'-4722'

4881'-4892'

4926'-4930'

5053'-5060'

5068'-5078'

5572'-5583'

5746'-5750'

5781'-5784'

5844'-5848'

5856'-5860'

5928'-5933'

PBTD @ 5987'

SHOE @ 6031'

TD @ 6050'

FRAC JOB

02/23/05 5746'-5933' Frac BSSD, CP5, CP4, CP3 sands as follows:  
 39,925# of 20/40 sand in 389 bbls lightning  
 17 frac fluid. Treated @ avg press of 1790,  
 w/avg rate of 24.7 bpm. ISIP 2025 psi. Calc  
 flush: 5744 gal. Actual flush: 5783 gal.

02/23/05 5572'-5583' Frac CP1 sands as follows:  
 20,108# of 20/40 sand in 256 bbls lightning  
 17 frac fluid. Treated @ avg press of 2040,  
 w/avg rate of 24.7 bpm. ISIP 2050 psi. Calc  
 flush: 5570 gal. Actual flush: 5586 gal.

02/23/05 5053'-5078' Frac A1 sands as follows:  
 75,275# of 20/40 sand in 567 bbls  
 lightning 17 frac fluid. Treated @ avg press  
 of 1890, w/avg rate of 24.9 bpm. ISIP 2200  
 psi. Calc flush: 5051 gal. Actual flush: 5040  
 gal.

02/23/05 4881'-4930' Frac B2 and B.5 sands as follows:  
 34,521# of 20/40 sand in 336 bbls lightning  
 17 frac fluid. Treated @ avg press of 1990,  
 w/avg rate of 24.7 bpm. ISIP 2125 psi. Calc  
 flush: 4879 gal. Actual flush: 4914 gal.

02/24/05 4672'-4722' Frac D2 and D1 sands as follows:  
 81,299# of 20/40 sand in 587 bbls lightning  
 17 frac fluid. Treated @ avg press of 1990  
 w/avg rate of 24.7 bpm. ISIP 2400 psi. Calc  
 flush: 4670 gal. Actual flush: 4578 gal.

3/3/2006 Well converted to an injection well.  
 3/27/2006 MIT Completed and submitted.  
 5/28/09 Marcit Squeeze  
 02/11/11 5 yr MIT

PERFORATION RECORD

02/16/05	5928'-5933'	4 JSPF	20 holes
02/16/05	5856'-5860'	4 JSPF	16 holes
02/16/05	5844'-5848'	4 JSPF	16 holes
02/16/05	5781'-5784'	4 JSPF	12 holes
02/16/05	5746'-5750'	4 JSPF	16 holes
02/23/05	5572'-5583'	4 JSPF	44 holes
02/23/05	5068'-5078'	4 JSPF	40 holes
02/23/05	5053'-5060'	4 JSPF	28 holes
02/23/05	4926'-4930'	4 JSPF	16 holes
02/23/05	4881'-4892'	4 JSPF	44 holes
02/23/05	4705'-4722'	4 JSPF	68 holes
02/23/05	4672'-4676'	4 JSPF	16 holes



Ashley Federal 11-13-9-15  
 1790' FSL & 2043' FWL  
 NE/SW Section 13-T9S-R15E  
 Duchesne Co, Utah  
 API #43-013-32457; Lease #UTU-66184

NEWFIELD

## Schematic

43-013-32456

Well Name: Ashley 12-13-9-15


Surface Legal Location 1984' FSL & 658' FWL (NW/SW) SECTION 13-T9S-R15E		API Well 43013324560000	Well RC 500151111	Lease	State/Province Utah	Field Name GMBU CTB2	County DUCHESNE
Spud Date 1/19/2005	Rig Release Date 1/31/2005	On Production Date 2/22/2005	Original KB Elevation (ft) 6,208	Ground Elevation (ft) 6,196	Total Depth All (TVD) (ftKB)	PBTD (All) (ftKB) Original Hole - 6,007.0	

## Most Recent Job

Job Category Production / Workover	Primary Job Type Conversion	Secondary Job Type OAP	Job Start Date 4/11/2014	Job End Date
---------------------------------------	--------------------------------	---------------------------	-----------------------------	--------------

TD: 6,051.4

Vertical - Original Hole, 5/1/2014 10:02:36 AM



## Ashley Federal 13-13-9-15

Spud Date: 12/15/04  
Put on Production: 02/16/05  
GL: 6209' KB: 6221'

Initial Production: 22 BOPD,  
92 MCFPD, 14 BWPD

### SURFACE CASING

CSG SIZE: 8-5/8"  
GRADE: J-55  
WEIGHT: 24#  
LENGTH: 7 jts. (301.65')  
DEPTH LANDED: 311.65'  
HOLE SIZE: 12-1/4"  
CEMENT DATA: 150 sks Class "G" cement, est. 3 bbls cement to surface


### PRODUCTION CASING

CSG SIZE: 5-1/2"  
GRADE: J-55  
WEIGHT: 15.5#  
LENGTH: 143 jts. (6033.78')  
DEPTH LANDED: 6031.78' KB  
HOLE SIZE: 7-7/8"  
CEMENT DATA: 300 sks Prem Lite II, 400 sks 50-50 Poz mix  
CEMENT TOP: 160'

### TUBING

SIZE/GRADE/WT.: 2 7/8" - 6.5# - J-55  
NO. OF JOINTS: 131 jts. (4145.18')  
SN LANDED AT: 1.10' (4157.18') KB  
NO. OF JOINTS: 2 jts. (63.63')  
TOTAL STRING LENGTH: 4165.68' w/ 12' KB

### Injection Wellbore Diagram



### FRAC JOB

02/11/05 5709'-5928' **Frac Bsh, CP5 and CP3 sand as follows:**  
25,175#'s of 20/40 sand in 301 bbls lightning 17 frac fluid. Treated w/avg press of 1946 psi, w/avg rate of 24.9 bpm. ISIP 2025 psi. Calc flush: 5707 gal. Actual flush: 5670 gal.

02/11/05 5384'-5476' **Frac LODC sand as follows:**  
20,593#'s of 20/40 sand in 212 bbls lightning 17 frac fluid. Treated w/avg press of 3286 psi, w/ avg rate of 24.5 bpm. Screened out

02/11/05 5033'-5041' **Frac A1 sand as follows:**  
35,788#'s of 20/40 sand in 343 bbls lightning 17 frac fluid. Treated w/avg press of 2141 psi, w/ avg rate of 24.8 bpm. ISIP 2280 psi. Calc flush: 5031 gal. Actual flush: 5040

02/11/05 4558'-4568' **Frac DS2 sand as follows:**  
30,496#'s of 20/40 sand in 299 bbls lightning 17 frac fluid. Treated w/avg press of 2007 psi w/avg rate of 24.8 bpm. ISIP 2250 psi. Calc flush: 4557 gal. Actual flush: 4536 gal.

02/11/05 4184'-4191' **Frac GB6 sand as follows:**  
23,380#'s of 20/40 sand in 238 bbls lightning 17 frac fluid. Treated @ w/avg press of 2114 psi, w/avg rate of 24.9 bpm. ISIP 2000 psi. Calc flush: 4182 gal. Actual flush: 4116 gal.

11/1/05 **Well converted to Injection well.**

11/17/05 **MIT submitted.**

### PERFORATION RECORD

02/04/05	5922'-5928'	4 JSPF	24 holes
02/04/05	5847'-5854'	4 JSPF	28 holes
02/04/05	5709'-5714'	4 JSPF	20 holes
02/11/05	5468'-5476'	4 JSPF	32 holes
02/11/05	5384'-5390'	4 JSPF	24 holes
02/11/05	5033'-5041'	4 JSPF	32 holes
02/11/05	4558'-4568'	4 JSPF	40 holes
02/11/05	4184'-4191'	4 JSPF	28 holes

**NEWFIELD**

**Ashley Federal 13-13-9-15**

665' FSL & 656' FWL

SW/SW Section 13-T9S-R15E

Duchesne Co, Utah

API 43-013-32455; Lease UTU68548

## Ashley Federal 16-13-9-15

Spud Date: 6/23/05

Put on Production: 8/12/05

GL: 6127' KB: 6139'

Initial Production: 31 BOPD,  
14 MCFD, 51 BWPD

## Wellbore Diagram

SURFACE CASING

CSG SIZE: 8 5/8"

GRADE: J-55

WEIGHT: 24#

LENGTH: 7 jts. (304.09')

DEPTH LANDED: 314.09' KB

HOLE SIZE: 12 1/4"

CEMENT DATA: 160 sks Class G Mix. Est 6 bbls cement to pit

PRODUCTION CASING

CSG SIZE: 5 1/2"

GRADE: J-55

WEIGHT: 15.5#

LENGTH: 141 jts. (5977.86')

DEPTH LANDED: 5975.86' KB

HOLE SIZE: 7 7/8"

CEMENT DATA: 325 sks Prem. Lite II mixed &amp; 450 sks 50/50 POZ mix.

CEMENT TOP AT: 70'

TUBING

SIZE/GRADE/WT.: 2 7/8" / J-55 / 6.5#

NO. OF JOINTS: 180 jts (5634.7')

TUBING ANCHOR: 5646.7' KB

NO. OF JOINTS: 2 jts (62.2')

SEATING NIPPLE: 2 7/8" (1.10')

SN LANDED AT: 5711.7' KB

NO. OF JOINTS: 2 jts (62.8')

TOTAL STRING LENGTH: EOT @ 5776'

SUCKER RODS

POLISHED ROD: 1 1/2" x 22'

SUCKER RODS: 1-2' x 3/4" pony rod, 1-8' x 3/4" pony rod, 222-3/4" guided rods, 6-1 1/2" weight bars

PUMP SIZE: 2 1/2" x 1 1/2" x 12' x 16' RHAC

STROKE LENGTH: 86"

PUMP SPEED, SPM: 5 SPM

FRAC JOB

8/8/05 5596'-5688'

**Frac CP2 and CP3 sands as follows:**  
48,881#s of 20/40 sand in 437 bbls lightning 17 frac fluid. Treated @ avg press of 1399, w/avg rate of 24.6 bpm. ISIP 2000 psi. Calc flush: 5594 gal. Actual flush: 5368 gal.

8/8/05 5462'-5506'

**Frac LODC sands as follows:**  
30,693#s of 20/40 sand in 330 bbls lightning 17 frac fluid. Treated @ avg press of 1837, w/avg rate of 24.9 bpm. ISIP 2200 psi. Calc flush: 5460 gal. Actual flush: 5212 gal.

8/9/05 5126'-5166'

**Frac LODC sands as follows:**  
30,385#s of 20/40 sand in 317 bbls lightning 17 frac fluid. Treated @ avg press of 1882, w/avg rate of 24.9 bpm. ISIP 2750 psi. Calc flush: 5124 gal. Actual flush: 4885 gal.

8/9/05 4777'-4786'

**Frac C sands as follows:**  
39,987#s of 20/40 sand in 370 bbls lightning 17 frac fluid. Treated @ avg press of 1674, w/avg rate of 24.7 bpm. ISIP 1800 psi. Calc flush: 4775 gal. Actual flush: 4536 gal.

8/9/05 4666'-4674'


**Frac D2 sands as follows:**  
35,978#s of 20/40 sand in 349 bbls lightning 17 frac fluid. Treated @ avg press of 1831, w/avg rate of 24.6 bpm. ISIP 1950 psi. Calc flush: 4664 gal. Actual flush: 4536 gal.

6/30/08  
1/28/09  
1/10/10  
6/17/2010  
7/2/2010

Hole in Tubing. Rod & tubing detail updated.  
Tubing Leak. Updated r & t detail.  
Parted rods. Updated rod and tubing detail.  
Parted rods. Updated rod and tubing detail.  
Parted rods. Updated rod and tubing detail.

PERFORATION RECORD

8/3/05	5672'-5688'	4 JSPF	64 holes
8/3/05	5596'-5600'	4 JSPF	16 holes
8/8/05	5500'-5506'	4 JSPF	24 holes
8/8/05	5462'-5470'	4 JSPF	32 holes
8/9/05	5160'-5166'	4 JSPF	24 holes
8/9/05	5126'-5135'	4 JSPF	36 holes
8/9/05	4777'-4786'	4 JSPF	36 holes
8/9/05	4666'-4674'	4 JSPF	32 holes

**NEWFIELD**

Ashley Federal 16-13-9-15

682' FSL &amp; 523' FEL

SE/SE Section 13-T9S-R15E

Duchesne Co, Utah

API #43-013-32668; Lease #UTU-68548

ML 7/20/2010



## Ashley Federal 15-13-9-15

Spud Date: 3-15-05  
Put on Production: 5-16-05

GL: 6114' KB: 6126'

### SURFACE CASING

CSG SIZE: 8-5/8"  
GRADE: J-55  
WEIGHT: 24#  
LENGTH: 7 jts. (301.02')  
DEPTH LANDED: 312.87' KB  
HOLE SIZE: 12-1/4"  
CEMENT DATA: 160 sxs Class "G" cmt, est 6 bbls cmt to surf.


### PRODUCTION CASING

CSG SIZE: 5-1/2"  
GRADE: J-55  
WEIGHT: 15.5#  
LENGTH: 166 jts. (5921.78')  
DEPTH LANDED: 5935.03' KB  
HOLE SIZE: 7-7/8"  
CEMENT DATA: 300 sxs Prem. Lite II & 400 sxs 50/50 POZ.  
CEMENT TOP AT: 610'

### TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55  
NO. OF JOINTS: 136 jts (4538.59')  
SEATING NIPPLE: 2-7/8" (1.10')  
SN LANDED AT: 4550.59' KB  
TOTAL STRING LENGTH: EOT @ 4559.09' KB

### Injection Wellbore Diagram



Initial Production: BOPD 52,  
MCFD 47, BWPD 152

### FRAC JOB

5-12-05	5625'-5704''	<b>Frac CP2 &amp; CP3 sand as follows:</b> 44,713#s 20/40 sand in 441 bbls Lightning 17 frac fluid. Treated @ avg press of 1843 psi w/avg rate of 24.7 BPM. ISIP was 1925 psi. Calc flush: 5623 gal. Actual flush: 5670 gal.
5-12-05	5434'-5442''	<b>Frac LODC sand as follows:</b> 30,309#s 20/40 sand in 327 bbls Lightning 17 frac fluid. Treated @ avg press of 2120 psi w/avg rate of 24.8 BPM. ISIP 2250 psi. Calc flush: 5432 gal. Actual flush: 5418 gal.
5-12-05	5114'-5123'	<b>Frac LODC sand as follows:</b> 25,380#s 20/40 sand in 284 bbls Lightning 17 frac fluid. Treated @ avg press of 2056 psi w/avg rate of 24.9 BPM. ISIP 2260 psi. Calc flush: 5112 gal. Actual flush: 5124 gal.
5-12-05	4814'-4856'	<b>Frac B1 &amp; B.5 sand as follows:</b> 55,249#s 20/40 sand in 459 bbls Lightning 17 frac fluid. Treated @ avg press of 2102 psi w/avg rate of 24.9 BPM. ISIP 2000 psi. Calc flush: 4812 gal. Actual flush: 4830 gal.
5-12-05	4706'-4716'	<b>Frac D3 sand as follows:</b> 45,168#s 20/40 sand in 405 bbls Lightning 17 frac fluid. Treated @ avg press of 1868 psi w/avg rate of 24.7 BPM. ISIP 2240 psi. Calc flush: 4704 gal. Actual flush: 4788 gal
5-12-05	4619'-4626'	<b>Frac D1 sand as follows:</b> 30,160#s 20/40 sand in 306 bbls Lightning 17 frac fluid. Treated @ avg press of 2332 psi w/avg rate of 24.6 BPM. ISIP 2800 psi. Calc flush: 4617 gal. Actual flush: 4536 gal.

09/09/05 Parted Rods. Detail tubing and rod Updated.  
6/8/06 Well converted to an injection well.  
6/30/06 MIT completed and submitted.

### PERFORATION RECORD

5-4-05	5691-5704'	4 JSPF	52 holes
5-5-05	5625-5629'	4 JSPF	16 holes
5-12-05	5434-5442'	4 JSPF	32 holes
5-12-05	5114-5123'	4 JSPF	36 holes
5-12-05	4852-4856'	4 JSPF	16 holes
5-12-05	4814-4821'	4 JSPF	28 holes
5-12-05	4706-4716'	4 JSPF	40 holes
5-12-05	4619-4626'	4 JSPF	28 holes

**NEWFIELD**



Ashley Federal 15-13-9-15  
570' FSL & 2050' FEL  
SW/SE Section 13-T9S-R15E  
Duchesne Co, Utah  
API #43-013-32454; Lease #UTU-68548

## NEWFIELD

## Schematic

Well Name: Ashley 16-14-9-15

43-013-32667

Surface Legal Location 620' FSL & 645' FEL (SE SE) SECTION 14-T9S-R15E	API/UWI 43013326670000	Well RC 500151916	Lease	State/Province Utah	Field Name GMBU CTB2	County DUCHESE
Spud Date 6/23/2005	Rig Release Date	On Production Date 9/22/2005	Original KB Elevation (ft) 6,285	Ground Elevation (ft) 6,273	Total Depth All (TVD) (ftKB)	PBTD (All) (ftKB) Original Hole - 6,035.0

## Most Recent Job

Job Category Production / Workover	Primary Job Type Conversion	Secondary Job Type Basic	Job Start Date 5/20/2014	Job End Date 5/22/2014
---------------------------------------	--------------------------------	-----------------------------	-----------------------------	---------------------------

TD: 6,090.0

Vertical - Original Hole, 5/27/2014 1:31:22 PM

MD (ftKB)	TVD (ftKB)	Incl (°)	DLS	Vertical schematic (actual)
12.1			DLS (°)	
129.9				
308.1				
312.0				
313.0				
4,068.2				
4,069.2				
4,071.2				
4,078.1				
4,078.7				
4,082.7				
4,084.6				
4,116.1				
4,126.0				
4,151.9				
4,162.1				
4,676.8				
4,689.0				
4,790.0				
4,812.0				
4,826.1				
4,830.1				
4,953.1				
4,956.0				
5,032.2				
5,038.1				
5,061.0				
5,064.0				
5,175.9				
5,208.0				
5,240.2				
5,247.0				
5,267.1				
5,276.9				
5,286.1				
5,298.9				
5,349.1				
5,357.9				
5,509.8				
5,516.1				
5,682.1				
5,690.0				
6,035.1				
6,035.8				
6,036.4				
6,080.7				
6,081.4				
6,089.9				

1: Surface; 8 5/8 in; 8,097 in; 12-313 ftKB; 301.07 ft

3-1; Tubing; 2 7/8; 2,441; 12-4,068; 4,056.23

3-2; Pump Seating Nipple; 2 7/8; 4,068-4,069; 1.10

3-3; On-Off Tool; 2 7/8; 4,069-4,071; 1.90

3-4; Packer; 5 1/2; 4,071-4,078; 6.92

3-5; Cross Over; 2 3/8; 4,078-4,079; 0.50

3-6; Tubing Pup Joint; 2 3/8; 4,079-4,083; 4.15

3-7; XN Nipple; 2 3/8; 4,083-4,085; 1.82

Perforated; 4,116-4,126; 9/14/2005

Perforated; 4,152-4,162; 9/14/2005

Perforated; 4,677-4,689; 9/14/2005

Perforated; 4,790-4,812; 9/14/2005

Perforated; 4,826-4,830; 9/14/2005

Perforated; 4,953-4,956; 9/14/2005

Perforated; 5,032-5,038; 9/14/2005

Perforated; 5,061-5,064; 9/14/2005

Perforated; 5,176-5,208; 9/13/2005

Perforated; 5,240-5,247; 9/13/2005

Perforated; 5,267-5,277; 9/13/2005

Perforated; 5,286-5,299; 9/13/2005

Perforated; 5,349-5,358; 9/13/2005

Perforated; 5,510-5,516; 9/1/2005

Perforated; 5,682-5,690; 9/1/2005

2: Production; 5 1/2 in; 4,950 in; 12-6,081 ftKB; 6,069.42 ft



## NEWFIELD

## Schematic

43-013-32645

Well Name: Ashley 2-24-9-15


Surface Legal Location 24-9S-15E	API/UWI 43013326450000	Well RC 500151914	Lease	State/Province Utah	Field Name GMBU CTB3	County DUCHESNE
Spud Date	Rig Release Date	On Production Date 9/2/2005	Original KB Elevation (ft) 6,199	Ground Elevation (ft) 6,187	Total Depth All (TVD) (ftKB)	PBTD (All) (ftKB) Original Hole - 5,933.0

## Most Recent Job

Job Category Production / Workover	Primary Job Type Conversion	Secondary Job Type Basic	Job Start Date 6/30/2014	Job End Date 7/8/2014
---------------------------------------	--------------------------------	-----------------------------	-----------------------------	--------------------------

TD: 5,985.0

Vertical - Original Hole, 7/9/2014 2:57:32 PM



## Ashley Federal 4-24-9-15

Spud Date: 7/21/05  
Put on Production: 9/8/05  
GL: 6207' KB: 6219'

**SURFACE CASING**

CSG SIZE: 8-5/8"  
GRADE: J-55  
WEIGHT: 24#  
LENGTH: 7 jts. (297.38')  
DEPTH LANDED: 307.38' KB  
HOLE SIZE: 12-1/4"  
CEMENT DATA: 150 sxs Class "G" cmt, est 5 bbls cmt to surf.

**PRODUCTION CASING**


CSG SIZE: 5-1/2"  
GRADE: J-55  
WEIGHT: 15.5#  
LENGTH: 138 jts. (5952.65')  
DEPTH LANDED: 5950.65' KB  
HOLE SIZE: 7-7/8"  
CEMENT DATA: 300 sxs Prem. Lite II & 450 sxs 50/50 POZ.  
CEMENT TOP AT: 340'

**TUBING**

SIZE/GRADE/WT.: 2-7/8" / J-55  
NO. OF JOINTS: 176 jts (5698.66')  
TUBING ANCHOR: 5710.66'  
NO. OF JOINTS: 1 jts (32.53')  
SEATING NIPPLE: 2-7/8" (1.10')  
SN LANDED AT: 5745.99'  
NO. OF JOINTS: 2 jts (65.14')  
TOTAL STRING LENGTH: EOT @ 5812.68'

**SUCKER RODS**

POLISHED ROD: 1-1/2" x 22'  
SUCKER RODS: 98- 3/4" guided rods, 115- 3/4" plain rods, 10- 3/4" guided rods, 6- 1 1/2" weight bars.  
PUMP SIZE: 2-1/2" x 1-1/2" x 12' x 17' RTBC Mcgyver pump  
STROKE LENGTH: 86"  
PUMP SPEED, 5 SPM

**Wellbore Diagram**

Initial Production: 48 BOPD,  
33 MCFD, 43 BWPD

**FRAC JOB**

8/31/05 5784-5798' **Frac CP5 sand as follows:**  
35,520#'s 20/40 sand in 360 bbls Lightning  
17 frac fluid. Treated @ avg press of 1504 psi  
w/avg rate of 23.4 BPM. ISIP 2400 Calc  
Flush: 5782 gal. Actual Flush 5796 gals.

9/1/05 5593-5664' **Frac CP2&3 sand as follows:**  
54,984#'s 20/40 sand in 483 bbls Lightning  
17 frac fluid. Treated @ avg press of 1786 psi  
w/avg rate of 23.2 BPM. ISIP 2400 Calc  
flush: 5591 gal. Actual flush: 5586 gal.

9/1/05 4845-5005' **Frac B1, A.5, & A3 sand as follows:**  
150,088#'s 20/40 sand in 1004 bbls Lightning  
17 frac fluid. Treated @ avg press of 1542 psi  
w/avg rate of 23.5 BPM. ISIP 1930 psi. Calc  
flush: 4843 gal. Actual flush: 4872 gal.

9/1/05 4640-4647' **Frac D2 sand as follows:**  
31,189#'s 20/40 sand in 304 bbls Lightning  
17 frac fluid. Treated @ avg press of 1740 psi  
w/avg rate of 23.4 BPM. ISIP 2150 psi. Calc  
flush: 4638 gal. Actual flush: 4536 gal.

09/30/05 Stuck Pump (sanded in) Detailed rod and tubing details.

10/1/07 Pump change. Updated rod & tubing details.

9/29/09 Tubing Leak. Updated rod & tubing details.

**PERFORATION RECORD**

8/23/05	5784-5798'	4 JSPF	56 holes
8/31/05	5656-5664'	4 JSPF	32 holes
8/31/05	5593-5600'	4 JSPF	28 holes
9/1/05	5003-5005'	4 JSPF	8 holes
9/1/05	4939-4943'	4 JSPF	16 holes
9/1/05	4883-4890'	4 JSPF	28 holes
9/1/05	4855-4870'	4 JSPF	60 holes
9/1/05	4845-4850'	4 JSPF	20 holes
9/1/05	4640-4647'	4 JSPF	28 holes



Ashley Federal 4-24-9-15  
768' FNL & 797' FWL  
NW/NW Section 24-T9S-R15E  
Duchesne Co, Utah  
API #43-013-32646; Lease #UTU-66185

## Ashley Federal 3-24-9-15

Spud Date: 3-09-05  
 Put on Production: 5-5-05  
 GL: 6195' KB: 6201'

Initial Production: BOPD 91,  
 MCFD 65, BWPD 142

Injection Wellbore  
DiagramSURFACE CASING


CSG SIZE: 8-5/8"  
 GRADE: J-55  
 WEIGHT: 24#  
 LENGTH: 7 jts. (295.78')  
 DEPTH LANDED: 307.63' KB  
 HOLE SIZE: 12-1/4"  
 CEMENT DATA: 160 sxs Class "G" cmt, est 3 bbls cmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"  
 GRADE: J-55  
 WEIGHT: 15.5#  
 LENGTH: 164 jts. (5919.97')  
 DEPTH LANDED: 5919.22' KB  
 HOLE SIZE: 7-7/8"  
 CEMENT DATA: 300 sxs Prem. Lite II & 400 sxs 50/50 POZ.  
 CEMENT TOP AT: 610'

TUBING

SIZE/GRADE/WT.: 2-7/8" / I-55  
 NO. OF JOINTS: 123 jts (3959.02')  
 SEATING NIPPLE: 2-7/8" (1.10')  
 SN LANDED AT: 3971.02' KB  
 TOTAL STRING LENGTH: EOT @ 3979.22' KB

FRAC JOB

5-2-05 5798'-5822' Frac CP5 sand as follows:  
 79,389#s 20/40 sand in 620 bbls Lightning  
 17 frac fluid. Treated @ avg press of 1239 psi  
 w/avg rate of 24.7 BPM. ISIP 2300 psi. Calc  
 flush: 5797 gal. Actual flush: 5796 gal.

5-2-05 4824'-4865' Frac B2 & B1 sand as follows:  
 59,163#s 20/40 sand in 476 bbls Lightning  
 17 frac fluid. Treated @ avg press of 1559 psi  
 w/avg rate of 24.8 BPM. ISIP 2200 psi. Calc  
 flush: 4822 gal. Actual flush: 4872 gal.

5-2-05 4648'-4673' Frac D2 & D3 sand as follows:  
 44,546#s 20/40 sand in 399 bbls Lightning  
 17 frac fluid. Treated @ avg press of 1880 psi  
 w/avg rate of 24.7 BPM. ISIP 2225 psi. Calc  
 flush: 4646 gal. Actual flush: 4662 gal.

5-2-05 4394'-4398' Frac PB11 & 10 sand as follows:  
 38935#s 20/40 sand in 354 bbls Lightning  
 17 frac fluid. Treated @ avg press of 2232 psi  
 w/avg rate of 24.8 BPM. ISIP 2400 psi. Calc  
 flush: 4392 gal. Actual flush: 4368 gal.

5-2-05 4038'-4050' Frac GB4 sand as follows:  
 48636#s 20/40 sand in 399 bbls Lightning  
 17 frac fluid. Treated @ avg press of 1698 psi  
 w/avg rate of 24.8 BPM. ISIP 2120 psi. Calc  
 flush: 4036 gal. Actual flush: 2120 gal.

1/5/07 Well converted to an Injection well. MIT  
 completed and submitted.

PERFORATION RECORD

4-26-05	5798-5822'	4 JSPF	96 holes
5-2-05	4856-4865'	4 JSPF	36 holes
5-2-05	4824-4830'	4 JSPF	24 holes
5-2-05	4669-4673'	4 JSPF	16 holes
5-2-05	4648-4656'	4 JSPF	32 holes
5-2-05	4394-4398'	4 JSPF	16 holes
5-2-05	4364-4368'	4 JSPF	16 holes
5-2-05	4038-4050'	4 JSPF	48 holes

NEWFIELD

Ashley Federal 3-24-9-15  
 660' FNL & 1980' FWL  
 NE/NW Section 24-T9S-R15E  
 Duchesne Co, Utah  
 API #43-013-32483; Lease #UTU-66185

## Ashley Federal 6-24-9-15

Spud Date: 07/03/06  
Put on Production: 08/09/06

K.B.: 6253, G.L.: 6241

SURFACE CASING

CSG SIZE: 8-5/8"  
GRADE: J-55  
WEIGHT: 24#  
LENGTH: 7 jts. (310.14')  
DEPTH LANDED: 321.99' KB  
HOLE SIZE: 12-1/4"  
CEMENT DATA: 160 sxs Class "G" cmt, est 4 bbls cmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"  
GRADE: J-55  
WEIGHT: 15.5#  
LENGTH: 137 jts. (5976.93')  
DEPTH LANDED: 5990.18' KB  
HOLE SIZE: 7-7/8"  
CEMENT DATA: 325 sxs Prem. Lite II mixed & 450 sxs 50/50 POZ.  
CEMENT TOP: 82'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#  
NO. OF JOINTS: 179 jts (5663.51')  
TUBING ANCHOR: 5666' KB  
NO. OF JOINTS: 2 jts (63.40')  
SEATING NIPPLE: 2-7/8" (1.10')  
SN LANDED AT: 5731' KB  
NO. OF JOINTS: 2 jts (63.40')  
TOTAL STRING LENGTH: EOT @ 5795' KB

SUCKER RODS

POLISHED ROD: 1-1/2" x 26' SM  
SUCKER RODS: 1-8, 1-6', 1-2', x 3/4" pony rods, 100-3/4" guided rods, 91-3/4" sucker rods, 32-3/4" guided rods, 6-1 1/2" weight rods.  
PUMP SIZE: 2-1/2" x 1-1/2" x 13' x 16' RHAC w/SM plunger  
STROKE LENGTH: 86"  
PUMP SPEED, 5 SPM:

## Wellbore Diagram

Cement Top @ 82'

SN 5731'

EOT @ 5795'

PBTD @ 5945'

SHOE @ 5990'

TD @ 6012'

FRAC JOB

08/03/06 5690-5705' Frac CP4 sands as follows:  
45123# 20/40 sand 428 bbls Lightning 17  
frac fluid. Treated @ avg press of 1888 psi  
w/avg rate of 25 BPM. ISIP 1825 psi. Calc  
flush: 5703 gal. Actual flush: 5208 gal.

08/03/06 5586-5607' Frac CP2 sands as follows:  
55280# 20/40 sand in 468 bbls Lightning 17  
frac fluid. Treated @ avg press of 1869 psi  
w/avg rate of 25 BPM. ISIP 1930 psi. Calc  
flush: 5605 gal. Actual flush: 5040 gal.

08/03/06 5094-5176' Frac LODC sands as follows:  
109900# 20/40 sand in 779 bbls Lightning 17  
frac fluid. Treated @ avg press of 2124 psi  
w/avg rate of 25 BPM. ISIP 2350 psi. Calc  
flush: 5174 gal. Actual flush: 4578 gal.

08/03/06 4810-4888' Frac B1, B2 sands as follows:  
135567# 20/40 sand in 929 bbls Lightning 17  
frac fluid. Treated @ avg press of 1605 psi  
w/avg rate of 25.3 BPM. ISIP 1720 psi. Calc  
flush: 4886 gal. Actual flush: 4284 gal.

08/04/06 4034-4044' Frac GB4 sands as follows:  
52617# 20/40 sand in 442 bbls Lightning 17  
frac fluid. Treated @ avg press of 1691 psi  
w/avg rate of 25.1 BPM. ISIP 2120 psi. Calc  
flush: 4042 gal. Actual flush: 3906 gal.

04/04/07 Pump Change: Rod & tubing detail updated.  
5-15-07 Pump Change: Rod & tubing detail updated.  
04-08-10 Parted Rods: Rod & tubing detail updated.

PERFORATION RECORD

07/27/06	5690-5705'	4 JSPF	60 holes
08/03/06	5586-5607'	4 JSPF	84 holes
08/03/06	5160-5176'	4 JSPF	64 holes
08/03/06	5149-5156'	4 JSPF	28 holes
08/03/06	5094-5109'	4 JSPF	40 holes
08/03/06	4884-4888'	4 JSPF	16 holes
08/03/06	4870-4874'	4 JSPF	16 holes
08/03/06	4850-4866'	4 JSPF	64 holes
08/03/06	4810-4817'	4 JSPF	28 holes
08/03/06	4034-4044'	4 JSPF	40 holes

**NEWFIELD**

**Ashley Federal 6-24-9-15**

1913' FNL & 2076' FWL

SE/NW Section 24-T9S-R15E

Duchesne Co, Utah

API #43-013-32874; Lease #UTU-02458

Spud Date: 02/03/05

Put on Production: 03/21/05

GL: 6157' KB: 6169'

## Ashley 6-13-9-15

Injection Wellbore  
DiagramInitial Production: 22 BOPD,  
129 MCFD, 10 BWPDSURFACE CASING

CSG SIZE: 8-5/8"  
 GRADE: J-55  
 WEIGHT: 24#  
 LENGTH: 7 jts. (295.17')  
 DEPTH LANDED: 315' KB  
 HOLE SIZE: 12-1/4"  
 CEMENT DATA: 160 sxs Class "G" cmt, est: 4 bbls cmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"  
 GRADE: J-55  
 WEIGHT: 15.5#  
 LENGTH: 159 jts. (6114.88')  
 DEPTH LANDED: 6112.88' KB  
 HOLE SIZE: 7-7/8"  
 CEMENT DATA: 304 sxs Prem. Lite II mixed & 465 sxs 50/50 POZ.  
 CEMENT TOP AT: 315'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#  
 NO. OF JOINTS: 152 jts (5053')  
 SEATING NIPPLE: 2-7/8" (1.10')  
 SN LANDED AT: 5065' KB  
 ON/OFF TOOL AT: 5066.1'  
 ARROW #1 PACKER CE AT: 5071.2'  
 XO 2-3/8 x 2-7/8 J-55 AT: 5074.9'  
 TBG PUP 2-3/8 J-55 AT: 5075.4'  
 X/N NIPPLE AT: 5079.5'  
 TOTAL STRING LENGTH: EOT @ 5081.12'

FRAC JOB

03/14/05 5938'-5958' **Frac CPS sands as follows:**  
 60,121# 20/40 sand in 495 bbls Lightning 17 frac fluid. Treated @ avg press of 2021 psi w/avg rate of 25.1 BPM. ISIP 2500 psi. Calc flush: 5955 gal. Actual flush: 5964 gal.

3/14/05 5806'-5814' **Frac CP3 sands as follows:**  
 29,892# 20/40 sand in 326 bbls Lightning 17 frac fluid. Treated @ avg press of 1992 psi w/avg rate of 25.2 BPM. ISIP 2500 psi. Calc flush: 5814 gal. Actual flush: 5838 gal.

03/14/05 5632'-5637' **Frac CP1 sands as follows:**  
 20,165# 20/40 sand in 264 bbls Lightning 17 frac fluid. Treated @ avg press of 2280 psi w/avg rate of 25.1 BPM. ISIP 2550 psi. Calc flush: 5634 gal. Actual flush: 5670 gal.

3/15/05 5408'-5430' **Frac LODC sands as follows:**  
 74,581# 20/40 sand in 588 bbls Lightning 17 frac fluid. Treated @ avg press of 2548 psi w/avg rate of 25.1 BPM. ISIP 2240 psi. Calc flush: 5411 gal. Actual flush: 5460 gal.

3/15/05 5117'-5206' **Frac A3 & A1 sands as follows:**  
 65,622# 20/40 sand in 506 bbls Lightning 17 frac fluid. Treated @ avg press of 2340 psi w/avg rate of 25.2 BPM. ISIP 2240 psi. Calc flush: 5204 gal. Actual flush: 5040 gal.

08/04/06 **Pump Change.** Update rod and tubing details.

3/10/09 **Pump Change.** Updated r & t details.

9/21/09 **Pump Change.** Updated rod & tubing details.


03/13/10 **Pump Change.** Updated rod & tubing details.

11/19/13 **Convert to Injection Well**

11/21/13 **Conversion MIT Finalized - update tbg detail**

PERFORATION RECORD

Date	Depth Range	Tool Joint	Holes
3/08/05	5938'-5958'	4 JSPP	80 holes
3/14/05	5806'-5814'	4 JSPP	32 holes
3/14/05	5632'-5637'	4 JSPP	20 holes
3/14/05	5420'-5430'	4 JSPP	40 holes
3/14/05	5408'-5414'	4 JSPP	24 holes
3/15/05	5193'-5206'	4 JSPP	52 holes
3/15/05	5117'-5125'	4 JSPP	32 holes

**NEWFIELD**

Ashley 6-13-9-15  
 1992' FNL & 2268' FWL  
 SENW Section 13-T9S-R15E  
 Duchesne Co. Utah  
 API #43-013-32464; Lease #UTU-66184





## Schematic

43-013-52363

Well Name: GMBU R-13-9-15

Surface Legal Location NESW 1773 FSL 2080 FWL Sec 13 T9S R15E Mer SLB			API/UWI 43013523630000	Well RC 500346530	Lease UTU66184	State/Province Utah	Field Name GMBU CTB3	County Duchesne
Spud Date 1/28/2014	Rig Release Date 2/14/2014	On Production Date 3/11/2014	Original KB Elevation (ft) 6,170	Ground Elevation (ft) 6,160	Total Depth All (TVD) (ftKB) Original Hole - 6,096.6		PBTD (All) (ftKB)	

## Most Recent Job

Job Category Initial Completion	Primary Job Type Fracture Treatment	Secondary Job Type P&P	Job Start Date 2/28/2014	Job End Date 3/11/2014
------------------------------------	--	---------------------------	-----------------------------	---------------------------

TD: 6,160.0

Original Hole, 5/15/2014 9:05:34 AM

MD (ftKB)	TVD (ftKB)	Incl (°)	DLS	DLS (° ...)	Vertical schematic (actual)
0.0	0.0	0.8			
	2.0				
9.8	9.9	0.8			
	10.2				
10.8	10.8	0.8			
	12.2				
14.1	14.1	0.8			
	15.1				
32.2	32.2	0.8			
	36.1				
42.0	42.0	0.8			
	49.9				
54.1	54.2	0.8			
	273.3				
274.3	274.3	0.8			
	318.2				
319.6	319.5	0.8			
	325.1				
2,049.9	2,033.7	10.7			
	3,335.4				
3,387.8	3,345.9	11.8			
	4,860.1				
5,024.0	4,956.8	9.5			
	5,070.4				
5,200.1	5,130.6	9.5			
	5,240.0				
5,558.1	5,483.6	9.5			
	5,487.5				
5,821.9	5,743.8	9.5			
	5,746.1				
5,924.2	5,844.8	9.5			
	5,847.7				
5,936.0	5,856.4	9.5			
	5,858.3				
5,945.9	5,866.1	9.5			
	5,868.4				
5,950.1	5,870.3	9.5			
	5,874.2				
5,956.0	5,876.1	9.5			
	5,879.1				
5,960.3	5,880.3	9.5			
	5,893.9				
6,023.3	5,942.5	9.5			
	5,943.1				
6,096.5	6,014.6	9.5			
	6,016.6				
6,142.4	6,059.9	9.5			
	6,060.9				
6,160.1	6,077.4	9.5			



## NEWFIELD

## Schematic

43-013-52364

Well Name: GMBU M-13-9-15


Surface Legal Location		API/UWI		Well RC	Lease	State/Province	Field Name	County
NESW 1784 FSL 2061 FWL Sec 13 T9S R15E Mer SLB		43013523640000		500346526	UTU66184	Utah	GMBU CTB2	Duchesne
Spud Date	Rig Release Date	On Production Date	Original KB Elevation (ft)	Ground Elevation (ft)	Total Depth All (TVD) (ftKB)	PBDT (All) (ftKB)		
2/8/2014	2/11/2014	3/6/2014	6,170	6,160	Original Hole - 6,136.4	Original Hole - 6,276.0		

## Most Recent Job

Job Category	Primary Job Type	Secondary Job Type	Job Start Date	Job End Date
Initial Completion	Fracture Treatment	P&P	2/28/2014	3/6/2014

TD: 6,327.0

Slant - Original Hole, 5/15/2014 9:05:07 AM





## NEWFIELD

## Schematic

43-013-52365

Well Name: GMBU S-13-9-15


Surface Legal Location		API/UWI	Well RC	Lease	State/Province	Field Name	County
NWSE 1933 FSL 1921 FEL Sec 13 T9S R15E		43013523650000	500346536	UTU66184	Utah	GMBU CTB3	Duchesne
Spud Date	Rig Release Date	On Production Date	Original KB Elevation (ft)	Ground Elevation (ft)	Total Depth All (TVD) (ftKB)	PSTD (All) (ftKB)	Original Hole - 6,175.4
1/30/2014	2/22/2014	3/20/2014	6,127	6,117	Original Hole - 6,081.2		

## Most Recent Job

Job Category	Primary Job Type	Secondary Job Type	Job Start Date	Job End Date
Initial Completion	Fracture Treatment	P&P	3/7/2014	3/20/2014

TD: 6,219.0

Slant - Original Hole, 8/18/2014 8:39:24 AM





## NEWFIELD

## Schematic

Well Name: GMBU L-13-9-15

43-013-52366


Surface Legal Location	APU/UWI	Well RC	Lease	State/Province	Field Name	County
NWSE 1936 FSL 1942 FEL Sec 13 T9S R15E Mer SLB	43013523660000	500348435	UTU66184	Utah	GMBU CTB2	Duchesne
Spud Date	Rig Release Date	On Production Date	Original KB Elevation (ft)	Ground Elevation (ft)	Total Depth All (TVD) (ftKB)	PBTD (All) (ftKB)
1/29/2014	2/18/2014		6,127	6,117	Original Hole - 6,119.9	Original Hole - 6,239.5

## Most Recent Job

Job Category	Primary Job Type	Secondary Job Type	Job Start Date	Job End Date
Initial Completion	Fracture Treatment	P&P	3/7/2014	3/17/2014

TD: 6,295.0

Slant - Original Hole, 8/18/2014 8:39:56 AM





Well Name: GMBU H-24-9-15

43-013-52386


Surface Legal Location		API/UWI	Well RC	Lease	State/Province	Field Name	County
NWNE 677 FNL 1759 FEL Sec 24 T9S R15E		43013523860000	500366837	UTU66185	Utah	GMBU CTB3	Duchesne
Spud Date	Rig Release Date	On Production Date	Original KB Elevation (ft)	Ground Elevation (ft)	Total Depth All (TVD) (ftKB)	PBTD (All) (ftKB)	Original Hole - 6,320.9
7/3/2014	7/17/2014		6,199	6,188	Original Hole - 6,193.1		

## Most Recent Job

Job Category	Primary Job Type	Secondary Job Type	Job Start Date	Job End Date
Initial Completion	Fracture Treatment	P&P	8/4/2014	8/8/2014

TD: 6,386.0

Slant - Original Hole, 8/22/2014 9:31:28 AM

MD (ftKB)	TVD (ftKB)	Incl (°)	DLS	Vertical schematic (actual)	
			DLS (°...		
0.0	0.0	0.0			
11.8	11.8	0.0			
15.1	15.1	0.1			
29.9	29.9	0.1			
36.1	36.1	0.1		1-1; Tubing Hanger; 7; 2.441; 11-12; 0.90	
49.9	49.9	0.2		1; Conductor; 14 in; 13.500 in; 11-16 ftKB; 5.00 ft	
281.5	281.5	1.1		2; Surface; 8 5/8 in; 8.097 in; 11-329 ftKB; 318.19 ft	
327.8	327.7	1.3			
336.0	335.9	1.3			
3,392.4	3,298.6	20.4			
4,790.0	4,632.6	17.9		1-2; Tubing; 2 7/8; 2.441; 12-5,848; 5,835.61	
4,815.9	4,657.3	17.8		Perforated; 4,790-4,792; 8/5/2014	
4,967.8	4,802.4	16.7		Perforated; 4,816-4,820; 8/5/2014	
4,983.9	4,817.8	16.9		Perforated; 4,968-4,969; 8/5/2014	
4,998.0	4,831.3	17.1		Perforated; 4,984-4,985; 8/5/2014	
5,012.1	4,844.8	17.3		Perforated; 4,998-5,000; 8/5/2014	
5,036.1	4,867.7	16.9		Perforated; 5,012-5,014; 8/5/2014	
5,149.9	4,976.9	16.2		Perforated; 5,036-5,040; 8/5/2014	
5,571.9	5,386.3	11.7		Perforated; 5,570-5,572; 8/5/2014	
5,582.0	5,396.3	11.7		Perforated; 5,580-5,582; 8/5/2014	
5,764.1	5,575.3	9.5		Perforated; 5,762-5,764; 8/4/2014	
5,840.9	5,651.1	8.8		Perforated; 5,838-5,841; 8/4/2014	
5,850.4	5,660.5	8.7		1-3; Anchor/catcher; 4.95; 2.441; 5,848-5,850; 2.80	
5,859.9	5,669.9	8.6		Perforated; 5,856-5,860; 8/4/2014	
5,883.2	5,692.9	8.4		1-4; Tubing; 2 7/8; 2.441; 5,850-5,883; 32.97	
5,899.0	5,708.5	8.3		1-5; Pump Seating Nipple; 2 7/8; 2.250; 5,883-5,884; 1.10	
5,921.3	5,730.6	8.2		1-6; Tubing; 2 7/8; 2.441; 5,884-5,917; 32.97	
6,004.3	5,812.8	7.3		1-7; Tubing Pup Joint; 2 7/8; 2.441; 5,917-5,921; 4.02	
6,320.9	6,128.0	3.3		1-8; Desander; 3 1/2; 1.000; 5,921-5,938; 17.06	
6,366.8	6,173.9	3.3		1-9; Tubing; 2 7/8; 2.441; 5,938-6,004; 65.97	
6,386.2	6,193.2	3.3		1-10; Valve; 2 7/8; 0.000; 6,004-6,005; 0.80	
				3; Production; 5 1/2 in; 4.950 in; 11-6,368 ftKB; 6,356.77 ft	



## NEWFIELD

## Schematic

Well Name: GMBU I-24-9-15

43-013-52387


Surface Legal Location		API/UWI	Well RC	Lease	State/Province	Field Name	County
NWNE 688 FNL 1741 FEL Sec 24 T9S R15E		43013523870000	500366841	UTU66185	Utah	GMBU CTB3	Duchesne
Spud Date	Rig Release Date	On Production Date	Original KB Elevation (ft)	Ground Elevation (ft)	Total Depth All (TVD) (ftKB)	PBTD (All) (ftKB)	Original Hole - 6,260.8
7/4/2014	7/20/2014		6,199	6,188	Original Hole - 6,225.1		

## Most Recent Job

Job Category	Primary Job Type	Secondary Job Type	Job Start Date	Job End Date
Initial Completion	Fracture Treatment	P&P	8/4/2014	8/12/2014

TD: 6,322.0

Slant - Original Hole, 8/22/2014 9:36:53 AM





## NEWFIELD

## Schematic

Well Name: GMBU B-24-9-15

43-013-52469


Surface Legal Location SWSE 555 FSL 2034 FEL Sec 13 T9S R15E				API/UWI 43013524690000	Well RC 500366601	Lease UTU68548	State/Province Utah	Field Name GMBU CTB3	County Duchesne
Spud Date 5/16/2014	Rig Release Date 5/29/2014	On Production Date 7/1/2014	Original KB Elevation (ft) 6,154	Ground Elevation (ft) 6,144	Total Depth All (TVD) (ftKB)		PBD (All) (ftKB) Original Hole - 6,239.7		

## Most Recent Job

Job Category Initial Completion	Primary Job Type Fracture Treatment	Secondary Job Type P&P	Job Start Date 6/16/2014	Job End Date 7/1/2014
------------------------------------	--	---------------------------	-----------------------------	--------------------------

TD: 6,274.0

Slant - Original Hole, 8/22/2014 9:29:06 AM







## Schematic

43-013-52470

Well Name: GMBU C-24-9-15

Surface Legal Location SWSE 534 FSL 2032 FEL Sec 13 T9S R15E				API/UWI 43013524700000	Well RC 500366663	Lease UTU68548	State/Province Utah	Field Name GMBU CTB3	County Duchesne
Spud Date 5/19/2014	Rig Release Date 6/1/2014	On Production Date 7/1/2014	Original KB Elevation (ft) 6,154	Ground Elevation (ft) 6,144	Total Depth All (TVD) (ftKB) Original Hole - 6,061.0	PSTD (All) (ftKB) Original Hole - 6,123.6			

## Most Recent Job

Job Category Initial Completion	Primary Job Type Fracture Treatment	Secondary Job Type P&P	Job Start Date 6/16/2014	Job End Date 7/1/2014
------------------------------------	--	---------------------------	-----------------------------	--------------------------

TD: 6,175.0

Slant - Original Hole, 8/22/2014 9:30:24 AM

MD (ftKB)	TVD (ftKB)	Incl (°)	DLS	DLS (° ...)	Vertical schematic (actual)
2.0	2.0	1.2			<p>1-1; Tubing Hanger; 7; 2.441; 10-11; 0.90</p> <p>1; Conductor; 14 in; 13.500 in; 10-15 ftKB; 5.00 ft</p> <p>2; Surface; 8 5/8 in; 8.097 in; 10-320 ftKB; 310.03 ft</p> <p>1-2; Tubing; 2 7/8; 2.441; 11-5,846; 5,835.03</p> <p>Perforated; 4,215-4,219; 6/18/2014</p> <p>Perforated; 4,755-4,757; 6/18/2014</p> <p>Perforated; 4,762-4,766; 6/18/2014</p> <p>Perforated; 4,920-4,921; 6/18/2014</p> <p>Perforated; 4,950-4,952; 6/18/2014</p> <p>Perforated; 5,085-5,088; 6/18/2014</p> <p>Perforated; 5,160-5,164; 6/18/2014</p> <p>Perforated; 5,238-5,239; 6/18/2014</p> <p>Perforated; 5,249-5,250; 6/18/2014</p> <p>Perforated; 5,262-5,263; 6/18/2014</p> <p>Perforated; 5,368-5,369; 6/18/2014</p> <p>Perforated; 5,506-5,508; 6/18/2014</p> <p>Perforated; 5,516-5,520; 6/18/2014</p> <p>Perforated; 5,687-5,688; 6/18/2014</p> <p>1-3; Anchor/catcher; 4 1/2; 2.441; 5,846-5,849; 2.80</p> <p>Perforated; 5,876-5,880; 6/18/2014</p> <p>1-4; Tubing; 2 7/8; 2.441; 5,849-5,915; 65.98</p> <p>1-5; Pump Seating Nipple; 2 7/8; 2.250; 5,915-5,916; 1.10</p> <p>1-6; Tubing; 2 7/8; 2.441; 5,916-5,949; 32.98</p> <p>1-7; Tubing Pup Joint; 2 7/8; 2.441; 5,949-5,953; 4.10</p> <p>1-8; Desander; 3.67; 0.000; 5,953-5,972; 19.00</p> <p>1-9; Tubing; 2 7/8; 2.441; 5,972-6,005; 32.98</p> <p>1-10; Valve; 3.67; 6,005-6,006; 0.80</p> <p>Perforated; 6,036-6,037; 6/16/2014</p> <p>Perforated; 6,040-6,041; 6/16/2014</p> <p>Perforated; 6,048-6,049; 6/16/2014</p> <p>Perforated; 6,055-6,057; 6/16/2014</p> <p>Perforated; 6,068-6,070; 6/16/2014</p> <p>3; Production; 5 1/2 in; 4.950 in; 10-6,170 ftKB; 6,160.15 ft</p>
10.2	10.2	1.2			
11.8	11.9	1.2			
15.1	15.1	1.2			
34.1	34.2	1.2			
53.8	53.8	1.2			
274.6	274.6	1.2			
319.9	319.9	1.2			
1,841.5	1,826.5	13.9			
3,412.4	3,354.3	12.0			
4,219.2	4,142.6	13.5			
4,756.9	4,664.8	12.7			
4,766.1	4,673.8	12.6			
4,920.9	4,825.4	11.4			
4,952.1	4,855.9	11.5			
5,087.9	4,989.4	10.3			
5,164.0	5,064.3	9.8			
5,237.9	5,137.1	9.5			
5,249.0	5,148.1	9.6			
5,262.1	5,161.0	9.6			
5,368.1	5,265.5	9.8			
5,505.9	5,401.4	9.1			
5,516.1	5,411.5	9.1			
5,687.0	5,580.3	9.2			
5,700.1	5,593.3	9.3			
5,845.8	5,736.9	9.9			
5,876.0	5,766.6	10.1			
5,914.7	5,804.7	10.3			
5,924.9	5,814.7	10.3			
5,952.8	5,842.2	10.1			
6,004.9	5,893.5	9.6			
6,036.1	5,924.3	9.8			
6,040.0	5,928.1	9.9			
6,047.9	5,935.9	9.9			
6,055.1	5,943.0	10.0			
6,067.9	5,955.6	10.1			
6,123.7	6,010.5	10.2			
6,169.3	6,055.4	10.2			
6,174.9	6,060.9	10.2			



**Multi-Chem Group, LLC**

Multi-Chem Analytical Laboratory  
1553 East Highway 40  
Vernal, UT 84078

multi-chem®

**Water Analysis Report**Production Company: **NEWFIELD PRODUCTION (158)**Sample ID: **WA-53130**Well Name: **Ashley IF**Sample Point: **tank**Sample Date: **1 /7 /2011**Sales Rep: **Monty Frost**Lab Tech: **Peter Poulsen**

Sample Specifics		Analysis @ Properties in Sample Specifics			
Test Date:	1/24/2011	<b>Cations</b>	<b>mg/L</b>	<b>Anions</b>	<b>mg/L</b>
Temperature (°F):	100	Calcium (Ca):	34.57	Chloride (Cl):	3000.00
Sample Pressure (psig):		Magnesium (Mg):	18.40	Sulfate (SO <sub>4</sub> ):	10.00
Specific Gravity (g/cm³):	1.0017	Barium (Ba):	7.62	Dissolved CO <sub>2</sub> :	-
pH:	7.98	Strontium (Sr):	-	Bicarbonate (HCO <sub>3</sub> ):	927.00
Turbidity (NTU):	-	Sodium (Na):	2218.00	Carbonate (CO <sub>3</sub> ):	-
		Potassium (K):	-	H <sub>2</sub> S:	1.00
		Iron (Fe):	0.32	Phosphate (PO <sub>4</sub> ):	-
		Manganese (Mn):	0.02	Silica (SiO <sub>2</sub> ):	-
		Lithium (Li):	-	Fluoride (F):	-
Calculated T.D.S. (mg/L)	6217	Aluminum (Al):	-	Nitrate (NO <sub>3</sub> ):	-
Molar Conductivity (µS/cm):	9420	Ammonia NH <sub>3</sub> :	-	Lead (Pb):	-
Resistivity (Mohm):	1.0616			Zinc (Zn):	-
				Bromine (Br):	-
				Boron (B):	-

Test Conditions		Scale Values @ Test Conditions - Potential Amount of Scale in lb/1000bbl											
		Calcium Carbonate CaCO <sub>3</sub>		Gypsum CaSO <sub>4</sub> · 2H <sub>2</sub> O		Calcium Sulfate CaSO <sub>4</sub>		Strontium Sulfate SrSO <sub>4</sub>		Barium Sulfate BaSO <sub>4</sub>		Calculated CO <sub>2</sub>	
		Sat Index	Scale	Sat Index	Scale	Sat Index	Scale	Sat Index	Scale	Sat Index	Scale	psi	
Temp °F	Gauge Press. psi												
100		4.86	11.91	0.00	-2023.00	0.00	-2138.60	-	-	2.71	6.25	0.26	
80	0	3.61	8.98	0.00	3.62	0.00	-2280.60	-	-	4.10	8.00	0.13	
100	0	4.86	11.91	0.00	7.31	0.00	-2138.70	-	-	2.71	6.25	0.16	
120	0	6.11	14.46	0.00	10.28	0.00	-1932.90	-	-	1.83	4.19	0.17	
140	0	7.38	16.89	0.00	12.81	0.00	-1692.50	-	-	1.27	1.80	0.20	
160	0	8.59	19.05	0.00	14.86	0.00	-1442.00	-	-	0.89	-0.93	0.22	
180	0	9.63	20.78	0.00	16.27	0.00	-1199.60	-	-	0.64	-4.03	0.24	
200	0	10.46	21.95	0.00	16.91	0.00	-977.39	-	-	0.47	-7.51	0.24	
220	2.51	10.94	22.56	0.00	16.78	0.00	-789.27	-	-	0.34	-11.65	0.25	
240	10.3	11.20	22.38	0.00	15.91	0.00	-621.34	-	-	0.25	-16.09	0.25	
260	20.76	11.19	21.60	0.00	14.67	0.00	-481.36	-	-	0.19	-21.06	0.25	
280	34.54	10.93	20.30	0.00	13.32	0.00	-367.07	-	-	0.14	-26.63	0.26	
300	52.34	10.47	18.65	0.00	11.99	0.01	-275.34	-	-	0.11	-32.87	0.26	

**Conclusions:****Notes:**

Calcium Carbonate scale is indicated at all temps from 80°F to 300°F

Gypsum Scaling Index is negative from 80°F to 300°F

Calcium Sulfate Scaling Index is negative from 80°F to 300°F

Strontium Sulfate scaling was not evaluated

Barium Sulfate NO CONCLUSION







**Multi-Chem Group, LLC**

Multi-Chem Analytical Laboratory

1553 East Highway 40

Vernal, UT 84078

multi-chem®

**Scale Prediction Graphs**Well Name: **Ashley IF**Sample ID: **WA-53130**

**Multi-Chem Group, LLC**

Multi-Chem Analytical Laboratory  
1553 East Highway 40  
Vernal, UT 84078

multi-chem®

**Water Analysis Report**Production Company: **NEWFIELD PRODUCTION (158)**Sample ID: **WA-53124**Well Name: **Ashley fed 14-13-9-15**Sample Point: **tank**Sample Date: **1 /7 /2011**Sales Rep: **Monty Frost**Lab Tech: **Peter Poulsen**

Sample Specifics		Analysis @ Properties in Sample Specifics			
Test Date:	1/24/2011	<b>Cations</b>	<b>mg/L</b>	<b>Anions</b>	<b>mg/L</b>
Temperature (°F):	140	Calcium (Ca):	4.78	Chloride (Cl):	2000.00
Sample Pressure (psig):		Magnesium (Mg):	2.01	Sulfate (SO <sub>4</sub> ):	7.00
Specific Gravity (g/cm <sup>3</sup> ):	1.0071	Barium (Ba):	4.09	Dissolved CO <sub>2</sub> :	-
pH:	8.4	Strontium (Sr):	-	Bicarbonate (HCO <sub>3</sub> ):	6344.00
Turbidity (NTU):	-	Sodium (Na):	3654.00	Carbonate (CO <sub>3</sub> ):	-
		Potassium (K):	-	H <sub>2</sub> S:	5.50
		Iron (Fe):	0.49	Phosphate (PO <sub>4</sub> ):	-
		Manganese (Mn):	0.16	Silica (SiO <sub>2</sub> ):	-
		Lithium (Li):	-	Fluoride (F):	-
Calculated T.D.S. (mg/L)	12022	Aluminum (Al):	-	Nitrate (NO <sub>3</sub> ):	-
Molar Conductivity (µS/cm):	18215	Ammonia NH <sub>3</sub> :	-	Lead (Pb):	-
Resitivity (Mohm):	0.5490			Zinc (Zn):	-
				Bromine (Br):	-
				Boron (B):	-

Test Conditions		Scale Values @ Test Conditions - Potential Amount of Scale in lb/1000bbl											
		Calcium Carbonate CaCO <sub>3</sub>		Gypsum CaSO <sub>4</sub> · 2H <sub>2</sub> O		Calcium Sulfate CaSO <sub>4</sub>		Strontium Sulfate SrSO <sub>4</sub>		Barium Sulfate BaSO <sub>4</sub>		Calculated CO <sub>2</sub>	
		Sat Index	Scale	Sat Index	Scale	Sat Index	Scale	Sat Index	Scale	Sat Index	Scale	psi	
Temp °F	Gauge Press. psi												
140		5.36	2.86	0.00	-2032.70	0.00	-1993.30	-	-	0.36	-6.49	0.58	
80	0	4.02	4.36	0.00	0.89	0.00	-2670.40	-	-	1.17	0.71	0.31	
100	0	4.64	3.82	0.00	1.38	0.00	-2510.90	-	-	0.77	-1.35	0.37	
120	0	5.06	3.30	0.00	1.45	0.00	-2274.00	-	-	0.52	-3.75	0.42	
140	0	5.36	2.86	0.00	1.34	0.00	-1993.30	-	-	0.36	-6.49	0.46	
160	0	5.55	2.53	0.00	1.17	0.00	-1698.20	-	-	0.26	-9.57	0.52	
180	0	5.66	2.30	0.00	1.01	0.00	-1411.60	-	-	0.19	-12.99	0.56	
200	0	5.69	2.15	0.00	0.86	0.00	-1149.20	-	-	0.14	-16.78	0.56	
220	2.51	5.65	2.08	0.00	0.75	0.00	-929.27	-	-	0.10	-21.31	0.57	
240	10.3	5.59	2.06	0.00	0.66	0.00	-733.97	-	-	0.08	-26.06	0.57	
260	20.76	5.48	2.08	0.00	0.58	0.00	-573.05	-	-	0.06	-31.37	0.57	
280	34.54	5.35	2.14	0.00	0.52	0.00	-443.30	-	-	0.05	-37.33	0.58	
300	52.34	5.18	2.23	0.00	0.47	0.00	-340.41	-	-	0.04	-44.06	0.58	

**Conclusions:**

Calcium Carbonate scale is indicated at all temps from 80°F to 300°F

Gypsum Scaling Index is negative from 80°F to 300°F

Calcium Sulfate Scaling Index is negative from 80°F to 300°F

Strontium Sulfate scaling was not evaluated

Barium Sulfate NO CONCLUSION

**Notes:**







**Multi-Chem Group, LLC**

Multi-Chem Analytical Laboratory

1553 East Highway 40

Vernal, UT 84078

multi-chem®

**Scale Prediction Graphs**Well Name: **Ashley fed 14-13-9-15**Sample ID: **WA-53124**

**Attachment "G"**

**Ashley Federal #14-13-9-15  
Proposed Maximum Injection Pressure**

Frac Interval (feet)		Avg. Depth (feet)	ISIP (psi)	Calculated Frac Gradient (psi/ft)	Pmax
Top	Bottom				
4828	4900	4864	2300	0.91	2269
4754	4762	4758	3650	1.20	3619
4672	4678	4675	2030	0.87	2000 ←
4006	4024	4015	2610	1.08	2584
				Minimum	<u>2000</u>

**Calculation of Maximum Surface Injection Pressure**

$P_{max} = (\text{Frac Grad} - (0.433 \times 1.015)) \times \text{Depth of Top Perf}$   
where pressure gradient for the fresh water is .433 psi/ft and  
specific gravity of the injected water is 1.015.

$\text{Frac Gradient} = (\text{ISIP} + (0.433 \times \text{Top Perf.})) / \text{Top Perf.}$

**Please note:** These are existing perforations; additional perforations may be added during the actual conversion procedure.



## DAILY COMPLETION REPORT

WELL NAME: Ashley Federal 14-13-9-15

Report Date: Sept. 16, 2005

Day: 01

Operation: Completion

Rig: Rigless

## WELL STATUS

Surf Csg: 8 5/8 @ 314'

Prod Csg: 5 1/2" @ 5977'

Csg PBTD: 5874' WL

Tbg: Size: Wt:

Grd: Pkr/EOT @:

BP/Sand PBTD:

## PERFORATION RECORD

Zone	Perfs	SPF/#shots	Zone	Perfs	SPF/#shots
B .5 sds	4828-4832'	4/16			
B2 sds	4894-4900'	4/24			

## CHRONOLOGICAL OPERATIONS

Date Work Performed: Sept. 15, 2005

SITP: SICP: 0

Install 5M frac head. NU 6" 5M Cameron BOP. RU H/O truck & pressure test casing, blind rams, frac head & casing valves to 4500 psi. RU Perforators WLT w/ mast & run CBL under pressure. WLTD @ 5874' & cmt top @ 91'. Perforate stage #1 W/ 4" ported guns as follows: B2 sds @ 4894-4900' and B .5 sds @ 4828-32'. All 4 JSPF in 1 run. SIFN W/ est 141 BWTR.

## FLUID RECOVERY (BBLs)

Starting fluid load to be recovered: 141

Starting oil rec to date:

Fluid lost/recovered today: 0

Oil lost/recovered today:

Ending fluid to be recovered: 141

Cum oil recovered:

IFL: FFL: FTP: Choke: Final Fluid Rate: Final oil cut:

## STIMULATION DETAIL

## COSTS

Base Fluid used: Job Type:

Company:

Procedure or Equipment detail:

Weatherford BOP	\$140
NPC NU crew	\$300
NDSI trucking	\$1,200
Drilling cost	\$262,920
NDSI HO trk	\$400
Location preparation	\$300
Admin. Overhead	\$3,000
Benco Anchors	\$1,200
NPC wellhead	\$1,500
Perforators - CBL/perf	\$5,328
NPC supervision	\$300

Max TP: Max Rate: Total fluid pmpd:

Avg TP: Avg Rate: Total Prop pmpd:

ISIP: 5 min: 10 min: 15 min:

Completion Supervisor: Gary Dietz

DAILY COST: \$276,588

TOTAL WELL COST: \$276,588



## DAILY COMPLETION REPORT

WELL NAME: Ashley Federal 14-13-9-15

Report Date: Sept. 20, 2005

Day: 2a

Operation: Completion

Rig: Rigless

## WELL STATUS

Surf Csg: 8 5/8 @ 314'

Prod Csg: 5 1/2" @ 5977'

Csg PBTD: 5874' WL

Tbg: Size: Wt:

Grd: Pkr/EOT @:

BP/Sand PBTD:

## PERFORATION RECORD

Zone	Perfs	SPF/#shots	Zone	Perfs	SPF/#shots
B .5 sds	4828-4832'	4/16			
B2 sds	4894-4900'	4/24			

## CHRONOLOGICAL OPERATIONS

Date Work Performed: Sept. 19, 2005

SITP: SICP: 125

Day2a.

RU BJ Services "Ram Head" frac flange. RU BJ & frac B sds, stage #1 down casing w/ 59,638#'s of 20/40 sand in 476 bbls of Lightning 17 frac fluid. Open well w/ 125 psi on casing. Perfs broke down @ 2560 psi, back to 1270 psi. Treated @ ave pressure of 1690 w/ ave rate of 25 bpm w/ 8 ppg of sand. Spot 5 bbls of 15% HCL in flush for next stage. ISIP was 2300. 617 bbls EWTR. Leave pressure on well. See day2b.

## FLUID RECOVERY (BBLs)

Starting fluid load to be recovered: 141

Starting oil rec to date:

Fluid lost/recovered today: 476

Oil lost/recovered today:

Ending fluid to be recovered: 617

Cum oil recovered:

IFL: FFL: FTP: Choke: Final Fluid Rate: Final oil cut:

## STIMULATION DETAIL

Base Fluid used: Lightning 17 Job Type: Sand frac

Company: BJ Services

Procedure or Equipment detail: B2 &amp; B.5 sds down casing

4620 gals of pad

3000 gals w/ 1-5 ppg of 20/40 sand

6000 gals w/ 5-8 ppg of 20/40 sand

1290 gals w/ 8 ppg of 20/40 sand

210 gals of 15% HCL acid

Flush w/ 4872 gals of slick water

\*\*Flush called @ blender to include 2 bbls pump/line volume\*\*

Max TP: 1925 Max Rate: 25.2 Total fluid pmpd: 476 bbls

Avg TP: 1690 Avg Rate: 25 Total Prop pmpd: 59,638#'s

ISIP: 2300 5 min: 10 min: FG: .91

Completion Supervisor: Ron Shuck

## COSTS

Weatherford BOP \$70

Weatherford Services \$700

Betts frac water \$810

NPC fuel gas \$162

BJ Services B sds \$21,987

NPC Supervisor \$85

DAILY COST: \$23,814

TOTAL WELL COST: \$300,402



## DAILY COMPLETION REPORT

WELL NAME: Ashley Federal 14-13-9-15

Report Date: Sept. 20, 2005

Day: 2b

Operation: Completion

Rig: Rigless

## WELL STATUS

Surf Csg: 8 5/8 @ 314'

Prod Csg: 5 1/2" @ 5977'

Csg PBTD: 5874' WL

Tbg: Size: Wt:

Grd: Pkr/EOT @:

BP/Sand PBTD: 4800'

## PERFORATION RECORD

Zone	Perfs	SPF/#shots	Zone	Perfs	SPF/#shots
C sds	4754-4762'	4/32			
B .5 sds	4828-4832'	4/16			
B2 sds	4894-4900'	4/24			

## CHRONOLOGICAL OPERATIONS

Date Work Performed: Sept. 19, 2005

SITP: SICP: 1256

Day2b.

RU Black Warrior WLT, crane & lubricator. RIH w/ Weatherford 5-1/2" composite flow through frac & 8' perf gun. Set plug @ 4800'. Perforate C sds @ 4754-4762' w/ 4" Port Guns (19 gram, .41"HE, 120°) w/ 4 spf for total of 32 shot. RU BJ & perfs won't break down. RIH & spot 10 gals of 15% HCL acid on perfs. RU BJ & frac stage #2 w/ 49,648#'s of 20/40 sand in 418 bbls of Lightning 17 frac fluid. Open well w/ 1256 psi on casing. Perfs broke down @ 3293 psi, back to 2150 psi. Treated @ ave pressure of 2308 w/ ave rate of 28.5 bpm w/ 8 ppg of sand. Spot 5 bbls of 15% HCL in flush for next stage. ISIP was 3650. 1035 bbls EWTR. Leave pressure on well. See day2c.

## FLUID RECOVERY (BBLs)

Starting fluid load to be recovered: 617

Starting oil rec to date:

Fluid lost/recovered today: 418

Oil lost/recovered today:

Ending fluid to be recovered: 1035

Cum oil recovered:

IFL: FFL: FTP: Choke: Final Fluid Rate: Final oil cut:

## STIMULATION DETAIL

Base Fluid used: Lightning 17 Job Type: Sand frac

Company: BJ Services

Procedure or Equipment detail: C sds down casing

## COSTS

Weatherford BOP \$70

Weatherford Services \$2,200

Betts frac water \$690

NPC fuel gas \$135

BJ Services C sds \$12,774

NPC Supervisor \$85

BWWC C sds \$4,490

3822 gals of pad

2625 gals w/ 1-5 ppg of 20/40 sand

5250 gals w/ 5-8 ppg of 20/40 sand

836 gals w/ 8 ppg of 20/40 sand

210 gals of 15% HCL acid

Flush w/ 4788 gals of slick water

\*\*Flush called @ blender to include 2 bbls pump/line volume\*\*

Max TP: 2485 Max Rate: 31.8 Total fluid pmpd: 418 bbls

Avg TP: 2308 Avg Rate: 28.5 Total Prop pmpd: 49,648#'s

ISIP: 3650 5 min: 10 min: FG: 1.2

Completion Supervisor: Ron Shuck

DAILY COST: \$20,444

TOTAL WELL COST: \$320,846



## DAILY COMPLETION REPORT

WELL NAME: Ashley Federal 14-13-9-15Report Date: Sept. 20, 2005Day: 2cOperation: CompletionRig: Rigless

## WELL STATUS

Surf Csg: 8 5/8 @ 314'  
Tbg: Size: \_\_\_\_\_ Wt: \_\_\_\_\_Prod Csg: 5 1/2" @ 5977'  
Grd: \_\_\_\_\_ Pkr/EOT @: \_\_\_\_\_Csg PBTD: 5874' WL  
BP/Sand PBTD: 4720'  
Plug 4800'

## PERFORATION RECORD

Zone	Perfs	SPF/#shots	Zone	Perfs	SPF/#shots
D2 sds	4672-4678'	4/24			
C sds	4754-4762'	4/32			
B .5 sds	4828-4832'	4/16			
B2 sds	4894-4900'	4/24			

## CHRONOLOGICAL OPERATIONS

Date Work Performed: Sept. 19, 2005SITP: \_\_\_\_\_ SICP: 1020

Day2c.

RU WLT. RIH w/ frac & 6' perf gun. Set plug @ 4720'. Perforate D2 sds @ 4672-4678' w/ 4 spf for total of 28 shot. RU BJ & perfs won't break down. RIH & spot 10 gals of 15% HCL acid on perfs. RU BJ & frac stage #3 w/ 30,644#'s of 20/40 sand in 323 bbls of Lightning 17 frac fluid. Open well w/ 1020 psi on casing. Perfs broke down @ 4255 psi, back to 2000 psi. Treated @ ave pressure of 1910 w/ ave rate of 25.1 bpm w/ up to 8 ppg of sand. Spot 5 bbls of 15% HCL in flush for next stage. ISIP was 2030. 1358 bbls EWTR. Leave pressure on well. **See day2d.**

## FLUID RECOVERY (BBLs)

Starting fluid load to be recovered: 1035

Starting oil rec to date: \_\_\_\_\_

Fluid lost/recovered today: 323

Oil lost/recovered today: \_\_\_\_\_

Ending fluid to be recovered: 1358

Cum oil recovered: \_\_\_\_\_

IFL: \_\_\_\_\_ FFL: \_\_\_\_\_ FTP: \_\_\_\_\_ Choke: \_\_\_\_\_ Final Fluid Rate: \_\_\_\_\_ Final oil cut: \_\_\_\_\_

## STIMULATION DETAIL

Base Fluid used: Lightning 17 Job Type: Sand fracCompany: BJ ServicesProcedure or Equipment detail: D2 sds down casing3192 gals of pad1875 gals w/ 1-5 ppg of 20/40 sand4047 gals w/ 5-8 ppg of 20/40 sand210 gals of 15% HCL acidFlush w/ 4662 gals of slick water**\*\*Flush called @ blender to include 2 bbls pump/line volume\*\***Max TP: 2125 Max Rate: 25.2 Total fluid pmpd: 323 bblsAvg TP: 1910 Avg Rate: 25.1 Total Prop pmpd: 30,644#'sISIP: 2030 5 min: \_\_\_\_\_ 10 min: \_\_\_\_\_ FG: .87Completion Supervisor: Ron Shuck

## COSTS

Weatherford BOP	\$70
Weatherford Services	\$2,200
Betts frac water	\$420
NPC fuel gas	\$84
BJ Services D2 sds	\$9,714
NPC Supervisor	\$85
BWWC D2 sds	\$4,490

DAILY COST: \$17,063TOTAL WELL COST: \$337,909





## DAILY COMPLETION REPORT

WELL NAME: Ashley Federal 14-13-9-15

Report Date: Sept. 20, 2005

Day: 2d

Operation: Completion

Rig: Rigless

## WELL STATUS

Surf Csg: 8 5/8 @ 314'  
Tbg: Size: Wt:Prod Csg: 5 1/2" @ 5977'  
Grd: Pkr/EOT @:Csg PBTD: 5874' WL  
BP/Sand PBTD: 4130'  
Plug 4800' 4720'

## PERFORATION RECORD

Zone	Perfs	SPF/#shots	Zone	Perfs	SPF/#shots
GB2 sds	4006-4024'	4/72			
D2 sds	4672-4678'	4/24			
C sds	4754-4762'	4/32			
B .5 sds	4828-4832'	4/16			
B2 sds	4894-4900'	4/24			

## CHRONOLOGICAL OPERATIONS

Date Work Performed: Sept. 19, 2005

SITP: SICP: 1460

Day 2d.

RU WLT. RIH w/ frac & 18' perf gun. Set plug @ 4130'. Perforate GB2 sds @ 4006-4024' w/ 4 spf for total of 72 shot. RU BJ & frac stage #4 w/ 84,673#'s of 20/40 sand in 583 bbls of Lightning 17 frac fluid. Open well w/ 1460 psi on casing. Perfs broke down @ 4340 psi, back to 1540 psi. Treated @ ave pressure of 1903 w/ ave rate of 25 bpm w/ 8 ppg of sand. ISIP was 2610. 1941 bbls EWTR. RD BJ & WLT. Flow well back. Well flowed for 5 hours & died w/ 330 bbls rec'd. SIFN.

## FLUID RECOVERY (BBLs)

Starting fluid load to be recovered: 1941

Starting oil rec to date:

Fluid lost/recovered today: 330

Oil lost/recovered today:

Ending fluid to be recovered: 1611

Cum oil recovered:

IFL: FFL: FTP: Choke: Final Fluid Rate: Final oil cut:

## STIMULATION DETAIL

Base Fluid used: Lightning 17 Job Type: Sand frac

Company: BJ Services

Procedure or Equipment detail: GB2 sds down casing

6006 gals of pad

4000 gals w/ 1-5 ppg of 20/40 sand

8000 gals w/ 5-8 ppg of 20/40 sand

2574 gals w/ 8 ppg of 20/40 sand

Flush w/ 3906 gals of slick water

## COSTS

Weatherford BOP	\$70
Weatherford Services	\$2,200
Betts frac water	\$1,110
NPC fuel gas	\$222
BJ Services GB2 sds	\$17,283
NPC Supervisor	\$85
BWWC GB2 sds	\$4,490
Betts water transfer	\$500

Max TP: 2100 Max Rate: 25.2 Total fluid pmpd: 583 bbls

Avg TP: 1903 Avg Rate: 25 Total Prop pmpd: 84,673#'s

ISIP: 2610 5 min: 10 min: FG: 1.08

Completion Supervisor: Ron Shuck

DAILY COST: \$25,960

TOTAL WELL COST: \$363,869



## DAILY COMPLETION REPORT

WELL NAME: Ashley Federal 14-13-9-15

Report Date: Sept. 23, 2005

Day: 03

Operation: Completion

Rig: NC #3

## WELL STATUS

Surf Csg: 8 5/8 @ 314' Prod Csg: 5 1/2" @ 5977' Csg PBTD: 5874' WL  
 Tbg: Size: 2 7/8 Wt: 6.5# Grd: J-55 Pkr/EOT @: 3983' BP/Sand PBTD: 4130'  
 Plug 4800' 4720'

## PERFORATION RECORD

Zone	Perfs	SPF/#shots	Zone	Perfs	SPF/#shots
GB2 sds	4006-4024'	4/72			
D2 sds	4672-4678'	4/24			
C sds	4754-4762'	4/32			
B .5 sds	4828-4832'	4/16			
B2 sds	4894-4900'	4/24			

## CHRONOLOGICAL OPERATIONS

Date Work Performed: Sept. 22, 2005

SITP: SICP: 100

MIRU NC #3. Bleed pressure off well. Rec est 25 BTF. ND Cameron BOP & 5M frac head. Install 3M production tbg head & NU Weatherford Schaeffer BOP. Talley, drift, PU & TIH W/ used Weatherford 4 3/4" "Chomp" bit, bit sub & new 2 7/8 8rd 6.5# J-55 tbg. Tag fill @ 4058'. Tbg displaced 10 BW on TIH. Pull EOT to 3983'. SIFN W/ est 1576 BWTR.

## FLUID RECOVERY (BBLs)

Starting fluid load to be recovered: 1611 Starting oil rec to date: \_\_\_\_\_  
 Fluid lost/recovered today: 35 Oil lost/recovered today: \_\_\_\_\_  
 Ending fluid to be recovered: 1576 Cum oil recovered: \_\_\_\_\_  
 IFL: \_\_\_\_\_ FFL: \_\_\_\_\_ FTP: \_\_\_\_\_ Choke: \_\_\_\_\_ Final Fluid Rate: \_\_\_\_\_ Final oil cut: \_\_\_\_\_

## STIMULATION DETAIL

Base Fluid used: Job Type: \_\_\_\_\_

Company: \_\_\_\_\_

Procedure or Equipment detail: \_\_\_\_\_

## COSTS

NC #3 rig	\$4,323
Weatherford BOP(X2)	\$280
NDSI trucking	\$1,200
NDSI wtr & truck	\$400
Unichem chemicals	\$300
NPC trucking	\$300
Aztec - new J55 tbg	\$28,797
NPC sfc equipment	\$120,000
R & T labor/welding	\$13,600
Monks pit reclaim	\$1,800
Mt. West sanitation	\$520
RNI wtr disposal	\$3,000
NPC supervision	\$300
<b>DAILY COST:</b>	<b>\$174,820</b>
<b>TOTAL WELL COST:</b>	<b>\$538,689</b>

Max TP: Max Rate: Total fluid pmpd: \_\_\_\_\_

Avg TP: Avg Rate: Total Prop pmpd: \_\_\_\_\_

ISIP: 5 min: 10 min: FG: \_\_\_\_\_

Completion Supervisor: Gary Dietz



## DAILY COMPLETION REPORT

WELL NAME: Ashley Federal 14-13-9-15

Report Date: Sept. 24, 2005

Day: 04

Operation: Completion

Rig: NC #3

## WELL STATUS

Surf Csg: 8 5/8 @ 314' Prod Csg: 5 1/2" @ 5977' Csg PBTD: 5931'  
 Tbg: Size: 2 7/8 Wt: 6.5# Grd: J-55 Pkr/EOT @: 5849' BP/Sand PBTD: 5931'

## PERFORATION RECORD

Zone	Perfs	SPF/#shots	Zone	Perfs	SPF/#shots
GB2 sds	4006-4024'	4/72			
D2 sds	4672-4678'	4/24			
C sds	4754-4762'	4/32			
B .5 sds	4828-4832'	4/16			
B2 sds	4894-4900'	4/24			

## CHRONOLOGICAL OPERATIONS

Date Work Performed: Sept. 23, 2005

SITP: 0 SICP: 0

TIH W/ bit & tbg f/ 3983'. Tag fill @ 4058'. RU power swivel. C/O sd & drill out composite bridge plugs as follows (using conventional circulation): sd @ 4058', plug @ 4130' in 35 minutes; sd @ 4700', plug @ 4720' in 37 minutes; no sd, plug @ 4800' in 32 minutes. Hang back swivel & con't PU tbg. Tag fill @ 5766'. PU swivel. Drill plug remains & sd to PBTD @ 5931'. Circ hole clean. Lost est 20 BW during cleanout. RD swivel. Pull EOT to 5849'. RU swab equipment. IFL @ sfc. Made 11 swab runs rec 169 BTF W/ light gas, tr oil & no sand. FFL @ 1100'. SIFN W/ est 1427 BWTR.

## FLUID RECOVERY (BBLs)

Starting fluid load to be recovered: 1576 Starting oil rec to date: \_\_\_\_\_  
 Fluid lost/recovered today: 149 Oil lost/recovered today: \_\_\_\_\_  
 Ending fluid to be recovered: 1427 Cum oil recovered: \_\_\_\_\_  
 IFL: sfc FFL: 1100' FTP: \_\_\_\_\_ Choke: \_\_\_\_\_ Final Fluid Rate: \_\_\_\_\_ Final oil cut: tr

## STIMULATION DETAIL

## COSTS

Base Fluid used: \_\_\_\_\_ Job Type: \_\_\_\_\_

Company: \_\_\_\_\_

Procedure or Equipment detail: \_\_\_\_\_

NC #3 rig	\$4,854
Weatherford BOP	\$140
Weatherford swivel	\$750
CDI TA	\$525
CDI SN	\$80
NPC trucking	\$300
NPC location cleanup	\$300
NPC supervision	\$300

Max TP: \_\_\_\_\_ Max Rate: \_\_\_\_\_ Total fluid pmpd: \_\_\_\_\_

Avg TP: \_\_\_\_\_ Avg Rate: \_\_\_\_\_ Total Prop pmpd: \_\_\_\_\_

ISIP: \_\_\_\_\_ 5 min: \_\_\_\_\_ 10 min: \_\_\_\_\_ FG: \_\_\_\_\_

Completion Supervisor: Gary Dietz

DAILY COST: \$7,249

TOTAL WELL COST: \$545,938



## DAILY COMPLETION REPORT

WELL NAME: Ashley Federal 14-13-9-15

Report Date: Sept. 25, 2005

Day: 05

Operation: Completion

Rig: NC #3

## WELL STATUS

Surf Csg: 8 5/8 @ 314' Prod Csg: 5 1/2" @ 5977' Csg PBTD: 5931'  
 Tbg: Size: 2 7/8 Wt: 6.5# Grd: J-55 Anchor @: 4870' BP/Sand PBTD: 5931'

## PERFORATION RECORD

Zone	Perfs	SPF/#shots	Zone	Perfs	SPF/#shots
GB2 sds	4006-4024'	4/72			
D2 sds	4672-4678'	4/24			
C sds	4754-4762'	4/32			
B .5 sds	4828-4832'	4/16			
B2 sds	4894-4900'	4/24			

## CHRONOLOGICAL OPERATIONS

Date Work Performed: Sept. 24, 2005

SITP: 25 SICP: 25

Bleed gas off well. RU swab equipment. IFL @ 600'. Made 2 swb runs rec 18 BTF (est 9 BW & 9 BO) W/ light gas & no sd. FOC @ 10%. FFL @ 1100'. TIH W/ tbg. Tag PBTD @ 5931' (no new fill). LD excess tbg. TOH W/ tbg--LD bit. TIH W/ BHA & production tbg as follows: 2 7/8 NC, 2 jts tbg, SN, 1 jt tbg, new CDI 5 1/2" TA (45K) & 156 jts 2 7/8 8rd 6.5# J-55 tbg. ND BOP. Set TA @ 4870' W/ SN @ 4904' & EOT @ 4968'. Land tbg W/ 15,000# tension. NU wellhead. PU & TIH W/ pump and "A" grade rod string as follows: new CDI 2 1/2" X 1 1/2" X 14.5' RHAC pump, 6-1 1/2" weight rods, 10-3/4" scraped rods, 80-3/4" plain rods, 99-3/4" scraped rods, 1-8', 1-6', 1-4' & 1-2' X 3/4" pony rods and 1 1/2" X 22' polished rod. Seat pump & RU pumping unit. Fill tbg W/ 1 BW. Pressure test tbg & pump to 200 psi. Stroke pump up W/ unit to 800 psi. Good pump action. RDMOSU. Est 1419 BWTR.

Place well on production @ 3:30 PM 9/24/2005 W/ 86" SL @ 5 SPM.

FINAL REPORT!!

## FLUID RECOVERY (BBLs)

Starting fluid load to be recovered: 1427 Starting oil rec to date: 5  
 Fluid lost/recovered today: 8 Oil lost/recovered today: 9  
 Ending fluid to be recovered: 1419 Cum oil recovered: 13  
 IFL: 600' FFL: 1100' FTP: Choke: Final Fluid Rate: Final oil cut: 10%

## TUBING DETAIL

## ROD DETAIL

## COSTS

TUBING DETAIL	ROD DETAIL	COSTS
KB 12.00'	1 1/2" X 22' polished rod	NC #3 rig \$3,562
156 2 7/8 J-55 tbg (4858.15')	1-8', 1-6', 1-4', 1-2' X 3/4" ponies	Weatherford BOP \$140
TA (2.80' @ 4870.15' KB)	99-3/4" scraped rods	CDI rod pump \$1,325
1 2 7/8 J-55 tbg (31.05')	80-3/4" plain rods	"A" grade rod string \$10,611
SN (1.10' @ 4904.00' KB)	10-3/4" scraped rods	Zubiate HO trk \$582
2 2 7/8 J-55 tbg (62.38')	6-1 1/2" weight rods	NPC frac tks(5X5 dys) \$1,000
2 7/8 NC (.45')	CDI 2 1/2" X 1 1/2" X 14.5'	NPC swab tk (3 days) \$120
EOT 4967.93' W/ 12' KB	RHAC pump W/ SM plunger	NPC frac head \$500
		NPC supervision \$300

DAILY COST: \$18,140

TOTAL WELL COST: \$564,078

Completion supervisor: Gary Dietz

## **ATTACHMENT H**

### **WORK PROCEDURE FOR PLUGGING AND ABANDONMENT**

1. Set CIBP @ 3956'
2. Plug #1 Set 100' plug on top of CIBP using 12 sx Class "G" cement
3. Plug #2 196' balance plug using 23 sx Class "G" cement 50' above Trona-Bird's Nest extending 50' below base of Mahogany Oil Shale
4. Plug #3 120' balance plug using 14 sx Class "G" cement 60' above Uinta/Green River and extending 60' below
5. Plug #4 Pump 42 sx Class "G" cement down 5 ½" casing to 364'

The approximate cost to plug and abandon this well is \$42,000.

## Ashley Federal 14-13-9-15

Spud Date: 7/27/05  
Put on Production: 9/24/05  
GL: 6158' KB: 6170'

Initial Production: 46 BOPD,  
32 MCFD, 92 BWPD

### Proposed P & A Wellbore Diagram

#### SURFACE CASING

CSG SIZE: 8 5/8"

GRADE: J-55

WEIGHT: 24#

LENGTH: 7 jts (304 2')

DEPTH LANDED: 314 2' KB

HOLE SIZE: 12 1/4"

CEMENT DATA: 160 sks Class G Mix. Est 4 bbls cement to pit

#### PRODUCTION CASING

CSG SIZE: 5 1/2"

GRADE: J-55

WEIGHT: 15 5#


LENGTH: 136 jts (5978 71')

DEPTH LANDED: 5976 71' KB

HOLE SIZE: 7 7/8"

CEMENT DATA: 300 sks Prem. Lite II mixed & 450 sks 50/50 POZ mix.

CEMENT TOP AT: 91'



**NEWFIELD**

Ashley Federal 14-13-9-15

758' FSL & 2020' FWL

SE/SW Section 13-T9S-R15E

Duchesne Co, Utah

API #43-013-32669; Lease #UTU-68548

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

**SUNDRY NOTICES AND REPORTS ON WELLS**  
**Do not use this form for proposals to drill or to re-enter an  
abandoned well. Use Form 3160-3 (APD) for such proposals.**

FORM APPROVED  
OMB No. 1004-0137  
Expires: July 31, 2010

**SUBMIT IN TRIPLICATE - Other Instructions on page 2**

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

NEWFIELD PRODUCTION COMPANY

3a. Address Route 3 Box 3630

Myton, UT 84052

3b. Phone (include area code)

435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

758 FSL 2020 FWL

SESW Section 13 T9S R15E

5. Lease Serial No.

USA UTU-68548

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or

GMBU

8. Well Name and No.

ASHLEY FEDERAL 14-13-9-15

9. API Well No.

4301332669

10. Field and Pool, or Exploratory Area

GREATER MB UNIT

11. County or Parish, State

DUCHESNE, UT

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug & Abandon	<input type="checkbox"/> Temporarily Abandon	_____
	<input checked="" type="checkbox"/> Convert to Injector	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	_____

13. Describe Proposed or Completed Operation: (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Newfield Production proposes to convert the above mentioned well from producing oil well to an injection well.

I hereby certify that the foregoing is true and correct (Printed/ Typed)

Jill Loyle

Signature

Title

Regulatory Technician

Date

2/9/2011

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on page 2)